
Quick Reference Guide to MS4 Bulletin #1

7 Simple Steps to ESC/SWM Compliance for construction projects at Fort Belvoir

1. Identify Project Size and Determine Required Plans and Review Authority (MS4 Bulletin #1 Section C.1)

Project Size	Plans Required	Review Authority
Less than 2,499 sq.ft.	None	DPW-Environmental Division
Between 2,500 sq.ft. and 9,999 sq.ft.	ESC & SWM	DPW-Environmental Division
Between 10,000 sq.ft. and 43,559 sq.ft.	ESC & SWM	VADEQ (for ESC portion only)
Greater than or equal to one (1) acre	ESC & SWM	VADEQ (for ESC & SWM)

2. Determine if you need a Construction General Permit (CGP) (MS4 Bulletin #1 Section C.2)



3. Review Requirements for Specific Plans and Prepare the Required Plans (MS4 Bulletin #1 Section C.3)

Stormwater Management Plan Quick Reference Checklist		Erosion and Sediment Control Plan Quick Reference Checklist	
	☐ If land disturbance is over 5,000 sf. Compliance with Section 438 of the Energy Independence and Security Act (EISA 438).		Comply with the 19 Virginia Minimum Standards (9VAC25-840-40).
	☐ Incorporate Low Impact Development Best Management Practices		Utilize erosion and sediment control standards and
	■ Address all components outlined in 9VAC25-870-55		specifications listed in Chapter 3 of the Virginia
	■ Utilize stormwater management BMPs from the Virginia BMP		Erosion and Sediment Control Handbook (VESCH).
	Clearinghouse		Nomenclature for erosion and sediment control
	☐ Use the Virginia Runoff Reduction Method (VRRM) Spreadsheet		measures shall be consistent with the VESCH and
	■ Each stormwater outfall location on the project site must be evaluated for		must follow the Virginia Uniform Coding System.
	Channel Protection and Flood Protection to the defined Limits of Analysis.		Comply with Chapter 11 of the Fairfax County Public
	☐ Comply with Chapter 6 of the Fairfax County Public Facilities Manual		Facilities Manual (PFM)
	(PFM)		VADEQ ESC Plan Review Checklist completed by
	□ Completed VADEQ SWM Plan Review Checklist		the designer and provided with plan submittal
1	☐ Plans appropriately sealed and signed by appropriate professional		·

4. Submit Plans for Review and Approval (MS4 Bulletin #1 Section C.4)

All Projects:

- 1. Submit one (1) hard copy and one (1) CD of the required plan(s) and supporting documentation to the DPW-ENV
- 2. Address comments made by DPW-ENV and resubmit plans as needed

Projects Requiring DPW Plan Approval Only < 10,000 square feet of Land Disturbance

Projects Requiring DPW and VADEQ Approval >10,000 square feet of Land Disturbance

Once the plans are determined to be adequate submit the following to the DPW-Environmental Division Stormwater POC:

- four (4) hard copies of the plans for signature by the Director of Public Works.
- one (1) CD that contains signed plans and any supporting documentation (calculations), if applicable.

- 1. Submit all documents to VADEQ for Approval
- 2. Submit copies of **ALL** documents submitted to VADEQ to DPW-ENV
- 3. Address any comments received by VADEQ and resubmit as needed
- 4. Ensure to provide copies of all re-submittals to DPW-ENV

Projects > 1 Acre of Land Disturbance will also need to:

- 5. Submit Registration Statement for CGP to VADEQ
- 6. Prepare and submit Stormwater Pollution Prevention Plan to DPW-ENV

5. Submit final documentation to receive a DPW Land Disturbance Letter (LDL) (MS4 Bulletin #1 Section C.5)



1. Provide contractor POC responsible for insuring that SWM and/or ESC plans are executed. This POC should be a VADEQ certified Responsible Land Disturber (RLD). Provide RLD Certificate.

Construction may begin ONLY

after receiving the

Land Disturbance Letter (LDL)


- 2. Submit and/or ensure DPW-ENV has received the following:

 - VADEQ CGP Approval Letter (for sites >1 acre)
 - SWPPP (for sites >1 acre)
 - RLD Certificate
 - Excavation Permit (DIG Permit)
 - Four (4) hard copies of the VADEQ Approved Plans
 - One (1) CD containing all the above documents
- 3. Submit a Fort Belvoir Excavation Permit Application
- 4. Schedule the Pre-Construction Meeting
- 5. Receive LDL from DPW-ENV
- 6. Notify construction start day to DPW-Environmental Stormwater POC

6. Follow ESC/SWM Compliance during Construction (MS4 Bulletin #1 Section C.6)

- 1 Conduct Internal ESC/SWM Inspection and Maintenance
- 2 Assist, respond and address compliance issues in DPW Inspection Reports

7. Follow ESC/SWM Compliance upon Construction Completion (MS4 Bulletin #1 Section C.7)



Reminder CGP cant be close out until site has reached final permanent stabilization: "uniform, mature enough to survive and inhibit erosion".

Please refer to MS4 Bulletin #1 for more details. Most up to date Version can be found here: https://home.army.mil/belvoir/index.php/about/Garrison/directorate-public-works/environmental-division