

FINAL

**CORRECTIVE ACTION PLAN - PART A REPORT
FOR
UNDERGROUND STORAGE TANK 28B
FACILITY ID #9-089011
BUILDING 1720
FORT STEWART, GEORGIA**

Prepared for:

**U.S. Army Corps of Engineers - Savannah District
and
Fort Stewart Directorate of Public Works
Under Contract Number DACA21-95-D-0022
Delivery Order 0024**

Prepared by:

**Science Applications International Corporation
800 Oak Ridge Turnpike
Oak Ridge, Tennessee 37830**

August 1999

TABLE OF CONTENTS

	<u>Page</u>
LIST OF ABBREVIATIONS AND ACRONYMS	v
I. PLAN CERTIFICATION	1
A. UST Owner/Operator Certification	1
B. Registered Professional Engineer or Professional Geologist Certification	1
II. INITIAL RESPONSE REPORT	2
A. Initial Abatement	2
B. Free Product Removal	2
C. Tank History	3
D. Initial Site Characterization	3
1. Regulated Substance Released	3
2. Source(s) of Contamination	3
3. Local Water Resources	4
a. Groundwater Pollution Susceptibility Area	4
b. Public and Non-Public Water Supplies	4
c. Surface Water Supplies and Sewers	4
4. Impacted Environmental Media	4
a. Soil Impacted	4
b. Groundwater Impacted	5
c. Surface Water Impacted	6
d. Point of Withdrawal Impacted	6
5. Other Geologic/Hydrogeologic Data	6
a. Depth to Groundwater	6
b. Groundwater Flow Direction	6
c. Hydraulic Gradient	6
d. Geophysical Province	6
e. Unique Geologic/Hydrogeological Conditions	6
6. Corrective Action Completed or In-Progress	6
a. Underground Storage Tank System Closure	6
b. Excavation and Treatment/Disposal of Backfill Materials and Native Soils	7
7. Site Ranking	7
8. Conclusions and Recommendations	7
a. No Further Action Required	7
b. Monitoring Only	7
c. CAP-B	7
III. MONITORING ONLY PLAN	8
A. Monitoring Points	8
B. Period/Frequency of Monitoring and Reporting	8
C. Monitoring Parameters	8
D. Milestone Schedule	8
E. Scenarios for Site Closure or CAP-Part B	8

IV. SITE INVESTIGATION PLAN	8
A. Proposed Investigation of Horizontal and Vertical Extent of Contamination	8
1. Soil	8
2. Groundwater.....	9
a. Free Product	9
b. Dissolved Phase	9
3. Surface Water.....	9
B. Proposed Investigation of Vadose Zone and Aquifer Characteristics.....	9
V. PUBLIC NOTICE	10
VI. CLAIM FOR REIMBURSEMENT	10

List of Appendices

APPENDIX I: REPORT FIGURES.....	I-1
Figure 1. Location Map of UST 28B, Fort Stewart, Liberty County, Georgia.....	I-3
Figure 2. Site Plan for the UST 28B Site Investigation	I-4
Figure 3. Map Showing Public and Private Drinking Water Sources and Surface Water Bodies at Fort Stewart, Liberty County, Georgia.....	I-5
Figure 4. Soil Quality Map of the UST 28B Site.....	I-7
Figure 5. Groundwater Quality Map of the UST 28B Site	I-9
Figure 6. Potentiometric Surface Map of the UST 28B Site	I-11
Figure 7. UST System Closure Sampling Locations at the UST 28B Site.....	I-12
Figure 8. Proposed Additional Boring/Monitoring Well Locations	I-13
Figure 9. Tax Map.....	I-14
APPENDIX II: REPORT TABLES	II-1
Table 1. Free Product Removal	II-3
Table 2a. Soil Analytical Results (Volatile Organic Compounds)	II-4
Table 2b. Soil Analytical Results (Polynuclear Aromatic Hydrocarbons).....	II-5
Table 3a. Groundwater Analytical Results (Volatile Organic Compounds).....	II-6
Table 3b. Groundwater Analytical Results (Polynuclear Aromatic Hydrocarbons)	II-7
Table 4. Groundwater Elevations	II-8
Table 5a. UST System Closure - Soil Analytical Results (Volatile Organic Compounds)	II-9
Table 5b. UST System Closure - Soil Analytical Results (Polynuclear Aromatic Hydrocarbons)	II-9
Table 6a. UST System Closure - Groundwater Analytical Results (Volatile Organic Compounds).....	II-10
Table 6b. UST System Closure - Groundwater Analytical Results (Polynuclear Aromatic Hydrocarbons)	II-10

APPENDIX III:	WATER RESOURCES SURVEY DOCUMENTATION	III-1
APPENDIX IV:	SOIL BORING LOGS	IV-1
APPENDIX V:	SOIL LABORATORY RESULTS.....	V-1
APPENDIX VI:	ALTERNATE THRESHOLD LEVEL (ATL) CALCULATIONS	VI-1
APPENDIX VII:	MONITORING WELL DETAILS.....	VII-1
APPENDIX VIII:	GROUNDWATER LABORATORY RESULTS	VIII-1
APPENDIX IX:	CONTAMINATED SOIL DISPOSAL MANIFESTS.....	IX-1
APPENDIX X:	SITE RANKING FORM.....	X-1
APPENDIX XI:	COPIES OF PUBLIC NOTIFICATION LETTERS AND CERTIFIED RECEIPTS OF NEWSPAPER NOTICE	XI-1
APPENDIX XII:	GUST TRUST FUND REIMBURSEMENT APPLICATION AND CLAIM FOR REIMBURSEMENT	XII-1

Attachments

A	TECHNICAL APPROACH.....	A-1
B	REFERENCES	B-1
C	SUPPLEMENTAL INFORMATION – RISK BASED CORRECTIVE ACTION	C-1

List of Abbreviations and Acronyms

ACE	Anderson Columbia Environmental, Inc.
ACL	alternate concentration limits
AMSL	above mean sea level
ARAR	applicable, relevant, and appropriate requirement
ASTM	American Society for Testing and Materials
ATL	alternate threshold level
BGS	below ground surface
BTEX	benzene, toluene, ethylbenzene, and xylene
BTOC	below top of casing
CAP	Corrective Action Plan
COCs	chemicals of concern
DAF	dilution-attenuation factor
DPW	Directorate of Public Works
DRO	diesel-range organics
EPA	U.S. Environmental Protection Agency

GA EPD	Georgia Environmental Protection Division
GRO	gasoline-range organics
HQ	hazard quotient
ID	inside diameter
IDW	investigation-derived waste
MCL	maximum contaminant level
MSL	mean sea level
ND	not detected
NRC	no regulatory criteria
OVA	organic vapor analyzer
OVM	organic vapor meter
PAH	polynuclear aromatic hydrocarbon
PVC	polyvinyl chloride
SAIC	Science Applications International Corporation
TPH	total petroleum hydrocarbon
USACE	U.S. Army Corps of Engineers
UST	underground storage tank
USTMP	Underground Storage Tank Management Program

CORRECTIVE ACTION PLAN PART A

Facility Name: UST 28B, Building 1720 Street Address: Divarty Road and McFarland Avenue

Facility ID: 9-089011 City: Fort Stewart County: Liberty Zip Code: 31314

Latitude: 31° 51' 24" Longitude: 82° 16' 38"

Submitted by UST Owner/Operator:

Name: Thomas C. Fry/ Environmental Branch

Company: U.S. Army/HQ 3d, Inf. Div (Mech)

Address: DPW ENRD ENV. Br. (Fry)

1557 Frank Cochran Drive

City: Fort Stewart State: GA

Zip Code: 31314-4928

Telephone: (912) 767-2010

Prepared by Consultant/Contractor:

Name: Patricia A. Stoll

Company: SAIC

Address: P.O. Box 2502

City: Oak Ridge State: TN

Zip Code: 37831

Telephone: (423) 481-8792

I. PLAN CERTIFICATION:

A. UST Owner/Operator Certification

I hereby certify that the information contained in this plan and in all the attachments is true, accurate, and the plan satisfies all criteria and requirements of rule 391-3-15-09 of the Georgia Rules for Underground Storage Tank Management.

Name: Thomas C. Fry

Signature: Thomas C. Fry Date: 09/07/99


B. Registered Professional Engineer or Professional Geologist Certification

I hereby certify that I have directed and supervised the field work and preparation of this plan, in accordance with State Rules and Regulations. As a registered professional geologist and/or professional engineer, I certify that I am a qualified groundwater professional, as defined by the Georgia State Board of Professional Geologists. All of the information and laboratory data in this plan and in all of the attachments are true, accurate, complete, and in accordance with applicable State Rules and Regulations.

Name: Patricia A. Stoll

Signature: Patricia A. Stoll

Date: 8/20/99



General: READ THE GUIDANCE DOCUMENT FOR CAP PART-A BEFORE COMPLETING THIS FORM. FAILURE TO READ THE GUIDANCE DOCUMENT WILL MOST LIKELY RESULT IN PREPARATION OF AN UNACCEPTABLE REPORT. All text, figures, and tables requested in their respective sections should be prepared strictly in accordance with the Georgia EPD CAP-A guidance document. Please fill out this form as provided. Do not change the size of the fields or alter the placement of each section on each page.

(Appendix I: All Report Figures)

(Appendix II: All Report Tables)

II. INITIAL RESPONSE REPORT

A. Initial Abatement

Were initial abatement actions initiated?

YES _____ NO X

If Yes, please summarize. If No, please explain why not.

Actions were not required to abate imminent hazards and/or emergency conditions at the UST 28B site. Therefore, contaminant migration and release prevention, fire and vapor migration, or emergency free product removal was not performed prior to, or during, the removal of UST 28B.

B. Free Product Removal

(Table 1: Summary of Free Product Removal – must include Free Product thickness in each well in which it was detected, and volume of product removed)

Free Product Detected?

YES _____ NO X

If Yes, please summarize free product recovery efforts.

Continuing free product recovery proposed?

YES _____ NO X

If yes, please indicate the method and frequency of removal.

C. Tank History

List current and former UST's operated at site based on owner/operator knowledge consistent with EPA 7530-1 Form). Systems must be illustrated on Figure 2 (Site Plan), as described in section D below.

CURRENT UST SYSTEMS (if applicable)

<u>Tank ID Number</u>	<u>Capacity (gal)</u>	<u>Substance</u> <u>Stored</u>	<u>Age (yrs)</u>	<u>Meets 1998 Upgrade</u> <u>Standards (Yes/No)</u>
N/A	N/A	N/A	N/A	N/A

FORMER UST SYSTEMS (if applicable)

<u>Tank ID Number</u>	<u>Capacity (gal)</u>	<u>Substance Stored</u>	<u>Date Removed</u>
28B	2,000	used oil	7/2/96

D. Initial Site Characterization

(Figure 1: Vicinity/Location Map)

(Figure 2: Site Plan)

1. Regulated Substance Released (gasoline, diesel, used oil, etc.): used oil
Discuss how this determination was made and circumstances of discovery.

Anderson Columbia Environmental, Inc. (ACE) initiated characterization of petroleum-related contamination at the site during UST system closure activities on July 2, 1996. After removing the tank, two soil samples were collected from the tank pit (Figure 7). BTEX compounds were not detected in these two samples; however, the detection limits were 0.116 mg/kg and 0.106 mg/kg in the two samples, 28B-T1-A1 and 28B-T1-S2, respectively. TPH was detected at concentrations of 14600 mg/kg and 13200 mg/kg in samples 28B-T1-S1 and 28B-T1-S2, respectively. No groundwater samples were collected during the tank removal activities.

2. Source(s) of Contamination: unknown; piping leakage or tank overflow suspected
Discuss how this determination was made.

A detailed schematic diagram illustrating the former UST 28B and ancillary piping as configured during operation is presented in Figure 2. During removal activities by ACE, no holes in the tank were reported. Therefore, the source of contamination is believed to have been piping leakage and/or tank overflow.

3. Local Water Resources

(Figure 3: Quadrangle Map – Public and Private drinking water and surface water)

(Appendix III: Water resources survey documentation, including, but not limited to: USGS database search, interview forms, and documentation of field survey)

a. Site located in high/average X OR low groundwater pollution susceptibility area?

b. Water Supplies within applicable radii? YES X NO

If yes,

i. Nearest public water supply located within: 1200 feet

ii. Nearest down-gradient public water supply located within: 5200 feet

iii. Nearest non-public water supply located within: >10,560 feet

iv. Nearest down-gradient non-public water supply located within: >10,560 feet

c. Surface Water Bodies and sewers:

i. Nearest surface water located within 2000 feet

ii. Nearest down-gradient surface water located within 3000 feet

iii. Nearest storm or sanitary sewer located within: 125 feet

iv. Depth to bottom of sewer at a point nearest the plume 3.2 feet

4. Impacted Environmental Media

a. Soil Impacted

(Table 2: Soil Analysis Results)

(Figure 4: Soil Quality Map)

(Appendix IV: Soil Boring Logs)

(Appendix V: Soil Laboratory Reports)

(Appendix VI: ATL Calculations, if applicable)

Provide a brief discussion of soil sampling.

Continuous soil cores were collected at 1.5- or 2.0-foot intervals during the installation of six boreholes. Field headspace gas analyses were performed on each sample to determine the organic vapor concentration. Two soil samples were selected from each borehole for laboratory chemical analysis of BTEX, TPH, and PAH. In boreholes where organic vapors were detected, one sample was collected from the sample interval where the highest vapor concentration was recorded, and the other from the deepest sample interval with the lowest concentration. If organic vapors were not detected, one sample was collected from the sample interval nearest the midpoint of the boring, and the other from the sample interval located immediately above the water table. Refer to Attachment A for complete documentation of the technical approach implemented during this investigation.

i. *Soil contamination above applicable threshold levels?*

YES X NO

If yes, indicate highest concentrations in soil along with locations and depths detected.

The benzene detection limits in the two closure soil samples were 0.116 mg/kg and 0.106 mg/kg. The exact location and depth of the closure samples collected in 1996 are unknown. The two samples also contained elevated TPH concentrations that may have contributed to the elevated benzene detection limits. CAP-Part A investigation soil samples did not contain contaminant concentrations above applicable soil threshold levels.

ii. *ATLs calculated?*

YES NO X

If yes, present ATLs.

iii. *If ATL's calculated, is soil contamination above ATL's?*

YES NO N/A X

b. *Groundwater Impacted*

(Table 3: Groundwater Analysis Results)

(Figure 5: Groundwater Quality Map)

(Appendix VII: Monitoring Well Details)

(Appendix VIII: Groundwater Laboratory Results)

Provide a brief discussion of groundwater sampling.

At each borehole location, except the vertical profile boring, one groundwater sample was collected from the temporary piezometer screened from ground surface to approximately 5.0 feet below the water table. At the vertical profile location (60-07), groundwater samples were collected every 5 feet below the water table until several groundwater sample intervals indicated a headspace gas measurement of zero. Chemical parameters for groundwater samples submitted for laboratory analysis included BTEX and PAH. Refer to Attachment A for complete documentation of the technical approach used to collect groundwater samples.

i. *Groundwater contamination above MCLs?*

YES X NO

ii. *Groundwater contamination above In-Stream Water Quality Standards?*

YES X NO

If yes, indicate highest concentrations in groundwater along with the locations.

In May 1998, benzene was present in borings 60-01 and 60-02 at concentrations of 128 µg/L and 171 µg/L, respectively. Both of these borings were located within the former tank pit.

In September 1998, the investigation was extended to include additional sampling in an effort to determine extent. BTEX was not present in the four additional shallow borings or vertical profile boring that were installed in September 1998. Refer to Attachment C for supplemental information on risk screening and fate and transport modeling.

c. *Surface Water Impacted?* YES _____ NO X
If Yes, indicate concentration(s) of surface water sample(s) taken from the surface water body/bodies impacted.

d. *Point of Withdrawal Impacted?* YES _____ NO _____ N/A X
If Yes, indicate concentration(s) of water sample(s) taken from withdrawal point(s).

5. Other Geologic/Hydrogeologic Data

- a. *Depth to Groundwater (ft BTOC):* 5.11 – 9.92 (Table 4: Groundwater Elevations)
b. *Groundwater Flow Direction:* southeast (Figure 6: Potentiometric Surface Map)
c. *Hydraulic Gradient* 0.0125 ft/ft
d. *Geophysical Province:* coastal plain
e. *Unique geologic/hydrological conditions:* The Hawthorn Formation acts as a confining unit between the surficial and Floridan aquifers.

6. Corrective Action Completed or In-Progress (if applicable)

(Table 5: UST System Closure Sampling)

(Figure 7: UST System Closure Sampling)

(Appendix IX: Contaminated Soil Disposal Manifests)

- a. *Underground Storage Tank (UST) System Closure:* N/A _____
If applicable, summarize UST system closure activities conducted.

ACE removed UST 28B on July 2, 1996. The UST piping was drained into the tank, and all used oil was subsequently removed using a vacuum truck and/or compressor-driven barrel vacuum device. A backhoe was used to excavate down to the tank top. All lines were capped except the fill and vent. After the tank atmosphere was tested with a combustible gas indicator, all accessible tank openings were capped and the tanks were lifted from the excavation pit. The ancillary piping was closed in-place due to the fact that it was covered with 12 inches of high strength concrete. In-place closure consisted of purging the line and grouting the end at the tank and the end at Building 1720.

b. Excavation and Treatment/Disposal of Backfill Materials and Native Soils

Check one: *No UST removal performed*

Returned to UST excavation

Excavated soils treated or disposal off site

X

If soils were excavated, summarize excavation and treatment/disposal activities:

All contaminated soil removed during the entire project (i.e., all USTs removed under contract with ACE, to include clean and non-clean closures) was tested in accordance with the disposal facility requirements and transported to Kedesh, Inc., Highway 84, Ludowici, GA, 31316. The Closure Report was not submitted to GA EPD in 1996 because review of the closure analytical data indicated that a CAP-Part A would be required (i.e., per requirements of GUST-9, Item 15, page 12, dated August 1995). However, all pertinent information (i.e., copies of analytical data, manifests, and maps) are provided in this CAP-Part A report. Disposal manifests for the UST 28B site were submitted to GA EPD USTMP in September 1998 with the UST 207A (Facility ID #9-089039) Closure Report response to comments correspondence (Perez 1998). Approximately 23.52 tons of contaminated soil was excavated from the site.

7. Site Ranking:

Environmental Site Sensitivity Score: 2850

(Appendix X: Site Ranking Form)

8. Conclusions and Recommendations

Complete applicable section below, one section only

- a. No Further Action Required (if applicable)
(provide justification)

N/A X

- b. Monitoring Only (if applicable)
(provide justification)

N/A

There was no soil contamination in excess of applicable GUST soil threshold levels (i.e., Table A, Column 2) during the CAP-Part A investigation. However, the benzene detection limits in the closure soil samples exceeded the applicable soil threshold level. Benzene was detected in two groundwater samples with the highest concentration being 171 ug/L. Fate and transport modeling results indicate that benzene concentrations in excess of the 5 µg/L MCL may extend up to 40 feet from the former tank pit. These results have been confirmed by CAP-Part A sampling results. In addition, benzene will not reach the drainage ditch located 250 feet southeast of the site at detectable concentrations. The horizontal and vertical extent of contamination was determined during the CAP-Part A.

- c. CAP-B (if applicable)
(provide justification)

N/A X

III. MONITORING ONLY PLAN (if applicable):

N/A _____

A. Monitoring points

Three shallow monitoring wells will be installed as part of the long-term monitoring as shown in Figure 8. The shallow wells will be screened across the water table with 3 to 5 feet of screen above the water table in order to detect the presence of free product. All monitoring wells will be completed flush with the ground surface. Boring logs and well construction diagrams will be provided in the first annual monitoring only report.

B. Period/Frequency of monitoring and reporting

Groundwater monitoring will be completed on a semiannual basis and the results will be summarized in an annual monitoring only report submitted to GA EPD. Monitoring will continue for a period of up to two years, for a total of up to four sampling events.

C. Monitoring Parameters

One groundwater sample will be collected from each of the three monitoring wells and analyzed for BTEX. No PAH compounds were detected in groundwater during the CAP-Part A investigation, thus PAH analysis will not be performed during the semiannual monitoring.

D. Milestone Schedule

Monitoring well installation will be conducted pending the availability of FY2000 funding. A milestone schedule will be provided to GA EPD upon availability of funds and approval of the monitoring only plan.

E. Scenarios for site closure or CAP-Part B

The monitoring system will be evaluated annually. A recommendation for no further action required will be made if benzene concentrations remain below the predicted two-year maximum concentrations.

IV. SITE INVESTIGATION PLAN (if applicable):

N/A X

(Figure 8: Proposed additional boring/monitoring well location)

A. Proposed Investigation of Horizontal and Vertical Extent of Contamination In:

1. Soil

N/A X

2. Groundwater

a. Free Product

N/A X

b. Dissolved phase

N/A X

3. Surface Water

N/A X

B. Proposed Investigation of Vadose Zone And Aquifer Characteristics:

Additional vadose zone and aquifer characteristics were collected as part of the CAP-Part A investigation, thus no additional data is required.

V. PUBLIC NOTICE

(Figure 9, Tax Map)

(Appendix XI: Copies of public notification letters & certified return receipts or newspaper notice if approved)

UST 28B is located within the confines of Fort Stewart Military Reservation, a federal facility. The U.S. Government owns all of the property contiguous to the site. The Fort Stewart Directorate of Public Works (DPW) has complied with the public notice requirements defined by Georgia Environmental Protection Division (GA EPD) guidance by publishing an announcement in the *Savannah Morning News* on June 27 and July 4, 1999.

VI. CLAIM FOR REIMBURSEMENT (for GUST Trust Fund sites only):

N/A X

(Appendix XII: GUST Trust Fund Reimbursement Application and Claim for reimbursement)

Fort Stewart is a federally owned facility and has funded the investigation for UST 28B, Building 1720, Facility ID #9-089011, using Department of Defense Environmental Restoration Account Funds. Application for Georgia Underground Storage Tank Trust Fund reimbursement is not being pursued at this time.

APPENDIX I

REPORT FIGURES

THIS PAGE INTENTIONALLY LEFT BLANK




Figure 1. Location Map of UST 28B, Fort Stewart, Liberty County, Georgia




Figure 2. Site Plan for the UST 28B Site Investigation




Figure 3. Map Showing Public and Private Drinking Water Bodies at Fort Stewart, Liberty County

THIS PAGE INTENTIONALLY LEFT BLANK




Figure 4. Soil Quality

THIS PAGE INTENTIONALLY LEFT BLANK




Figure 5. Groundwater Qua

THIS PAGE INTENTIONALLY LEFT BLANK




Figure 6. Potentiometric Surface Map of the UST 28B Site




Figure 7. UST System Closure Sampling Locations at the UST 28B Site




Figure 8. Proposed Additional Boring/Monitoring Well Locations

**No tax map is available for Fort Stewart Military Reservation,
which is a government owned facility.**

Figure 9. Tax Map

APPENDIX II

REPORT TABLES

THIS PAGE INTENTIONALLY LEFT BLANK

TABLE 1: FREE PRODUCT REMOVAL

Monitoring Well Number: N/A				
Date of Measurement	Groundwater Elev. (ft AMSL)	Product Thickness (ft)	Corrected Water Elev. (ft AMSL)	Product Removed (gal)
No Free Product Detected				
			TOTAL	NONE

Monitoring Well Number: N/A				
Date of Measurement	Groundwater Elev. (ft AMSL)	Product Thickness (ft)	Corrected Water Elev. (ft AMSL)	Product Removed (gal)
No Free Product Detected				
			TOTAL	NONE

NOTE:
AMSL Above mean sea level.

TABLE 2a: SOIL ANALYTICAL RESULTS
(VOLATILE ORGANIC COMPOUNDS)

Sample Location	Sample ID	Depth (ft BGS)	Date Sampled	Benzene (mg/kg)	Toluene (mg/kg)	Ethyl-benzene (mg/kg)	Xylenes (mg/kg)	Total BTEX (mg/kg)	TPH (mg/kg)
60-01	600111	0.5 - 2.0	5/10/98	0.00055 U	0.0523 =	0.0022 U	0.0066 U	0.0523	23.3 U
60-01	600121	4.0 - 6.0	5/10/98	0.00055 U	0.0152 =	0.0022 U	0.0066 U	0.0152	15.9 U
60-02	600221	0.2 - 2.0	5/10/98	0.0006 UJ	0.0342 J	0.0024 UJ	0.0071 UJ	ND	2420 =
60-03	600311	0.5 - 2.0	9/20/98	0.0022 U	0.0079 =	0.0022 U	0.0067 U	0.0079	10.8 UJ
60-03	600321	4.0 - 6.0	9/20/98	0.0022 U	0.0022 U	0.0022 U	0.0066 U	ND	13.6 J
60-04	600411	0.5 - 2.0	9/18/98	0.0021 U	0.0021 U	0.0021 U	0.0064 U	ND	2 UJ
60-04	600421	2.0 - 4.0	9/18/98	0.0021 U	0.0023 =	0.0021 U	0.0064 U	0.0023	23.9 J
60-05	600511	0.5 - 2.0	9/18/98	0.0022 U	0.004 =	0.0022 U	0.0067 U	0.004	27.8 J
60-05	600521	4.0 - 6.0	9/18/98	0.0023 U	0.0023 U	0.0023 U	0.0063 U	ND	7.02 UJ
60-06	600611	0.5 - 2.0	9/18/98	0.0021 U	0.0111 =	0.0021 U	0.0062 U	0.0111	2660 J
60-06	600621	4.0 - 6.0	9/18/98	0.0023 U	0.004 =	0.0023 U	0.0068 U	0.004	265 J
Applicable Standards ¹				0.008	6	10	700	NRC	NRC

NOTES:

May 1998 sampling was conducted prior to the new CAP-Part A guidance that was published in May 1998; thus, the new SW-846 analytical methods were not used during that sampling event.

Contract for September 1998 sampling was issued prior to the new CAP-Part A guidance that was published in May 1998, thus the new SW-846 analytical methods were not used during that sampling event.

¹ Georgia Department of Natural Resources Applicable Soil Threshold Levels (Table A, Column 2)

BGS Below ground surface

BTEX Benzene, toluene, ethylbenzene, and xylene

ND Not detected

NRC No regulatory criteria

TPH Total petroleum hydrocarbon

Laboratory Qualifiers

U Indicates that the compound was not detected above the reported sample quantitation limit.

UJ Indicates that the compound was not detected above an approximated sample quantitation limit.

J Indicates that the value for the compound was an estimated value.

R Indicates that the sample results are unusable and the presence or absence of the compound could not be verified.

= Indicates that the compound was detected at the concentration reported.

TABLE 2b: SOIL ANALYTICAL RESULTS
(POLYNUCLEAR AROMATIC HYDROCARBONS)

Sample Location	Sample ID	Depth (ft BGS)	Date Sampled	Detected PAH Compounds (mg/kg)						Total PAHs (mg/kg)
60-01	600111	0.5 - 2.0	5/10/98							ND
60-01	600121	4.0 - 6.0	5/10/98							ND
60-02	600221	0.2 - 2.0	5/10/98							ND
60-03	600311	0.5 - 2.0	9/20/98							ND
60-03	600321	4.0 - 6.0	9/20/98							ND
60-04	600411	0.5 - 2.0	9/18/98							ND
60-04	600421	2.0 - 4.0	9/18/98							ND
60-05	600511	0.5 - 2.0	9/18/98							ND
60-05	600521	4.0 - 6.0	9/18/98							ND
60-06	600611	0.5 - 2.0	9/18/98							ND
60-06	600621	4.0 - 6.0	9/18/98							ND
Applicable Standards ¹										NRC

NOTES:

May 1998 sampling was conducted prior to the new CAP-Part A guidance that was published in May 1998; thus, the new SW-846 analytical methods were not used during that sampling event.

Contract for September 1998 sampling was issued prior to the new CAP-Part A guidance that was published in May 1998, thus the new SW-846 analytical methods were not used during that sampling event.

¹ Georgia Department of Natural Resources Applicable Soil Threshold Levels (Table A, Column 2)

BGS Below ground surface

ND Not detected (refer to Appendix V, Table V-A, for complete list of PAH results)

NRC No regulatory criteria

PAH Polynuclear aromatic hydrocarbon

Laboratory Qualifiers

U Indicates that the compound was not detected above the reported sample quantitation limit.

UJ Indicates that the compound was not detected above an approximated sample quantitation limit.

J Indicates that the value for the compound was an estimated value.

= Indicates that the compound was detected at the concentration reported.

TABLE 3a: GROUNDWATER ANALYTICAL RESULTS
(VOLATILE ORGANIC COMPOUNDS)

Sample Location	Sample ID	Depth (ft BGS)	Date Sampled	Benzene (ug/L)	Toluene (ug/L)	Ethyl - benzene (ug/L)	Xylenes (ug/L)	Total BTEX (ug/L)
60-01	600112	2.0 - 12.0	5/10/98	128 =	424 =	50 U	88.8 J	690.8
60-02	600212	0.0 - 12.0	5/10/98	171 =	512 =	17.8 =	92 =	792.8
60-03	600312	0.1 - 10.1	9/18/98	2 U	2 U	2 U	6 U	ND
60-04	600412	0.0 - 10.0	9/18/98	2 U	2 U	2 U	6 U	ND
60-05	600512	0.0 - 9.5	9/18/98	2 U	2 U	2 U	6 U	ND
60-06	600612	0.0 - 10.0	9/18/98	2 U	2 U	2 U	6 U	ND
60-07	600712	6.0 - 10.0	9/20/98	2 U	2 U	2 U	6 U	ND
60-07	600722	11.0 - 15.0	9/20/98	2 U	2 U	2 U	6 U	ND
60-07	600732	16.0 - 20.0	9/20/98	2 U	2 U	2 U	6 U	ND
Applicable Standards ¹				5	700	1000	10000	NRC

NOTE:

May 1998 sampling was conducted prior to the new CAP-Part A guidance that was published in May 1998; thus, the new SW-846 analytical methods were not used during that sampling event.

Contract for September 1998 sampling was issued prior to the new CAP-Part A guidance that was published in May 1998, thus the new SW-846 analytical methods were not used during that sampling event.

¹ U.S. Environmental Protection Agency maximum contaminant level

BTEX Benzene, toluene, ethylbenzene, and xylene

BGS Below ground surface

ND Not detected

NRC No regulatory criteria

Laboratory Qualifiers

U Indicates the compound was not detected above the reported sample quantitation limit.

UJ Indicates that the compound was not detected above an approximated sample quantitation limit.

J Indicates the value for the compound is an estimated value.

= Indicates the compound was detected at the concentration reported.

TABLE 3b: GROUNDWATER ANALYTICAL RESULTS
(POLYNUCLEAR AROMATIC HYDROCARBONS)

Sample Location	Sample ID	Depth (ft BGS)	Date Sampled	Detected PAH Compounds (ug/L)				Total PAH (ug/L)
60-01	600112	2.0 - 12.0	5/10/98					ND
60-02	600212	0.0 - 12.0	5/10/98					ND
60-03	600312	0.1 - 10.1	9/18/98					ND
60-04	600412	0.0 - 10.0	9/18/98					ND
60-05	600512	0.0 - 9.5	9/18/98					ND
60-06	600612	0.0 - 10.0	9/18/98					ND
60-07	600712	6.0 - 10.0	9/20/98					ND
60-07	600722	11.0 - 15.0	9/20/98					ND
60-07	600732	16.0 - 20.0	9/20/98					ND
Applicable Standards ¹								NRC

NOTE:

May 1998 sampling was conducted prior to the new CAP-Part A guidance that was published in May 1998; thus, the new SW-846 analytical methods were not used during that sampling event.

Contract for September 1998 sampling was issued prior to the new CAP-Part A guidance that was published in May 1998, thus the new SW-846 analytical methods were not used during that sampling event.

¹ U.S. Environmental Protection Agency maximum contaminant level

BGS Below ground surface

ND Not detected (refer to Appendix VIII, Table VIII-A, for complete list of PAH results)

NRC No regulatory criteria

PAH Polynuclear aromatic hydrocarbon

Laboratory Qualifiers

U Indicates the compound was not detected above the reported sample quantitation limit.

UJ Indicates that the compound was not detected above an approximated sample quantitation limit.

J Indicates the value for the compound is an estimated value.

= Indicates the compound was detected at the concentration reported.

TABLE 4: GROUNDWATER ELEVATIONS

Well Number	Date Measured	Ground Surface Elev. (ft MSL)	Top of Casing Elev. (ft MSL)	Depth of Screened Interval (ft BGS)	Depth of Free Product (ft BTOC)	Water Depth (ft BTOC)	Product Thickness (ft)	Specific Gravity Adjustment	Corrected Groundwater Elev. (ft MSL)
60-01	5/11/98	73.08	77.09	2.0 - 12.0	N/A	9.92	N/A	N/A	67.17
60-02	5/11/98	73.11	74.66	0.0 - 12.0	N/A	7.48	N/A	N/A	67.18
60-03	9/21/98	73.16	73.12	0.1 - 10.1	N/A	5.11	N/A	N/A	68.01
60-04	9/21/98	73.09	72.85	0.0 - 10.0	N/A	5.41	N/A	N/A	67.44
60-05	9/21/98	72.78	73.45	0.0 - 9.5	N/A	6.13	N/A	N/A	67.32
60-06	9/21/98	73.07	73.06	0.0 - 10.0	N/A	5.68	N/A	N/A	67.38

NOTE:

MSL Mean sea level
BGS Below ground surface
BTOC Below top of casing
N/A Not applicable

TABLE 5a: UST SYSTEM CLOSURE¹ - SOIL ANALYTICAL RESULTS
(VOLATILE ORGANIC COMPOUNDS)

Sample Location	Depth (ft BGS)	Date Sampled	Benzene (mg/kg)	Toluene (mg/kg)	Ethylbenzene (mg/kg)	Xylenes (mg/kg)	Total BTEX (mg/kg)	TPH (mg/kg)
28B-T1-S1	unknown	7/2/96	0.116 U	0.116 U	0.116 U	0.116 U	ND	14600 =
28B-T1-S2	unknown	7/2/96	0.106 U	0.106 U	0.016 U	0.106 U	ND	13200 =
Applicable Standards ²			0.008	6	10	700	NRC	NRC

TABLE 5b: UST SYSTEM CLOSURE¹ - SOIL ANALYTICAL RESULTS
(POLYNUCLEAR AROMATIC HYDROCARBONS)

Sample Location	Depth (ft BGS)	Date Sampled	Detected PAH Compounds (mg/kg)				Total PAHs (mg/kg)
			Benzo(k) fluoranthene	Fluoranthene	Pyrene		
28B-T1-S1	unknown	7/2/96	0.778 J	0.523 J	0.581 J		1.882
28B-T1-S2	unknown	7/2/96					ND
Applicable Standards ²			NRC	NRC			NRC

NOTE:

- ¹ Underground storage tank system closure performed by Anderson Columbia Environmental, Inc. (1996)
² Georgia Department of Natural Resources Applicable Soil Threshold Levels (Table A, Column 2)

BGS Below ground surface
BTEX Benzene, toluene, ethylbenzene, and xylene
NRC No regulatory criteria
PAH Polynuclear aromatic hydrocarbons
TPH Total petroleum hydrocarbons

Laboratory Qualifiers

- U Indicates the compound was not detected above the reported sample quantitation limit.
UJ Indicates that the compound was not detected above an approximated sample quantitation limit.
J Indicates the value for the compound is an estimated value.
= Indicates the compound was detected at the concentration reported.

**TABLE 6a: UST SYSTEM CLOSURE¹ - GROUNDWATER ANALYTICAL RESULTS
(VOLATILE ORGANIC COMPOUNDS)**

Sample Location	Depth (ft BGS)	Date Sampled	Benzene (ug/L)	Toluene (ug/L)	Ethyl – benzene (ug/L)	Xylenes (ug/L)	Total BTEX (ug/L)
			No groundwater samples were collected.				
Applicable Standards ²			5	1,000	700	10,000	NRC

**TABLE 6b: UST SYSTEM CLOSURE¹ - GROUNDWATER ANALYTICAL RESULTS
(POLYNUCLEAR ANALYTICAL RESULTS)**

Sample Location	Depth (ft BGS)	Date Sampled	Detected PAH Compounds (ug/L)								Total PAHs (ug/L)
			No groundwater samples were collected.								
Applicable Standards ¹											NRC

NOTE:

- ¹ Underground storage tank system closure performed by Anderson Columbia Environmental, Inc. (1996)
² U.S. Environmental Protection Agency maximum contaminant levels
 BGS Below ground surface
 BTEX Benzene, toluene, ethylbenzene, and xylene
 NRC No regulatory criteria.
 PAH Polynuclear aromatic hydrocarbons

Laboratory Qualifiers

- U Indicates the compound was not detected above the reported sample quantitation limit.
 UJ Indicates that the compound was not detected above an approximated sample quantitation limit.
 J Indicates the value for the compound is an estimated value.
 = Indicates the compound was detected at the concentration reported.

APPENDIX III
WATER RESOURCES SURVEY DOCUMENTATION

THIS PAGE INTENTIONALLY LEFT BLANK

WATER RESOURCES SURVEY DOCUMENTATION

1.0 LOCAL WATER RESOURCES

As required by the GA EPD UST CAP-Part A guidance, a water resource survey documenting information for public and non-public water supply wells, surface water bodies, underground utilities, and potential receptors was conducted for the Fort Stewart UST investigation sites. The information presented in this appendix provides the supporting documentation for Section II.D.3 of the CAP-Part A Form.

1.1 WATER SUPPLY WELL SURVEY

The water supply well survey was conducted using the following GA EPD guidelines/requirements:

- Fort Stewart is located in an area of average or higher groundwater pollution susceptibility.
- Locate all public supply wells as defined by GA EPD that exist within 2 miles of the investigation sites.
- Locate all non-public supply wells that exist within 0.5 miles of the investigation sites.
- Locate all supply wells nearest the investigation sites.
- Locate all wells downgradient of the investigation sites.

A total of seven groundwater supply wells are located within a 2-mile radius of the Fort Stewart garrison area. Six of these wells are located within the confines of the garrison area. The other well is located at Wright Army Airfield, approximately 1.2 miles northeast of the garrison area. All of the groundwater supply wells are classified as public wells that supply water to Fort Stewart for drinking and nondrinking purposes. These wells are approximately 450 feet deep and draw groundwater from the Principal Artesian (also known as the Floridian) aquifer. Chlorine and fluoride are added into the groundwater at the well heads prior to being pumped into storage tanks and/or water towers, according to Fort Stewart DPW personnel. The location of these wells, along with a 500-foot radius drawn around each well, is shown in Figure 3.

1.2 SURFACE WATER BODIES

Surface water(s) in the State of Georgia, as defined by Rules and Regulations for Water Quality Control, Chapter 391-3-6, shall mean any and all rivers, streams, creeks, branches, lakes, reservoirs, ponds, drainage systems, springs producing 100,000 gallons per day, and all other bodies of surface water, natural or artificial, lying within or forming part of the boundaries of the state, which are not entirely confined and retained completely upon the property of a single individual, partnership, or corporation. The surface water body survey was conducted using the following GA EPD guidelines/requirements:

- surface water bodies that exist within 1 mile of the investigation sites,
- all surface water bodies nearest the investigation sites if these bodies lie outside the 1-mile radius of concern,

- all surface water bodies downgradient of the investigation sites, and
- the storm and sanitary sewers adjacent to the investigation sites.

Several surface water bodies are located within a 1-mile radius of the Fort Stewart garrison area. These are shown in Figure 3 and include Mill Creek, Taylors Creek, Peacock Creek, Childpen's Pond, and two unnamed ponds. Mill Creek extends along the western side of the garrison area and flows into Taylors Creek, located approximately 0.75 miles northwest of the garrison area. Taylors Creek then flows northward approximately 3.5 miles to its confluence with Canoochee Creek. Peacock Creek originates near the east corner of the garrison area and flows southward from the garrison. Mill Creek, Taylors Creek, and Peacock Creek all have natural streambeds and exhibit perennial flow.

Childpen's Pond is located at the northwest end of the garrison area. The two unnamed ponds are located at the northwest end of the facility golf course in the vicinity of Childpen's Pond. All of the ponds are isolated water bodies that are relatively small in size, measuring less than 500 feet in diameter.

Typically, surface water run-off from the UST site moves over the existing concrete and asphalt cover to the Fort Stewart storm water drainage system. Since petroleum contamination at the sites primarily impacts surficial groundwater, the surface water run-off pathway is not a viable contaminant transport mechanism because of the concrete acting as a barrier and the location of the nearest surface water body.

2.0 POTENTIAL RECEPTOR SURVEY SUMMARY OF THE UST 28B SITE

A field potential receptor survey was conducted for the UST 28B site in May 1998. The site and adjacent areas were surveyed for locations of surface water bodies, utility lines, and basements. Basements do not exist in the buildings adjacent to the site. Additional information, provided by DPW, was used to determine the location of the nearest public and non-public water supply wells and downgradient surface water bodies not located during the field survey.

2.1 Water Supply Wells Near the UST 28B Site

The UST 28B site is located approximately 1200 feet south (downgradient) of the Well #3. Well #1 is located approximately 5200 feet southeast (downgradient) of the site. Therefore, the UST 28B site is classified as being located greater than 500 feet to a withdrawal point. There are no non-public supply wells located downgradient of the site within a 2-mile radius.

2.2 Surface Water Bodies Near the UST 28B Site

At the closest point to the site, a tributary to Mill Creek is located approximately 2000 feet north (upgradient) of the site. In the direction of groundwater flow, a drainage ditch is located approximately 250 feet southeast of the site and Mill Creek is located approximately 3000 feet south of the site. Based on the distances between the UST and the nearest surface water body, the site is classified as being located less than 500 feet to a downgradient surface water body.

2.3 Underground Utility Lines Near the UST 28B Site

A catchbasin for a storm drain is located about 125 feet southeast of the former tank pit. The invert elevation of the catchbasin is estimated to be approximately 67.55 feet AMSL or 3.2 feet bgs, which is above the water table, thus the storm drain is not considered a preferential pathway.



Science Applications International Corporation

CONTACT REPORT

INDIVIDUAL CONTACTED, TITLE: Pam Babbs	ORIGINATOR: Patty Stoll
ORGANIZATION: Fort Stewart DPW - Water Resources	DATE CONTACTED: October 10, 1998
PHONE: 912 - 767 - 2281	TIME CONTACTED: 11:00 am
ADDRESS:	CONTACT TYPE: telephone
SUBJECT: Update Supply Well Information for Fort Stewart Supply Wells for Water Resources Survey	
<p>DISCUSSION:</p> <p>During a telephone conversation with Pam Babbs on October 10, 1998 the following information on the supply wells at Fort Stewart was provided.</p> <p>Well No.1 1750 gpm, CD = 451 ft, TD = 816 ft Well No.2 1400 gpm, CD = 470 ft, TD = 808 ft Well No.3 1400 gpm, CD = 436 ft, TD = 750 ft Well No.5 1100 gpm, CD = 560 ft, TD = 779 ft Well No.6A 500 gpm, CD = 374 ft, TD = 472 ft Well No.6B 500 gpm, CD = 393 ft, TD = 508 ft Evans Well 190 gpm, CD = 404 ft, TD = 600 ft Camp Oliver Well 400 gpm, CD = 451 ft, TD = 706 ft</p>	<p>COMMENTS, ACTIONS, DATES</p> <p>Incorporate new pumping rate data into the CAP Part A and B reports being prepared for Fort Stewart.</p>
<p>DISTRIBUTION: Melanie Little (Fort Stewart DPW) Central Records (SAIC) Project File (SAIC)</p>	



Science Applications International Corporation

CONTACT REPORT

INDIVIDUAL CONTACTED, TITLE: Jeff Barnes	ORIGINATOR: Patty Stoll
ORGANIZATION: Georgia Department of Natural Resources	DATE CONTACTED: October 1, 1997
PHONE: 912 - 353 - 3225	TIME CONTACTED: 11:00 am
ADDRESS:	CONTACT TYPE: telephone
SUBJECT: Update Supply Well Information for Liberty County Supply Wells for Water Resources Survey	
<p>DISCUSSION:</p> <p>During a telephone conversation with the Ga DNR, regarding drinking water wells in Liberty County, it was suggested I contact Mr. Jeff Barnes. After being transferred to Mr. Jeff Barnes and explaining our needs, he agreed to send a printout of the permitted drinking water systems in Liberty County.</p> <p>On October 17, 1997 we received the list of permitted drinking water systems in Liberty County.</p>	<p>COMMENTS, ACTIONS, DATES</p> <p>Review list of permitted drinking water supply wells for proximity to Fort Stewart CAP Part A and B sites.</p>
DISTRIBUTION: Melanie Little (Fort Stewart DPW) Central Records (SAIC) Project File (SAIC)	

APPENDIX IV

SOIL BORING LOGS

THIS PAGE INTENTIONALLY LEFT BLANK

HTRW DRILLING LOG						HOLE NUMBER 60-01
PROJECT: Fort Stewart USTs			INSPECTOR J. K. Ledbetter		SHEET 1 OF 1	
ELEV. (A)	DEPTH (B)	DESCRIPTION OF MATERIALS (C)	FIELD SCREENING RESULTS	GEOTECH SAMPLE OR CORE BOX	ANALYTICAL SAMPLE NO. (F)	REMARKS (G)
		Concrete				
	1	Silty SAND, 20% silt, fine to medium grained, soft, dry, brown (10YR 5/3) with clumps of clayey SAND	Oppm		Soil Sample 600111	
	2	20% clay, medium grained, low plasticity, firm, moist, gray (10YR 5/1)				
	3	No Recovery	Oppm			
	4	SAND, medium to coarse grained, subrounded, soft, dry, very pale brown (10YR 8/3)				
	5	Silty SAND, 20% silt, fine to medium grained, soft, moist, brown (10YR 5/3)	Oppm		Soil Sample 600121	Wet below 5.1 FT BGS
	6	No Recovery				
	7		N/A			
	8					
	9					Pushed to 12.0 FT. Set piezometer
	10					

HTRW DRILLING LOG						HOLE NUMBER 60-02
PROJECT: Fort Stewart USTs			INSPECTOR J. K. Ledbetter		SHEET 1 OF 1	
ELEV. (A)	DEPTH (B)	DESCRIPTION OF MATERIALS (C)	FIELD SCREENING RESULTS	GEOTECH SAMPLE OR CORE BOX	ANALYTICAL SAMPLE NO. (F)	REMARKS (G)
		Concrete				
	1	Sandy CLAY, 20% medium grained sand, medium plasticity, soft, moist, red (10R 5/6)	30ppm		Soil Sample 600221	
	2	Sandy SILT, 10% sand, soft, moist to wet, dark brown (10YR 3/3)				Wet below 1.6 FT BGS
	3	No Recovery	0ppm			
	4					
	5		0ppm			
	6	grading to clayey SAND, 15% clay, low plasticity, firm, wet, very pale brown (10YR 8/2)				
	7	grading to SAND, medium to coarse grained, soft, wet, very pale brown (10YR 8/3)	0ppm			
	8					
	9					Pushed to 12.0 FT Set piezometer
	10					

HTRW DRILLING LOG						HOLE NUMBER 60-03
PROJECT: Fort Stewart USTs			INSPECTOR K. Ledbetter			SHEET 1 OF 1
ELEV. (A)	DEPTH (B)	DESCRIPTION OF MATERIALS (C)	FIELD SCREENING RESULTS	GEOTECH SAMPLE OR CORE BOX	ANALYTICAL SAMPLE NO. (F)	REMARKS (G)
		CONCRETE				
	1	sandy SILT (ML), 5% fine grained sand, soft, dry, dark brown (10 YR 3/3)	300 ppm		Soil Sample 600321	
	2	silty SAND (SM), 10% silt, fine grained, soft, dry, light gray (10 YR 7/1)				
	3	SAND (SP), fine to medium grained, soft, dry, yellowish brown (10 YR 5/4)	111 ppm			
	4	sandy SILT (ML), 10% fine to medium grained sand, soft, dry, dark brown (10 YR 3/3)				
	5		94 ppm		Soil Sample 600311	WET BELOW 4.9 FT BGS
	6					
	7	clayey SAND (SC), 15% clay, low plasticity, medium grained, subrounded, firm to hard, wet, gray (10 YR 6/1)				
	8					
	9					COLLECTED GROUNDWATER SAMPLE 600312 FROM TEMPORARY PIEZOMETER SCREENED AT 0.1 TO 10.1 FT BGS (10 FT SCREEN)
	10					PUSHED TO 10.1 FT BGS TO SET TEMPORARY PIEZOMETER

HTRW DRILLING LOG						HOLE NUMBER 60-04
PROJECT: Fort Stewart USTs			INSPECTOR K. Ledbetter			SHEET 1 OF 1
ELEV. (A)	DEPTH (B)	DESCRIPTION OF MATERIALS (C)	FIELD SCREENING RESULTS	GEOTECH SAMPLE OR CORE BOX	ANALYTICAL SAMPLE NO. (F)	REMARKS (G)
		CONCRETE				
	1	silty SAND (SM), 5% silt, fine to medium grained, subrounded, soft, dry, dark brown (10YR 3/3)	41 ppm		Soil Sample 600421	
	2	GRAVEL				
	3	silty SAND (SM), 5% silt, fine to medium grained, subrounded, soft, dry, dark brown (10YR 3/3) to very pale brown (10YR 7/3)	20 ppm		Soil Sample 600411	
	4					7 WET BELOW
	5	silty SAND (SM), 5% silt, fine to medium grained, subrounded, soft, wet, brown (10YR 4/3) to very pale brown (10YR 7/4)				= 4.1 FT BGS
	6					
	7					
	8					
	9					COLLECTED GROUNDWATER SAMPLE 600412 FROM TEMPORARY PIEZOMETER SCREENED AT 0.25 TO 10.25 FT BGS (10 FT SCREEN)
	10					PUSHED TO 12.0 FT BGS TO SET TEMPORARY PIEZOMETER

HTRW DRILLING LOG						HOLE NUMBER 60-05
PROJECT: Fort Stewart USTs			INSPECTOR K. Ledbetter			SHEET 1 OF 1
ELEV. (A)	DEPTH (B)	DESCRIPTION OF MATERIALS (C)	FIELD SCREENING RESULTS	GEOTECH SAMPLE OR CORE BOX	ANALYTICAL SAMPLE NO. (F)	REMARKS (G)
		CONCRETE				
	1	silty SAND (SM), 10% silt, fine to medium grained, subrounded, soft, dry, grayish brown (10 YR 5/2)	25 ppm		Soil Sample 600511	
	2					
	3	clayey SAND (SC), 15% clay, firm, low plasticity, fine grained, dry, gray (10 YR 6/1)	54 ppm			
	4					
	5	sandy silt (ML), 15% fine sand, soft, dry, dark brown (10 YR 3/3) clayey SAND (SC), 20% clay, medium plasticity, fine to medium grained, firm, moist, light gray (10 YR 7/2)	88 ppm		Soil Sample 600521	
	6					
	7	silty SAND (SM), 10% silt, fine to medium grained, subrounded, firm, wet, light gray (10 YR 7/1)				7 WET BELOW 6.3 FT BGS
	8					
	9					COLLECTED GROUNDWATER SAMPLE 600512 FROM TEMPORARY PIEZOMETER SCREENED AT 0 TO 9.35 FT BGS (10 FT SCREEN)
	10					PUSHED TO 10.0 FT BGS TO SET TEMPORARY PIEZOMETER

HTRW DRILLING LOG						HOLE NUMBER 60-06
PROJECT: Fort Stewart USTs			INSPECTOR K. Ledbetter			SHEET 1 OF 1
ELEV. (A)	DEPTH (B)	DESCRIPTION OF MATERIALS (C)	FIELD SCREENING RESULTS	GEOTECH SAMPLE OR CORE BOX	ANALYTICAL SAMPLE NO. (F)	REMARKS (G)
		CONCRETE				
	1	clayey SAND (SC), 10% clay, low plasticity, fine to medium grained, firm, dry to moist, grayish brown (10 YR 5/2)	21 ppm		Soil Sample 600611	
	2	silt (ML), soft, dry, black (10 YR 2/1)				
	3	silty SAND (SM), 5% silt, fine to medium grained, soft, dry, light brownish gray (10 YR 6/2)	24 ppm			
	4					
	5		61 ppm		Soil Sample 600621	
	6	clayey SAND (SC), 15% clay, low plasticity, firm, moist brownish yellow (10 YR 6/8)				WET BELOW 5.7 FT BGS
	7	silty SAND (SM), 10% silt, fine grained, firm, wet, pale brown (10 YR 6/3)				
	8					
	9					Collected groundwater sample 600612 from temporary piezometer screened at 0.05 to 10.05 ft bgs (10 ft screen)
	10					Pushed to 10.05 ft bgs to set temporary piezometer

HTRW DRILLING LOG						HOLE NUMBER 60-07
PROJECT: Fort Stewart USTs			INSPECTOR J. Celeste			SHEET 1 OF 2
ELEV. (A)	DEPTH (B)	DESCRIPTION OF MATERIALS (C)	FIELD SCREENING RESULTS	GEOTECH SAMPLE OR CORE BOX	ANALYTICAL SAMPLE NO. (F)	REMARKS (G)
	0	DID NOT COLLECT SOIL FOR LITHOLOGY DESCRIPTION. NO SOIL CUTTINGS FROM GEOPROBE				
	1					
	2					
	3					
	4					
	5					
	6					
	7		Oppm			Vertical profile screened from 6.0 to 10.0 ft BGS
	8					
	9					
	10					

HTRW DRILLING LOG						HOLE NUMBER 60-07
PROJECT: Fort Stewart USTs			INSPECTOR J. Celeste			SHEET 2 OF 2
ELEV. (A)	DEPTH (B)	DESCRIPTION OF MATERIALS (C)	FIELD SCREENING RESULTS	GEOTECH SAMPLE OR CORE BOX	ANALYTICAL SAMPLE NO. (F)	REMARKS (G)
	11		Oppm		GW Sample 600722	Vertical profile screened from 11.0 to 15.0 ft BGS
	12					
	13					
	14					
	15					
	16		Oppm		GW Sample 600732	Vertical profile screened from 16.0 to 20.0 ft BGS
	17					
	18					
	19					
	20					END OF GEOPROBE

APPENDIX V
SOIL LABORATORY REPORTS

THIS PAGE INTENTIONALLY LEFT BLANK

TABLE V-A. Summary of Soil Analytical Results

Station:	GA UST	60-01	60-01	60-02	60-03
Sample ID:	Soil	600111	600121	600221	600311
Sample Interval (ft):	Threshold	0.5 - 2.0	4.0 - 6.0	0.2 - 2.0	0.5 - 2.0
Collection Date:	Level ¹	10-May-98	10-May-98	10-May-98	20-Sep-98
Units:	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)
<i>VOLATILE ORGANIC COMPOUNDS</i>					
Benzene	0.008	0.00055 U	0.00055 U	0.0006 UJ	0.0022 U
Toluene	6	0.0523 =	0.0152 =	0.0342 J	0.0079 =
Ethylbenzene	10	0.0022 U	0.0022 U	0.0024 UJ	0.0022 U
Xylenes, Total	700	0.0066 U	0.0066 U	0.0071 UJ	0.0067 U
<i>POLYNUCLEAR AROMATIC HYDROCARBONS</i>					
2-Chloronaphthalene	NRC	0.359 U	0.364 U	3.93 U	0.365 U
Acenaphthene	NRC	0.359 U	0.364 U	3.93 U	0.365 U
Acenaphthylene	NRC	0.359 U	0.364 U	3.93 U	0.365 U
Anthracene	NRC	0.359 U	0.364 U	3.93 U	0.365 U
Benzo(a)anthracene	NRC	0.359 U	0.364 U	3.93 U	0.365 U
Benzo(a)pyrene	NRC	0.359 U	0.364 U	3.93 U	0.365 U
Benzo(b)fluoranthene	NRC	0.359 U	0.364 U	3.93 U	0.365 U
Benzo(g,h,i)perylene	NRC	0.359 U	0.364 U	3.93 U	0.365 U
Benzo(k)fluoranthene	NRC	0.359 U	0.364 U	3.93 U	0.365 U
Chrysene	NRC	0.359 U	0.364 U	3.93 U	0.365 U
Dibenzo(a,h)anthracene	NRC	0.359 U	0.364 U	3.93 U	0.365 U
Fluoranthene	NRC	0.359 U	0.364 U	3.93 U	0.365 U
Fluorene	NRC	0.359 U	0.364 U	3.93 U	0.365 U
Indeno(1,2,3-cd)pyrene	NRC	0.359 U	0.364 U	3.93 U	0.365 U
Naphthalene	NRC	0.359 U	0.364 U	3.93 U	0.365 U
Phenanthrene	NRC	0.359 U	0.364 U	3.93 U	0.365 U
Pyrene	NRC	0.359 U	0.364 U	3.93 U	0.365 U
<i>OTHER ANALYTES</i>					
Lead	NRC		2.2 =	4.4 =	
Total Petroleum Hydrocarbons	NRC	23.3 U	15.9 U	2420 =	10.8 UJ

NOTE:

May 1998 sampling was performed prior to the new CAP-Part A guidance that was published in May 1998. Thus, the new SW-846 analytical methods were not used during that sampling event.

Contract for the September 1998 sampling was prior to the new CAP-Part A guidance that was published in May 1998, thus the new SW-846 analytical methods were not used during that sampling event.

Analytical data for the UST closure is summarized in Appendix II, and the analytical data is included at the end of this appendix but not summarized in this table.

Analytical data for QA/QC samples 600313 (duplicate) and 600415 (equipment rinsate) are contained within this appendix, but are not summarized in this table.

Elevated PAH detection limits are a result of associated organic content such as TPH. During extraction of the PAH compounds, all other organic compounds are extracted, causing a wide range of organic compounds to be present; thus, the target PAHs become small peaks in the chromatograph. As a result, the laboratory dilutes the concentrate, in turn elevating the detection limit.

¹ Georgia Department of Natural Resources Applicable Soil Threshold Levels (Table A, Column 2)

Bold values exceed soil threshold levels

NRC No regulatory criteria

Laboratory Qualifiers

U Indicates that the compound was not detected above the reported sample quantitation limit.

UJ Indicates that the compound was not detected above an approximated sample quantitation limit.

J Indicates that the value for the compound was an estimated value.

= Indicates that the compound was detected at the concentration reported.

R Indicates that the sample results are unusable and the presence or absence of the compound could not be verified.

TABLE V-A. Summary of Soil Analytical Results (continued)

Station:	GA UST	60-03	60-04	60-04	60-05
Sample ID:	Soil	600321	600411	600421	600511
Sample Interval (ft):	Threshold	4.0 - 6.0	0.5 - 2.0	2.0 - 4.0	0.5 - 2.0
Collection Date:	Level ¹	20-Sep-98	18-Sep-98	18-Sep-98	18-Sep-98
Units:	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)
VOLATILE ORGANIC COMPOUNDS					
Benzene	0.008	0.0022 U	0.0021 U	0.0021 U	0.0022 U
Toluene	6	0.0022 U	0.0021 U	0.0023 =	0.004 =
Ethylbenzene	10	0.0022 U	0.0021 U	0.0021 U	0.0022 U
Xylenes, Total	700	0.0066 U	0.0064 U	0.0064 U	0.0067 U
POLYNUCLEAR AROMATIC HYDROCARBONS					
2-Chloronaphthalene	NRC	0.365 U	1.4 U	0.35 U	0.37 U
Acenaphthene	NRC	0.365 U	1.4 U	0.35 U	0.37 U
Acenaphthylene	NRC	0.365 U	1.4 U	0.35 U	0.37 U
Anthracene	NRC	0.365 U	1.4 U	0.35 U	0.37 U
Benzo(a)anthracene	NRC	0.365 U	1.4 U	0.35 U	0.37 U
Benzo(a)pyrene	NRC	0.365 U	1.4 U	0.35 U	0.37 U
Benzo(b)fluoranthene	NRC	0.365 U	1.4 U	0.35 U	0.37 U
Benzo(g,h,i)perylene	NRC	0.365 U	1.4 U	0.35 U	0.37 U
Benzo(k)fluoranthene	NRC	0.365 U	1.4 U	0.35 U	0.37 U
Chrysene	NRC	0.365 U	1.4 U	0.35 U	0.37 U
Dibenzo(a,h)anthracene	NRC	0.365 U	1.4 U	0.35 U	0.37 U
Fluoranthene	NRC	0.365 U	1.4 U	0.35 U	0.37 U
Fluorene	NRC	0.365 U	1.4 U	0.35 U	0.37 U
Indeno(1,2,3-cd)pyrene	NRC	0.365 U	1.4 U	0.35 U	0.37 U
Naphthalene	NRC	0.365 U	1.4 U	0.35 U	0.37 U
Phenanthrene	NRC	0.365 U	1.4 U	0.35 U	0.37 U
Pyrene	NRC	0.365 U	1.4 U	0.35 U	0.37 U
OTHER ANALYTES					
Lead	NRC	8.4 =		3.4 =	
Total Petroleum Hydrocarbons	NRC	13.6 J	2 UJ	23.9 J	27.8 J

NOTE:

May 1998 sampling was performed prior to the new CAP-Part A guidance that was published in May 1998. Thus, the new SW-846 analytical methods were not used during that sampling event.

Contract for the September 1998 sampling was prior to the new CAP-Part A guidance that was published in May 1998, thus the new SW-846 analytical methods were not used during that sampling event.

Analytical data for the UST closure is summarized in Appendix II, and the analytical data is included at the end of this appendix but not summarized in this table.

Analytical data for QA/QC samples 600313 (duplicate) and 600415 (equipment rinsate) are contained within this appendix, but are not summarized in this table.

Elevated PAH detection limits are a result of associated organic content such as TPH. During extraction of the PAH compounds, all other organic compounds are extracted, causing a wide range of organic compounds to be present; thus, the target PAHs become small peaks in the chromatograph. As a result, the laboratory dilutes the concentrate, in turn elevating the detection limit.

¹ Georgia Department of Natural Resources Applicable Soil Threshold Levels (Table A, Column 2)

Bold values exceed soil threshold levels

NRC No regulatory criteria

Laboratory Qualifiers

U Indicates that the compound was not detected above the reported sample quantitation limit.

UJ Indicates that the compound was not detected above an approximated sample quantitation limit.

J Indicates that the value for the compound was an estimated value.

= Indicates that the compound was detected at the concentration reported.

R Indicates that the sample results are unusable and the presence or absence of the compound could not be verified.

TABLE V-A. Summary of Soil Analytical Results (continued)

Station:	GA UST	60-05	60-06	60-06
Sample ID:	Soil	600521	600611	600621
Sample Interval (ft):	Threshold	4.0 - 6.0	0.5 - 2.0	4.0 - 6.0
Collection Date:	Level ¹	18-Sep-98	18-Sep-98	18-Sep-98
Units:	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)
<i>VOLATILE ORGANIC COMPOUNDS</i>				
Benzene	0.008	0.0023 U	0.0021 U	0.0023 U
Toluene	6	0.0023 U	0.0111 =	0.004 =
Ethylbenzene	10	0.0023 U	0.0021 U	0.0023 U
Xylenes, Total	700	0.0069 U	0.0062 U	0.0068 U
<i>POLYNUCLEAR AROMATIC HYDROCARBONS</i>				
2-Chloronaphthalene	NRC	0.382 U	1.37 U	0.378 U
Acenaphthene	NRC	0.382 U	1.37 U	0.378 U
Acenaphthylene	NRC	0.382 U	1.37 U	0.378 U
Anthracene	NRC	0.382 U	1.37 U	0.378 U
Benzo(a)anthracene	NRC	0.382 U	1.37 U	0.378 U
Benzo(a)pyrene	NRC	0.382 U	1.37 U	0.378 U
Benzo(b)fluoranthene	NRC	0.382 U	1.37 U	0.378 U
Benzo(g,h,i)perylene	NRC	0.382 U	1.37 U	0.378 U
Benzo(k)fluoranthene	NRC	0.382 U	1.37 U	0.378 U
Chrysene	NRC	0.382 U	1.37 U	0.378 U
Dibenzo(a,h)anthracene	NRC	0.382 U	1.37 U	0.378 U
Fluoranthene	NRC	0.382 U	1.37 U	0.378 U
Fluorene	NRC	0.382 U	1.37 U	0.378 U
Indeno(1,2,3-cd)pyrene	NRC	0.382 U	1.37 U	0.378 U
Naphthalene	NRC	0.382 U	1.37 U	0.378 U
Phenanthrene	NRC	0.382 U	1.37 U	0.378 U
Pyrene	NRC	0.382 U	1.37 U	0.378 U
<i>OTHER ANALYTES</i>				
Lead	NRC	3.2 =		3.5 =
Total Petroleum Hydrocarbons	NRC	7.02 UJ	2660 J	265 J

NOTE:

May 1998 sampling was performed prior to the new CAP-Part A guidance that was published in May 1998. Thus, the new SW-846 analytical methods were not used during that sampling event.

Contract for the September 1998 sampling was prior to the new CAP-Part A guidance that was published in May 1998, thus the new SW-846 analytical methods were not used during that sampling event.

Analytical data for the UST closure is summarized in Appendix II, and the analytical data is included at the end of this appendix but not summarized in this table.

Analytical data for QA/QC samples 600313 (duplicate) and 600415 (equipment rinsate) are contained within this appendix, but are not summarized in this table.

Elevated PAH detection limits are a result of associated organic content such as TPH. During extraction of the PAH compounds, all other organic compounds are extracted, causing a wide range of organic compounds to be present; thus, the target PAHs become small peaks in the chromatograph. As a result, the laboratory dilutes the concentrate, in turn elevating the detection limit.

¹ Georgia Department of Natural Resources Applicable Soil Threshold Levels (Table A, Column 2)

Bold values exceed soil threshold levels

NRC No regulatory criteria

Laboratory Qualifiers

- U Indicates that the compound was not detected above the reported sample quantitation limit.
- UJ Indicates that the compound was not detected above an approximated sample quantitation limit.
- J Indicates that the value for the compound was an estimated value.
- = Indicates that the compound was detected at the concentration reported.
- R Indicates that the sample results are unusable and the presence or absence of the compound could not be verified.

THIS PAGE INTENTIONALLY LEFT BLANK

DATA VALIDATION

COPY 1A VOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

600111

Lab Name: GENERAL ENGINEERING LABOR Contract: NA

Lab Code: NA Case No.: NA SAS No.: NA

SDG No.: FS4008S

Matrix: (soil/water) SOIL

Lab Sample ID: 9805300-04

Sample wt/vol: 10.0 (g/mL) G

Lab File ID: 2I6017

Level: (low/med) LOW

Date Received: 05/11/98

% Moisture: not dec. 9

Date Analyzed: 05/17/98

GC Column: J&W DB-624(PID) ID: 0.53 (mm)

Dilution Factor: 1.0

Soil Extract Volume: (ml)

Soil Aliquot Volume: (uL)

CAS NO.

COMPOUND

CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/KG

Q

71-43-2-----	Benzene	0.55	U	U = U U
108-88-3-----	Toluene	52.3		
100-41-4-----	Ethylbenzene	2.2	U	
1330-20-7-----	Xylenes (total)	6.6	U	

FORM I VOA

DATA VALIDATION

1B
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

600111

Lab Name: GENERAL ENGINEERING LABOR Contract: NA
 Lab Code: NA Case No.: NA SAS No.: NA SDG No.: FS4008S
 Matrix: (soil/water) SOIL Lab Sample ID: 9805300-04
 Sample wt/vol: 30.6 (g/mL) G Lab File ID: 7U415
 Level: (low/med) LOW Date Received: 05/11/98
 % Moisture: 9 decanted: (Y/N) N Date Extracted: 05/15/98
 Concentrated Extract Volume: 1.00 (mL) Date Analyzed: 05/21/98
 Injection Volume: 1.0 (uL) Dilution Factor: 1.0
 GPC Cleanup: (Y/N) N pH: 7.0

CAS NO.

COMPOUND

CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/KG

Q

91-20-3-----	naphthalene	359	U
91-58-7-----	2-chloronaphthalene	359	U
208-96-8-----	acenaphthylene	359	U
83-32-9-----	acenaphthene	359	U
86-73-7-----	fluorene	359	U
85-01-8-----	phenanthrene	359	U
120-12-7-----	anthracene	359	U
206-44-0-----	fluoranthene	359	U
129-00-0-----	pyrene	359	U
56-55-3-----	benzo (a) anthracene	359	U
218-01-9-----	chrysene	359	U
205-99-2-----	benzo (b) fluoranthene	359	U
207-08-9-----	benzo (k) fluoranthene	359	U
50-32-8-----	benzo (a) pyrene	359	U
193-39-5-----	indeno (1,2,3-cd) pyrene	359	U
53-70-3-----	dibenz (a,h) anthracene	359	U
191-24-2-----	benzo (g,h,i) perylene	359	U

FORM I SV-1

OLM03.0

Client: Science Applications International Corp.
P.O. Box 2502
800 Oak Ridge Turnpike
Oak Ridge, Tennessee 37831
Contact: Ms. Lorene Rollins
Project Description: CAP-Part A for UST Sites (Task Order No. 8)

cc: SAIC00598

Report Date: June 01, 1998

Page 1 of 1

Sample ID : 600111
Lab ID : 9805300-04
Matrix : Soil
Date Collected : 05/10/98
Date Received : 05/11/98
Priority : Routine
Collector : Client

Parameter	Qualifier	Result	DL	RL	Units	DF	Analyst	Date	Time	Batch	M
General Chemistry											
Total Rec. Petro. Hydrocarbons		23.3 45.4 <i>45.4</i>	72.18		11.0 mg/kg	1.0	JLP	05/26/98	1330	122880	1

M = Method	Method-Description
M 1	EPA 418.1 Modified

Notes:

The qualifiers in this report are defined as follows:

ND indicates that the analyte was not detected at a concentration greater than the detection limit.

J indicates presence of analyte at a concentration less than the reporting limit (RL) and greater than the detection limit (DL).

U indicates that the analyte was not detected at a concentration greater than the detection limit.

* indicates that a quality control analyte recovery is outside of specified acceptance criteria.

This data report has been prepared and reviewed
in accordance with General Engineering Laboratories
standard operating procedures. Please direct
any questions to your Project Manager, Valerie Davis at (803) 769-7391.

Reviewed By



9805300-04

DATA VALIDATION

1A
COPY VOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

600121

Lab Name: GENERAL ENGINEERING LABOR Contract: NA

Lab Code: NA Case No.: NA SAS No.: NA

Matrix: (soil/water) SOIL

SDG No.: FS4008S

Sample wt/vol: 10.0 (g/mL) G

Lab Sample ID: 9805300-10

Level: (low/med) LOW

Lab File ID: 2I7017

% Moisture: not dec. 9

Date Received: 05/11/98

GC Column: J&W DB-624 (PID) ID: 0.53 (mm)

Date Analyzed: 05/18/98

Soil Extract Volume: (ml)

Dilution Factor: 1.0

Soil Aliquot Volume: (uL)

CAS NO.

COMPOUND

CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/KG

Q

71-43-2-----Benzene	0.55	U	U = U U
108-88-3-----Toluene	15.2		
100-41-4-----Ethylbenzene	2.2	U	
1330-20-7-----Xylenes (total)	6.6	U	

FORM I VOA

1B
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

600121

Lab Name: GENERAL ENGINEERING LABOR Contract: NA

Lab Code: NA Case No.: NA SAS No.: NA SDG No.: FS4008S

Matrix: (soil/water) SOIL Lab Sample ID: 9805300-10

Sample wt/vol: 30.2 (g/mL) G Lab File ID: 7U421

Level: (low/med) LOW Date Received: 05/11/98

% Moisture: 9 decanted: (Y/N) N Date Extracted: 05/15/98

Concentrated Extract Volume: 1.00 (mL) Date Analyzed: 05/21/98

Injection Volume: 1.0 (uL) Dilution Factor: 1.0

GPC Cleanup: (Y/N) N pH: 7.0

CAS NO. COMPOUND CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/KG Q

91-20-3	-----naphthalene	364	U
91-58-7	-----2-chloronaphthalene	364	U
208-96-8	-----acenaphthylene	364	U
83-32-9	-----acenaphthene	364	U
86-73-7	-----fluorene	364	U
85-01-8	-----phenanthrene	364	U
120-12-7	-----anthracene	364	U
206-44-0	-----fluoranthene	364	U
129-00-0	-----pyrene	364	U
56-55-3	-----benzo (a) anthracene	364	U
218-01-9	-----chrysene	364	U
205-99-2	-----benzo (b) fluoranthene	364	U
207-08-9	-----benzo (k) fluoranthene	364	U
50-32-8	-----benzo (a) pyrene	364	U
193-39-5	-----indeno (1,2,3-cd) pyrene	364	U
53-70-3	-----dibenz (a,h) anthracene	364	U
191-24-2	-----benzo (g,h,i) perylene	364	U

FORM I SV-1

OLM03.0

Client: Science Applications International Corp.
P.O. Box 2502
800 Oak Ridge Turnpike
Oak Ridge, Tennessee 37831
Contact: Ms. Lorens Rollins
Project Description: CAP-Part A for UST Sites (Task Order No. 8)

cc: SAIC00598

Report Date: June 01, 1998

Page 1 of 1

Sample ID : 600121
Lab ID : 9805300-10
Matrix : Soil
Date Collected : 05/10/98
Date Received : 05/11/98
Priority : Routine
Collector : Client

Parameter	Qualifier	Result	DL	RL	Units	DF	Analyst	Date	Time	Batch	M
General Chemistry											
Total Rec. Petro. Hydrocarbons		15.9 15.9 <i>u</i>	2.18	11.0	mg/kg	1.0	JLP	05/26/98	1330	122880	1

M = Method

Method-Description

M 1

EPA 418.1 Modified

Notes:

The qualifiers in this report are defined as follows:

- ND indicates that the analyte was not detected at a concentration greater than the detection limit.
- J indicates presence of analyte at a concentration less than the reporting limit (RL) and greater than the detection limit (DL).
- U indicates that the analyte was not detected at a concentration greater than the detection limit.
- * indicates that a quality control analyte recovery is outside of specified acceptance criteria.

This data report has been prepared and reviewed in accordance with General Engineering Laboratories standard operating procedures. Please direct any questions to your Project Manager, Valerie Davis at (803) 769-7391.

Reviewed By



9805300-10

SDG No.: FS4008S

Form 1. Inorganic Analyses Data Sheet

Method Type: Total Metals

Sample ID: 9805300-10

Client ID: 600121

Contract: SAIC00598

Lab Code: GEL

Case No.:

SAS No.:

Matrix: SOIL

Date Received: 5/11/98

Level: LOW

% Solids: 91.00

CAS No.	Analyte	Concentration	Units	C	Qual	M	DL	Instrument ID	Analytical Run
7439-92-1	Lead ==	2.2	mg/kg			P	0.10	TJA61 Trace ICPAES	980517-1

Color Before:

Clarity Before:

Texture:

Color After:

Clarity After:

Artifacts:

Comments:

DATA VALIDATION
COPY

1A
VOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

600221

Lab Name: GENERAL ENGINEERING LABOR Contract: NA

Lab Code: NA

Case No.: NA

SAS No.: NA

SDG No.: PS4008S

Matrix: (soil/water) SOIL

Sample wt/vol: 10.0 (g/mL) G

Lab Sample ID: 9805300-09

Level: (low/med) LOW

Lab File ID: 2I6022

% Moisture: not dec. 16

Date Received: 05/11/98

GC Column: J&W DB-624 (PID) ID: 0.53 (mm)

Date Analyzed: 05/17/98

Soil Extract Volume: (ml)

Dilution Factor: 1.0

Soil Aliquot Volume: (uL)

CAS NO.

COMPOUND

CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/KG

Q

71-43-2-----	Benzene	0.60	U
108-88-3-----	Toluene	34.2	U
100-41-4-----	Ethylbenzene	2.4	U
1330-20-7-----	Xylenes (total)	7.1	U

UJ G02, K01
J G02, K01
UJ G02, K01
UJ G02, K01

Use

G02, K01

FORM I VOA

1B
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

600221

Lab Name: GENERAL ENGINEERING LABOR Contract: NA

Lab Code: NA Case No.: NA SAS No.: NA SDG No.: FS4008S

Matrix: (soil/water) SOIL Lab Sample ID: 9805300-09

Sample wt/vol: 30.3 (g/mL) G Lab File ID: 7U507

Level: (low/med) LOW Date Received: 05/11/98

% Moisture: 16 decanted: (Y/N) N Date Extracted: 05/15/98

Concentrated Extract Volume: 1.00 (mL) Date Analyzed: 05/22/98

Injection Volume: 1.0 (uL) Dilution Factor: 10.0

GPC Cleanup: (Y/N) N pH: 7.0

CAS NO. COMPOUND CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/KG Q

91-20-3	-----naphthalene	3930	U
91-58-7	-----2-chloronaphthalene	3930	U
208-96-8	-----acenaphthylene	3930	U
83-32-9	-----acenaphthene	3930	U
86-73-7	-----fluorene	3930	U
85-01-8	-----phenanthrene	3930	U
120-12-7	-----anthracene	3930	U
206-44-0	-----fluoranthene	3930	U
129-00-0	-----pyrene	3930	U
56-55-3	-----benzo(a)anthracene	3930	U
218-01-9	-----chrysene	3930	U
205-99-2	-----benzo(b)fluoranthene	3930	U
207-08-9	-----benzo(k)fluoranthene	3930	U
50-32-8	-----benzo(a)pyrene	3930	U
193-39-5	-----indeno(1,2,3-cd)pyrene	3930	U
53-70-3	-----dibenz(a,h)anthracene	3930	U
191-24-2	-----benzo(g,h,i)perylene	3930	U

FORM I SV-1

OLM03.0

DATA VALIDATION COPY

Client: Science Applications International Corp.
P.O. Box 2502
800 Oak Ridge Turnpike
Oak Ridge, Tennessee 37831
Contact: Ms. Lorene Rollins
Project Description: CAP-Part A for UST Sites (Task Order No. 8)

cc: SAIC00598

Report Date: June 01, 1998

Page 1 of 1

Sample ID : 600221
Lab ID : 9805300-09
Matrix : Soil
Date Collected : 05/10/98
Date Received : 05/11/98
Priority : Routine
Collector : Client

Parameter	Qualifier	Result	DL	RL	Units	DF	Analyst	Date	Time	Batch	M
General Chemistry											
Total Rec. Petro. Hydrocarbons		2420	5145 F01, F08	58.9	298 mg/kg	25	JLP	05/26/98	1330	122880	1

M = Method

Method-Description

M 1

EPA 418.1 Modified

Notes:

The qualifiers in this report are defined as follows:

- ND indicates that the analyte was not detected at a concentration greater than the detection limit.
- J indicates presence of analyte at a concentration less than the reporting limit (RL) and greater than the detection limit (DL).
- U indicates that the analyte was not detected at a concentration greater than the detection limit.
- * indicates that a quality control analyte recovery is outside of specified acceptance criteria.

This data report has been prepared and reviewed in accordance with General Engineering Laboratories standard operating procedures. Please direct any questions to your Project Manager, Valerie Davis at (803) 769-7391.

Reviewed By



SDG No.: FS4008S

FORM 1: Inorganic Analysis Data Sheet

Method Type: Total Metals

Sample ID: 9805300-09

Client ID: 600221

Contract: SAIC00598

Lab Code: GEL

Case No.:

SAS No.:

Matrix: SOIL

Date Received: 5/11/98

Level: LOW

% Solids: 84.00

CAS No.	Analyte	Concentration	Units	C	Qual	M	DL	Instrument ID	Analytical Run
7439-92-1	Lead	4.4	mg/kg			P	0.11	TJA61 Trace ICPAES	980517-1

Color Before:

Clarity Before:

Texture:

Color After:

Clarity After:

Artifacts:

Comments:



SAIC
An Employee-Owned Company
Science Applications International Corporation

800 Oak Ridge Turnpike, Oak Ridge, TN 37831 (423) 481-4600

10/2

COC NO.: GAB016

CHAIN OF CUSTODY RECORD

PROJECT NAME: Fort Stewart New CAP Part A UST Investigation 9805				REQUESTED PARAMETERS												LABORATORY NAME: General Engineering Laboratory							
PROJECT NUMBER: 01-0331-04-9305-200																LABORATORY ADDRESS: 2040 Savage Road Charleston, SC 29417							
PROJECT MANAGER: Patty Stoll																PHONE NO: (803) 556-8171							
Sampler (Signature) <i>Laura Lumley</i>				No. of Bottles/Vials												OBSERVATIONS, COMMENTS, SPECIAL INSTRUCTIONS							
Sample ID	Date Collected	Time Collected	Matrix	BTEX	PAH	TOC	BTEX, GRO	PAH, DRO	PAH, DRO, Lead	PAH, TPH	PAH, TPH, Lead	PAH, TPH, Lead, TOC											
580011	5/10/98	1120	So.1	1	1	1	1	1	1	1	1	1	2										
730111	5/10/98	1110		1	1	1	1	1	1	1	1	1	2										
730311	5/10/98	1430		1	1	1	1	1	1	1	1	1	2										
640211	5/9/98	1510		1	1	1	1	1	1	1	1	1	2										
100521	5/10/98	1035		1	1	1	1	1	1	1	1	1	2										
590111	5/10/98	1010		1	1	1	1	1	1	1	1	1	2										
130541	5/10/98	1455		1	1	1	1	1	1	1	1	1	2										
130531	5/10/98	1450		1	1	1	1	1	1	1	1	1	2										
730411	5/10/98	1545		1	1	1	1	1	1	1	1	1	2										
130521	5/10/98	1335		1	1	1	1	1	1	1	1	1	2										
600111	5/10/98	1520		1	1	1	1	1	1	1	1	1	2										
580021	5/10/98	1120		1	1	1	1	1	1	1	1	1	2										
590121	5/10/98	1010		1	1	1	1	1	1	1	1	1	2										
RELINQUISHED BY: <i>Laura Lumley</i>				Date/Time 5/11/98		RECEIVED BY:		Date/Time		Date/Time		TOTAL NUMBER OF CONTAINERS:		Cooler Temperature: 210C									
COMPANY NAME: SAIC				1130		COMPANY NAME:		COMPANY NAME:		Cooler ID: # 2341		FEDEX NUMBER:											
RELINQUISHED BY: <i>Patty Stoll</i>				Date/Time 5/11/98		RELINQUISHED BY:		Date/Time		Date/Time													
COMPANY NAME: SAIC				1130		COMPANY NAME:		COMPANY NAME:															
RELINQUISHED BY:				Date/Time		RECEIVED BY:		Date/Time		Date/Time													
COMPANY NAME:						COMPANY NAME:		COMPANY NAME:															

1A
VOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

600311

Lab Name: GENERAL ENGINEERING LABOR Contract: NA

Lab Code: NA Case No.: NA SAS No.: NA SDG No.: FS4B03S

Matrix: (soil/water) SOIL Lab Sample ID: 9809639-03

Sample wt/vol: 10.0 (g/mL) G Lab File ID: 2C3014

Level: (low/med) LOW Date Received: 09/21/98

% Moisture: not dec. 10 Date Analyzed: 09/30/98

GC Column: J&W DB-624 (PID) ID: 0.53 (mm) Dilution Factor: 1.0

Soil Extract Volume: _____ (mL) Soil Aliquot Volume: _____ (uL)

CAS NO.	COMPOUND	CONCENTRATION UNITS: (ug/L or ug/Kg) UG/KG		Q
71-43-2-----	Benzene	2.2	U	21125
108-88-3-----	Toluene	7.9		
100-41-4-----	Ethylbenzene	2.2	U	
1330-20-7-----	Xylenes (total)	6.7	U	

FORM I VOA

18
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

600311

Lab Name: GENERAL ENGINEERING LABOR Contract: NA
 Lab Code: NA Case No.: NA SAS No.: NA SDG No.: FS4B03S
 Matrix: (soil/water) SOIL Lab Sample ID: 9809639-03
 Sample wt/vol: 30.4 (g/mL) G Lab File ID: 2M410
 Level: (low/med) LOW Date Received: 09/21/98
 % Moisture: 10 decanted: (Y/N) N Date Extracted: 09/23/98
 Concentrated Extract Volume: 1.00 (mL) Date Analyzed: 09/24/98
 Injection Volume: 1.0 (uL) Dilution Factor: 1.0
 GPC Cleanup: (Y/N) N pH: 7.0

CAS NO.	COMPOUND	CONCENTRATION UNITS: (ug/L or ug/Kg) UG/KG		Q
91-20-3	naphthalene	365	U	U ↓
91-58-7	2-chloronaphthalene	365	U	
209-96-8	acenaphthylene	365	U	
83-32-9	acenaphthene	365	U	
86-73-7	fluorene	365	U	
85-01-8	phenanthrene	365	U	
120-12-7	anthracene	365	U	
206-44-0	fluoranthene	365	U	
129-00-0	pyrene	365	U	
56-55-3	benzo (a) anthracene	365	U	
218-01-9	chrysene	365	U	
205-99-2	benzo (b) fluoranthene	365	U	
207-08-9	benzo (k) fluoranthene	365	U	
50-32-8	benzo (a) pyrene	365	U	
193-39-5	indeno (1,2,3-cd) pyrene	365	U	
53-70-3	dibenz (a,h) anthracene	365	U	
191-24-2	benzo (g,h,i) perylene	365	U	

FORM I SV-1

OLM03.0

DATA VALIDATION
COPY

Client: Science Applications International Corp.
P.O. Box 2502
800 Oak Ridge Turnpike
Oak Ridge, Tennessee 37831
Contact: Ms. Lorene Rollins
Project Description: CAP-Part A for UST Sites (Task Order No. 8)

cc: SAIC00598

Report Date: October 08, 1998

Page 1 of 1

Sample ID : 600311
Lab ID : 9809639-03
Matrix : Soil
Date Collected : 09/20/98
Date Received : 09/21/98
Priority : Routine
Collector : Client

Parameter	Qualifier	Result	DL	RL	Units	DF	Analyst	Date	Time	Batch	M
General Chemistry											
Total Rec. Petro. Hydrocarbons	J	10.8	2.20	11.1	mg/kg	1.0	AAT	10/06/98	1100	132776	1

M = Method	Method-Description
M 1	EPA 418.1 Modified

Notes:

The qualifiers in this report are defined as follows:

ND indicates that the analyte was not detected at a concentration greater than the detection limit.

J indicates presence of analyte at a concentration less than the reporting limit (RL) and greater than the detection limit (DL).

U indicates that the analyte was not detected at a concentration greater than the detection limit.

* indicates that a quality control analyte recovery is outside of specified acceptance criteria.

This data report has been prepared and reviewed
in accordance with General Engineering Laboratories
standard operating procedures. Please direct
any questions to your Project Manager, Valerie Davis at (803) 769-7391.

Reviewed By



9809639-03

1A
VOLATILE ORGANICS ANALYSIS DATA SHEET

DUPLICATE
EPA SAMPLE NO.

600313

Lab Name: GENERAL ENGINEERING LABOR Contract: NA

Lab Code: NA Case No.: NA SAS No.: NA SDG No.: FS4B03S

Matrix: (soil/water) SOIL Lab Sample ID: 9809639-02

Sample wt/vol: 10.0 (g/mL) G Lab File ID: 2C3013

Level: (low/med) LOW Date Received: 09/21/98

% Moisture: not dec. 7 Date Analyzed: 09/30/98

GC Column: J&W DB-624 (PID) ID: 0.53 (mm) Dilution Factor: 1.0

Soil Extract Volume: _____ (ml) Soil Aliquot Volume: _____ (uL)

CAS NO.	COMPOUND	CONCENTRATION UNITS: (ug/L or ug/Kg) UG/KG	Q
---------	----------	---	---

71-43-2-----Benzene	2.2	U
108-88-3-----Toluene	2.8	U
100-41-4-----Ethylbenzene	2.2	U
1330-20-7-----Xylenes (total)	6.4	U

U
U
U
U

FORM I VOA

SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET

DUPLICATE

600313

Lab Name: GENERAL ENGINEERING LABOR Contract: NA
 Lab Code: NA Case No.: NA SAS No.: NA SDG No.: FS4B03S
 Matrix: (soil/water) SOIL Lab Sample ID: 9809639-02
 Sample wt/vol: 30.4 (g/mL) G Lab File ID: 2M409
 Level: (low/med) LOW Date Received: 09/21/98
 % Moisture: 7 decanted: (Y/N) N Date Extracted: 09/23/98
 Concentrated Extract Volume: 1.00 (mL) Date Analyzed: 09/24/98
 Injection Volume: 1.0 (uL) Dilution Factor: 1.0
 GPC Cleanup: (Y/N) N pH: 7.0

CAS NO.	COMPOUND	CONCENTRATION UNITS: (ug/L or ug/Kg) UG/KG		Q
91-20-3	-----naphthalene	354	U	U ↓
91-58-7	-----2-chloronaphthalene	354	U	
209-96-8	-----acenaphthylene	354	U	
83-32-9	-----acenaphthene	354	U	
86-73-7	-----fluorene	354	U	
85-01-8	-----phenanthrene	354	U	
120-12-7	-----anthracene	354	U	
206-44-0	-----fluoranthene	354	U	
129-00-0	-----pyrene	354	U	
56-55-3	-----benzo (a) anthracene	354	U	
218-01-9	-----chrysene	354	U	
205-99-2	-----benzo (b) fluoranthene	354	U	
207-08-9	-----benzo (k) fluoranthene	354	U	
50-32-8	-----benzo (a) pyrene	354	U	
193-39-5	-----indeno (1,2,3-cd) pyrene	354	U	
53-70-3	-----dibenz (a,h) anthracene	354	U	
191-24-2	-----benzo (g,h,i) perylene	354	U	

FORM I SV-1

OLM03.0

DATA VALIDATION
COPY

Client: Science Applications International Corp.
P.O. Box 2502
800 Oak Ridge Turnpike
Oak Ridge, Tennessee 37831
Contact: Ms. Lorene Rollins
Project Description: CAP-Part A for UST Sites (Task Order No. 8)

DUPLICATE

cc: SAIC00598

Report Date: October 08, 1998

Page 1 of 1

Sample ID : 600313
Lab ID : 9809639-02
Matrix : Soil
Date Collected : 09/20/98
Date Received : 09/21/98
Priority : Routine
Collector : Client

Parameter	Qualifier	Result	DL	RL	Units	DF	Analyst	Date	Time	Batch	M
General Chemistry											
Total Rec. Petro. Hydrocarbons	J	4.55	U5	F01, F06, I02 2.13	10.8	mg/kg	1.0	AAT	10/06/98	1100	132776 1

M = Method

Method-Description

M 1

EPA 418.1 Modified

Notes:

The qualifiers in this report are defined as follows:

ND indicates that the analyte was not detected at a concentration greater than the detection limit.

J indicates presence of analyte at a concentration less than the reporting limit (RL) and greater than the detection limit (DL).

U indicates that the analyte was not detected at a concentration greater than the detection limit.

* indicates that a quality control analyte recovery is outside of specified acceptance criteria.

This data report has been prepared and reviewed
in accordance with General Engineering Laboratories
standard operating procedures. Please direct
any questions to your Project Manager, Valerie Davis at (803) 769-7391.

Reviewed By



1A
VOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

600321

Lab Name: GENERAL ENGINEERING LABOR Contract: NA

Lab Code: NA Case No.: NA SAS No.: NA SDG No.: FS4B04S

Matrix: (soil/water) SOIL Lab Sample ID: 9809641-02

Sample wt/vol: 10.0 (g/mL) G Lab File ID: 2B507

Level: (low/med) LOW Date Received: 09/21/98

% Moisture: not dec. 9 Date Analyzed: 09/25/98

GC Column: J&W DB-624(PID) ID: 0.53 (mm) Dilution Factor: 1.0

Soil Extract Volume: _____ (ml) Soil Aliquot Volume: _____ (uL)

CAS NO.	COMPOUND	CONCENTRATION UNITS:		Q
		(ug/L or ug/Kg)	UG/KG	
71-43-2-----	Benzene	2.2	U	U ↓
108-88-3-----	Toluene	2.2	U	
100-41-4-----	Ethylbenzene	2.2	U	
1330-20-7-----	Xylenes (total)	6.6	U	

FORM I VOA

DATA VALIDATION
COPY

1B
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

600321

Lab Name: GENERAL ENGINEERING LABOR Contract: NA
Lab Code: NA Case No.: NA SAS No.: NA SDG No.: FS4B04S
Matrix: (soil/water) SOIL Lab Sample ID: 9809641-02
Sample wt/vol: 30.1 (g/mL) G Lab File ID: 7M512
Level: (low/med) LOW Date Received: 09/21/98
% Moisture: 9 decanted: (Y/N) N Date Extracted: 09/23/98
Concentrated Extract Volume: 1.00 (mL) Date Analyzed: 09/24/98
Injection Volume: 1.0 (uL) Dilution Factor: 1.0
GPC Cleanup: (Y/N) N pH: 7.0

CAS NO. COMPOUND CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/KG Q

91-20-3-----	naphthalene	365	U
91-58-7-----	2-chloronaphthalene	365	U
208-96-8-----	acenaphthylene	365	U
83-32-9-----	acenaphthene	365	U
86-73-7-----	fluorene	365	U
85-01-8-----	phenanthrene	365	U
120-12-7-----	anthracene	365	U
206-44-0-----	fluoranthene	365	U
129-00-0-----	pyrene	365	U
56-55-3-----	benzo (a) anthracene	365	U
218-01-9-----	chrysene	365	U
205-99-2-----	benzo (b) fluoranthene	365	U
207-08-9-----	benzo (k) fluoranthene	365	U
50-32-8-----	benzo (a) pyrene	365	U
193-39-5-----	indeno (1,2,3-cd) pyrene	365	U
53-70-3-----	dibenz (a,h) anthracene	365	U
191-24-2-----	benzo (g,h,i) perylene	365	U

FORM I SV-1

OLM03.0

Client: Science Applications International Corp.
P.O. Box 2502
800 Oak Ridge Turnpike
Oak Ridge, Tennessee 37831
Contact: Ms. Lorene Rollins
Project Description: CAP-Part A for UST Sites (Task Order No. 8)

cc: SAIC00598

Report Date: October 08, 1998

Page 1 of 1

Sample ID : 600321
Lab ID : 9809641-02
Matrix : Soil
Date Collected : 09/20/98
Date Received : 09/21/98
Priority : Routine
Collector : Client

Parameter	Qualifier	Result	DL	RL	Units	DF	Analyst	Date	Time	Batch	M
General Chemistry											
Total Rec. Petro. Hydrocarbons		13.6	2.18	11.0	mg/kg	1.0	AAT	10/06/98	1100	132809	1

M = Method

Method-Description

M 1 EPA 418.1 Modified

Notes:

The qualifiers in this report are defined as follows:

ND indicates that the analyte was not detected at a concentration greater than the detection limit.

J indicates presence of analyte at a concentration less than the reporting limit (RL) and greater than the detection limit (DL).

U indicates that the analyte was not detected at a concentration greater than the detection limit.

* indicates that a quality control analyte recovery is outside of specified acceptance criteria.

This data report has been prepared and reviewed
in accordance with General Engineering Laboratories
standard operating procedures. Please direct
any questions to your Project Manager, Valerie Davis at (803) 769-7391.

Reviewed By



9809641-02

DATA VALIDATION

Form 1: Inorganic Analyses Data Sheet

SDG No.: FS4804SDY

Method Type: Total Metals

Sample ID: 9809641-02

Client ID: 600321

Contract: SAIC00598

Lab Code: GEL

Case No.:

SAS No.:

Matrix: SOIL

Date Received: 9/21/98

Level: LOW

% Solids: 91.00

CAS No.	Analyte	Concentration	Units	C	Qual	M	DL	Instrument ID	Analytical Run
7439-92-1	Lead	8.4	mg/kg			P	0.15	TJA61 Trace2 ICPAES	980924-1

Color Before:

Clarity Before:

Texture:

Color After:

Clarity After:

Artifacts:

Comments:

1A
VOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

600411

Lab Name: GENERAL ENGINEERING LABOR Contract: NA

Lab Code: NA Case No.: NA SAS No.: NA SDG No.: FS4B03S

Matrix: (soil/water) SOIL Lab Sample ID: 9809639-04

Sample wt/vol: 10.0 (g/mL) G Lab File ID: 2C3015

Level: (low/med) LOW Date Received: 09/21/98

% Moisture: not dec. 6 Date Analyzed: 09/30/98

GC Column: J&W DB-624(PID) ID: 0.53 (mm) Dilution Factor: 1.0

Soil Extract Volume: _____ (ml) Soil Aliquot Volume: _____ (uL)

CAS NO.	COMPOUND	CONCENTRATION UNITS: (ug/L or ug/Kg) UG/KG		Q
71-43-2-----	Benzene	2.1	U	U ↓
108-88-3-----	Toluene	2.1	U	
100-41-4-----	Ethylbenzene	2.1	U	
1330-20-7-----	Xylenes (total)	6.4	U	

FORM I VOA

SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

600411

Lab Name: GENERAL ENGINEERING LABOR Contract: NA
 Lab Code: NA Case No.: NA SAS No.: NA SDG No.: FS4B03S
 Matrix: (soil/water) SOIL Lab Sample ID: 9809639-04
 Sample wt/vol: 30.4 (g/mL) G Lab File ID: 2M508
 Level: (low/med) LOW Date Received: 09/21/98
 % Moisture: 6 decanted: (Y/N) N Date Extracted: 09/23/98
 Concentrated Extract Volume: 1.00 (mL) Date Analyzed: 09/25/98
 Injection Volume: 1.0 (uL) Dilution Factor: 4.0
 GPC Cleanup: (Y/N) N pH: 7.0

CAS NO.	COMPOUND	CONCENTRATION UNITS: (ug/L or ug/Kg) UG/KG		Q
91-20-3	-----naphthalene	1400	U	U ↓
91-58-7	-----2-chloronaphthalene	1400	U	
209-96-8	-----acenaphthylene	1400	U	
83-32-9	-----acenaphthene	1400	U	
86-73-7	-----fluorene	1400	U	
85-01-8	-----phenanthrene	1400	U	
120-12-7	-----anthracene	1400	U	
206-44-0	-----fluoranthene	1400	U	
129-00-0	-----pyrene	1400	U	
56-55-3	-----benzo(a)anthracene	1400	U	
218-01-9	-----chrysene	1400	U	
205-99-2	-----benzo(b)fluoranthene	1400	U	
207-08-9	-----benzo(k)fluoranthene	1400	U	
50-32-8	-----benzo(a)pyrene	1400	U	
193-39-5	-----indeno(1,2,3-cd)pyrene	1400	U	
53-70-3	-----dibenz(a,h)anthracene	1400	U	
191-24-2	-----benzo(g,h,i)perylene	1400	U	

FORM I SV-1

OLM03.0

DATA VALIDATION

1A
VOLATILE ORGANICS ANALYSIS DATA SHEET

QINSATE
EPA SAMPLE NO.

600415

Lab Name: GENERAL ENGINEERING LABOR Contract: NA
 Lab Code: NA Case No.: NA SAS No.: NA SDG No.: FS4B06W
 Matrix: (soil/water) WATER Lab Sample ID: 9809645-02
 Sample wt/vol: 10.00 (g/ml) ML Lab File ID: 2B3011
 Level: (low/med) LOW Date Received: 09/21/98
 % Moisture: not dec. Date Analyzed: 09/23/98
 GC Column: J&W DB-624(PID) ID: 0.53 (mm) Dilution Factor: 1.0
 Soil Extract Volume: (ml) Soil Aliquot Volume: (uL)

CAS NO.	COMPOUND	CONCENTRATION UNITS: (ug/L or ug/Kg) UG/L		Q
71-43-2-----	Benzene	2.0	U	U ↓
108-88-3-----	Toluene	2.0	U	
100-41-4-----	Ethylbenzene	2.0	U	
1330-20-7-----	Xylenes (total)	6.0	U	

FORM I VOA

1B
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET

RINSATE
EPA SAMPLE NO.

600415

Lab Name: GENERAL ENGINEERING LABOR Contract: NA
 Lab Code: NA Case No.: NA SAS No.: NA SDG No.: FS4B01W
 Matrix: (soil/water) GROUNDH2O Lab Sample ID: 9809637-09
 Sample wt/vol: 1020 (g/mL) ML Lab File ID: 4M416
 Level: (low/med) LOW Date Received: 09/21/98
 % Moisture: _____ decanted: (Y/N) _____ Date Extracted: 09/22/98
 Concentrated Extract Volume: 1.00 (mL) Date Analyzed: 09/24/98
 Injection Volume: 1.0 (uL) Dilution Factor: 1.0
 GPC Cleanup: (Y/N) N pH: 7.0

CAS NO.	COMPOUND	CONCENTRATION UNITS: (ug/L or ug/Kg) UG/L		Q
91-20-3	-----naphthalene	9.8	U	U ↓
91-58-7	-----2-chloronaphthalene	9.8	U	
209-96-8	-----acenaphthylene	9.8	U	
83-32-9	-----acenaphthene	9.8	U	
86-73-7	-----fluorene	9.8	U	
85-01-8	-----phenanthrene	9.8	U	
120-12-7	-----anthracene	9.8	U	
206-44-0	-----fluoranthene	9.8	U	
129-00-0	-----pyrene	9.8	U	
56-55-3	-----benzo (a) anthracene	9.8	U	
218-01-9	-----chrysene	9.8	U	
205-99-2	-----benzo (b) fluoranthene	9.8	U	
207-08-9	-----benzo (k) fluoranthene	9.8	U	
50-32-8	-----benzo (a) pyrene	9.8	U	
193-39-5	-----indeno (1,2,3-cd) pyrene	9.8	U	
53-70-3	-----dibenz (a,h) anthracene	9.8	U	
191-24-2	-----benzo (g,h,i) perylene	9.8	U	

DATA VALIDATION COPY

Client: Science Applications International Corp.
P.O. Box 2502
800 Oak Ridge Turnpike
Oak Ridge, Tennessee 37831
Contact: Ms. Lorene Rollins
Project Description: CAP-Part A for UST Sites (Task Order No. 8)

cc: SAIC00598

Report Date: October 08, 1998

Page 1 of 1

Sample ID : 600411
Lab ID : 9809639-04
Matrix : Soil
Date Collected : 09/18/98
Date Received : 09/21/98
Priority : Routine
Collector : Client

Parameter	Qualifier	Result	DL	RL	Units	DF	Analyst	Date	Time	Batch	M
General Chemistry											
Total Rec. Petro. Hydrocarbons	U	2.00	2.11	10.6	mg/kg	1.0	AAT	10/06/98	1100	132776	1

M = Method

Method-Description

M 1

EPA 418.1 Modified

Notes:

The qualifiers in this report are defined as follows:

ND indicates that the analyte was not detected at a concentration greater than the detection limit.

J indicates presence of analyte at a concentration less than the reporting limit (RL) and greater than the detection limit (DL).

U indicates that the analyte was not detected at a concentration greater than the detection limit.

* indicates that a quality control analyte recovery is outside of specified acceptance criteria.

This data report has been prepared and reviewed

in accordance with General Engineering Laboratories

standard operating procedures. Please direct

any questions to your Project Manager, Valerie Davis at (803) 769-7391.

Reviewed By



1A
VOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

600421

Lab Name: GENERAL ENGINEERING LABOR Contract: NA

Lab Code: NA Case No.: NA SAS No.: NA SDG No.: FS4B03S

Matrix: (soil/water) SOIL Lab Sample ID: 9809639-18

Sample wt/vol: 10.0 (g/mL) G Lab File ID: 2C4010

Level: (low/med) LOW Date Received: 09/21/98

% Moisture: not dec. 6 Date Analyzed: 10/01/98

GC Column: J&W DB-624 (PID) ID: 0.53 (mm) Dilution Factor: 1.0

Soil Extract Volume: _____ (mL) Soil Aliquot Volume: _____ (uL)

CAS NO.	COMPOUND	CONCENTRATION UNITS: (ug/L or ug/Kg) UG/KG	Q
---------	----------	---	---

71-43-2-----	Benzene	2.1	U
108-88-3-----	Toluene	2.3	U
100-41-4-----	Ethylbenzene	2.1	U
1330-20-7-----	Xylenes (total)	6.4	U

01100

FORM I VOA

1B
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

600421

Lab Name: GENERAL ENGINEERING LABOR Contract: NA

Lab Code: NA Case No.: NA SAS No.: NA SDG No.: FS4B03S

Matrix: (soil/water) SOIL Lab Sample ID: 9809639-18

Sample wt/vol: 30.4 (g/mL) G Lab File ID: 2M425

Level: (low/med) LOW Date Received: 09/21/98

% Moisture: 6 decanted: (Y/N) N Date Extracted: 09/23/98

Concentrated Extract Volume: 1.00 (mL) Date Analyzed: 09/24/98

Injection Volume: 1.0 (uL) Dilution Factor: 1.0

GPC Cleanup: (Y/N) N pH: 7.0

CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/KG

CAS NO. COMPOUND Q

91-20-3-----	naphthalene	350	U
91-58-7-----	2-chloronaphthalene	350	U
209-96-8-----	acenaphthylene	350	U
83-32-9-----	acenaphthene	350	U
86-73-7-----	fluorene	350	U
85-01-8-----	phenanthrene	350	U
120-12-7-----	anthracene	350	U
206-44-0-----	fluoranthene	350	U
129-00-0-----	pyrene	350	U
56-55-3-----	benzo (a) anthracene	350	U
218-01-9-----	chrysene	350	U
205-99-2-----	benzo (b) fluoranthene	350	U
207-08-9-----	benzo (k) fluoranthene	350	U
50-32-8-----	benzo (a) pyrene	350	U
193-39-5-----	indeno (1,2,3-cd) pyrene	350	U
53-70-3-----	dibenz (a,h) anthracene	350	U
191-24-2-----	benzo (g,h,i) perylene	350	U

FORM I SV-1

OLM03.0

Client: Science Applications International Corp.
P.O. Box 2502
800 Oak Ridge Turnpike
Oak Ridge, Tennessee 37831
Contact: Ms. Lorene Rollins
Project Description: CAP-Part A for UST Sites (Task Order No. 8)

cc: SAIC00598

Report Date: October 08, 1998

Page 1 of 1

Sample ID : 600421
Lab ID : 9809639-18
Matrix : Soil
Date Collected : 09/18/98
Date Received : 09/21/98
Priority : Routine
Collector : Client

Parameter	Qualifier	Result	DL	RL	Units	DF	Analyst	Date	Time	Batch	M
General Chemistry											
Total Rec. Petro. Hydrocarbons		23.9	J	FQ, FQS, IQ2	mg/kg	1.0	AAT	10/06/98	1100	132776	1

M = Method

Method-Description

M 1

EPA 418.1 Modified

Notes:

The qualifiers in this report are defined as follows:

ND indicates that the analyte was not detected at a concentration greater than the detection limit.

J indicates presence of analyte at a concentration less than the reporting limit (RL) and greater than the detection limit (DL).

U indicates that the analyte was not detected at a concentration greater than the detection limit.

* indicates that a quality control analyte recovery is outside of specified acceptance criteria.

This data report has been prepared and reviewed
in accordance with General Engineering Laboratories
standard operating procedures. Please direct
any questions to your Project Manager, Valerie Davis at (803) 769-7391.

Reviewed By



Sample ID: 9809639-18

Client ID: 600421

Contract: SAIC00598

Lab Code: GEL

Case No.:

SAS No.:

Matrix: SOIL

Date Received: 9/21/98

Level: LOW

% Solids: 94.00

CAS No.	Analyte	Concentration	Units	C	Qual	M	DL	Instrument ID	Analytical Run
7439-92-1	Lead	3.4	mg/kg			P	0.15	TJA61 Trace2 ICPAES	980924-1

Color Before:

Clarity Before:

Texture:

Color After:

Clarity After:

Artifacts:

Comments:

1A
VOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

600511

Lab Name: GENERAL ENGINEERING LABOR Contract: NA

Lab Code: NA Case No.: NA SAS No.: NA SDG No.: FS4B03S

Matrix: (soil/water) SOIL Lab Sample ID: 9809639-12

Sample wt/vol: 10.0 (g/mL) G Lab File ID: 2C404

Level: (low/med) LOW Date Received: 09/21/98

% Moisture: not dec. 11 Date Analyzed: 10/01/98

GC Column: J&W DB-624 (PID) ID: 0.53 (mm) Dilution Factor: 1.0

Soil Extract Volume: _____ (ml) Soil Aliquot Volume: _____ (uL)

CAS NO. COMPOUND CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/KG Q

71-43-2-----Benzene	2.2	U
108-88-3-----Toluene	4.0	
100-41-4-----Ethylbenzene	2.2	U
1330-20-7-----Xylenes (total)	6.7	U

U
U
U
U

FORM I VOA

1B
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

600511

Lab Name: GENERAL ENGINEERING LABOR Contract: NA

Lab Code: NA Case No.: NA SAS No.: NA SDG No.: FS4B03S

Matrix: (soil/water) SOIL Lab Sample ID: 9809639-12

Sample wt/vol: 30.4 (g/mL) G Lab File ID: 2M419

Level: (low/med) LOW Date Received: 09/21/98

% Moisture: 11 decanted: (Y/N) N Date Extracted: 09/23/98

Concentrated Extract Volume: 1.00 (mL) Date Analyzed: 09/24/98

Injection Volume: 1.0 (uL) Dilution Factor: 1.0

GPC Cleanup: (Y/N) N pH: 7.0

CAS NO. COMPOUND CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/KG Q

91-20-3	-----naphthalene	370	U
91-58-7	-----2-chloronaphthalene	370	U
209-96-8	-----acenaphthylene	370	U
83-32-9	-----acenaphthene	370	U
86-73-7	-----fluorene	370	U
85-01-8	-----phenanthrene	370	U
120-12-7	-----anthracene	370	U
206-44-0	-----fluoranthene	370	U
129-00-0	-----pyrene	370	U
56-55-3	-----benzo (a) anthracene	370	U
218-01-9	-----chrysene	370	U
205-99-2	-----benzo (b) fluoranthene	370	U
207-08-9	-----benzo (k) fluoranthene	370	U
50-32-8	-----benzo (a) pyrene	370	U
193-39-5	-----indeno (1,2,3-cd) pyrene	370	U
53-70-3	-----dibenz (a,h) anthracene	370	U
191-24-2	-----benzo (g,h,i) perylene	370	U

FORM I SV-1

OLM03.0

DATA VALIDATION
COPI

Client: Science Applications International Corp.
P.O. Box 2502
800 Oak Ridge Turnpike
Oak Ridge, Tennessee 37831
Contact: Ms. Lorene Rollins
Project Description: CAP-Part A for UST Sites (Task Order No. 8)

cc: SAIC00598

Report Date: October 08, 1998

Page 1 of 1

Sample ID : 600511
Lab ID : 9809639-12
Matrix : Soil
Date Collected : 09/18/98
Date Received : 09/21/98
Priority : Routine
Collector : Client

Parameter	Qualifier	Result	DL	RL	Units	DF	Analyst	Date	Time	Batch	M
General Chemistry											
Total Rec. Petro. Hydrocarbons		27.8	2.23	11.2	mg/kg	1.0	AAT	10/06/98	1100	132776	1

M = Method	Method-Description
M 1	EPA 418.1 Modified

Notes:

The qualifiers in this report are defined as follows:

ND indicates that the analyte was not detected at a concentration greater than the detection limit.

J indicates presence of analyte at a concentration less than the reporting limit (RL) and greater than the detection limit (DL).

U indicates that the analyte was not detected at a concentration greater than the detection limit.

* indicates that a quality control analyte recovery is outside of specified acceptance criteria.

This data report has been prepared and reviewed
in accordance with General Engineering Laboratories
standard operating procedures. Please direct
any questions to your Project Manager, Valerie Davis at (803) 769-7391.

Reviewed By



9809639-12

1A
VOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

600521

Lab Name: GENERAL ENGINEERING LABOR Contract: NA

Lab Code: NA Case No.: NA SAS No.: NA SDG No.: FS4B04S

Matrix: (soil/water) SOIL Lab Sample ID: 9809641-05

Sample wt/vol: 10.0 (g/mL) G Lab File ID: 2B5010

Level: (low/med) LOW Date Received: 09/21/98

% Moisture: not dec. 13 Date Analyzed: 09/25/98

GC Column: J&W DB-624 (PID) ID: 0.53 (mm) Dilution Factor: 1.0

Soil Extract Volume: _____ (ml) Soil Aliquot Volume: _____ (uL)

CAS NO.	COMPOUND	CONCENTRATION UNITS: (ug/L or ug/Kg) UG/KG	Q
---------	----------	---	---

71-43-2-----Benzene	2.3	U	
108-88-3-----Toluene	2.3	U	
100-41-4-----Ethylbenzene	2.3	U	
1330-20-7-----Xylenes (total)	6.9	U	

U
↓

FORM I VOA

DATA VALIDATION
COPY

1B
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

600521

Lab Name: GENERAL ENGINEERING LABOR Contract: NA

Lab Code: NA Case No.: NA SAS No.: NA SDG No.: FS4B04S

Matrix: (soil/water) SOIL Lab Sample ID: 9809641-05

Sample wt/vol: 30.1 (g/mL) G Lab File ID: 7M515

Level: (low/med) LOW Date Received: 09/21/98

% Moisture: 13 decanted: (Y/N) N Date Extracted: 09/23/98

Concentrated Extract Volume: 1.00 (mL) Date Analyzed: 09/24/98

Injection Volume: 1.0 (uL) Dilution Factor: 1.0

GPC Cleanup: (Y/N) N pH: 7.0

CAS NO. COMPOUND CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/KG Q

91-20-3	-----naphthalene	382	U
91-58-7	-----2-chloronaphthalene	382	U
208-96-8	-----acenaphthylene	382	U
83-32-9	-----acenaphthene	382	U
86-73-7	-----fluorene	382	U
85-01-8	-----phenanthrene	382	U
120-12-7	-----anthracene	382	U
206-44-0	-----fluoranthene	382	U
129-00-0	-----pyrene	382	U
56-55-3	-----benzo (a) anthracene	382	U
218-01-9	-----chrysene	382	U
205-99-2	-----benzo (b) fluoranthene	382	U
207-08-9	-----benzo (k) fluoranthene	382	U
50-32-8	-----benzo (a) pyrene	382	U
193-39-5	-----indeno (1,2,3-cd) pyrene	382	U
53-70-3	-----dibenz (a,h) anthracene	382	U
191-24-2	-----benzo (g,h,i) perylene	382	U

FORM I SV-1

OLM03.0

Client: Science Applications International Corp.
P.O. Box 2502
800 Oak Ridge Turnpike
Oak Ridge, Tennessee 37831

Contact: Ms. Lorene Rollins

Project Description: CAP-Part A for UST Sites (Task Order No. 8)

cc: SAIC00598

Report Date: October 08, 1998

Page 1 of 1

Sample ID : 600521
Lab ID : 9809641-05
Matrix : Soil
Date Collected : 09/18/98
Date Received : 09/21/98
Priority : Routine
Collector : Client

Parameter	Qualifier	Result	DL	RL	Units	DF	Analyst	Date	Time	Batch	M
General Chemistry											
Total Rec. Petro. Hydrocarbons	J	7.02	2.27	11.5	mg/kg	1.0	AAT	10/06/98	1100	132809	1

UJ F01, F06, I02

M = Method

Method-Description

M 1

EPA 418.1 Modified

Notes:

The qualifiers in this report are defined as follows:

ND indicates that the analyte was not detected at a concentration greater than the detection limit.

J indicates presence of analyte at a concentration less than the reporting limit (RL) and greater than the detection limit (DL).

U indicates that the analyte was not detected at a concentration greater than the detection limit.

* indicates that a quality control analyte recovery is outside of specified acceptance criteria.

This data report has been prepared and reviewed
in accordance with General Engineering Laboratories
standard operating procedures. Please direct
any questions to your Project Manager, Valerie Davis at (803) 769-7391.

Reviewed By



9809641-05

DATA VALIDATION
COPY

Form 1: Inorganic Analyses Data Sheet

SDG No.: FS4B04S

Method Type: Total Metals

Sample ID: 9809641-05

Client ID: 600521

Contract: SAIC00598

Lab Code: GEL

Case No.:

SAS No.:

Matrix: SOIL

Date Received: 9/21/98

Level: LOW

% Solids: 87.00

CAS No.	Analyte	Concentration	Units	C	Qual	M	DL	Instrument ID	Analytical Run
7439-92-1	Lead	3.2	mg/kg			P	0.16	TJA61 Trace2 ICPAES	980924-1

Color Before:

Clarity Before:

Texture:

Color After:

Clarity After:

Artifacts:

Comments:

1A
VOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

600611

Lab Name: GENERAL ENGINEERING LABOR Contract: NA

Lab Code: NA Case No.: NA SAS No.: NA SDG No.: FS4B03S

Matrix: (soil/water) SOIL Lab Sample ID: 9809639-08

Sample wt/vol: 10.0 (g/mL) G Lab File ID: 2C3019

Level: (low/med) LOW Date Received: 09/21/98

% Moisture: not dec. 4 Date Analyzed: 09/30/98

GC Column: J&W DB-624(PID) ID: 0.53 (mm) Dilution Factor: 1.0

Soil Extract Volume: _____(ml) Soil Aliquot Volume: _____(uL)

CAS NO.	COMPOUND	CONCENTRATION UNITS:		Q
		(ug/L or ug/Kg)	UG/KG	
71-43-2-----	Benzene	2.1	U	U U U U
108-88-3-----	Toluene	11.1	U	
100-41-4-----	Ethylbenzene	2.1	U	
1330-20-7-----	Xylenes (total)	6.2	U	

FORM I VOA

1B
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

600611

Lab Name: GENERAL ENGINEERING LABOR Contract: NA
 Lab Code: NA Case No.: NA SAS No.: NA SDG No.: FS4B03S
 Matrix: (soil/water) SOIL Lab Sample ID: 9809639-08
 Sample wt/vol: 30.4 (g/mL) G Lab File ID: 2M505
 Level: (low/med) LOW Date Received: 09/21/98
 % Moisture: 4 decanted: (Y/N) N Date Extracted: 09/23/98
 Concentrated Extract Volume: 1.00 (mL) Date Analyzed: 09/25/98
 Injection Volume: 1.0 (uL) Dilution Factor: 4.0
 GPC Cleanup: (Y/N) N pH: 7.0

CAS NO.	COMPOUND	CONCENTRATION UNITS: (ug/L or ug/Kg) UG/KG	Q
91-20-3	-----naphthalene	1370	U
91-58-7	-----2-chloronaphthalene	1370	U
209-96-8	-----acenaphthylene	1370	U
83-32-9	-----acenaphthene	1370	U
86-73-7	-----fluorene	1370	U
85-01-8	-----phenanthrene	1370	U
120-12-7	-----anthracene	1370	U
206-44-0	-----fluoranthene	1370	U
129-00-0	-----pyrene	1370	U
56-55-3	-----benzo (a) anthracene	1370	U
218-01-9	-----chrysene	1370	U
205-99-2	-----benzo (b) fluoranthene	1370	U
207-08-9	-----benzo (k) fluoranthene	1370	U
50-32-8	-----benzo (a) pyrene	1370	U
193-39-5	-----indeno (1,2,3-cd) pyrene	1370	U
53-70-3	-----dibenz (a,h) anthracene	1370	U
191-24-2	-----benzo (g,h,i) perylene	1370	U

FORM I SV-1

OLM03.0

Client: Science Applications International Corp.
P.O. Box 2502
800 Oak Ridge Turnpike
Oak Ridge, Tennessee 37831
Contact: Ms. Lorene Rollins
Project Description: CAP-Part A for UST Sites (Task Order No. 8)

cc: SAIC00598

Report Date: October 08, 1998

Page 1 of 1

Sample ID : 600611
Lab ID : 9809639-08
Matrix : Soil
Date Collected : 09/18/98
Date Received : 09/21/98
Priority : Routine
Collector : Client

Parameter	Qualifier	Result	DL	RL	Units	DF	Analyst	Date	Time	Batch	M
General Chemistry											
Total Rec. Petro. Hydrocarbons		2660	51.5	260	mg/kg	25	AAT	10/06/98	1100	132776	1

M = Method

Method-Description

M 1

EPA 418.1 Modified

Notes:

The qualifiers in this report are defined as follows:

ND indicates that the analyte was not detected at a concentration greater than the detection limit.

J indicates presence of analyte at a concentration less than the reporting limit (RL) and greater than the detection limit (DL).

U indicates that the analyte was not detected at a concentration greater than the detection limit.

* indicates that a quality control analyte recovery is outside of specified acceptance criteria.

This data report has been prepared and reviewed

in accordance with General Engineering Laboratories

standard operating procedures. Please direct

any questions to your Project Manager, Valerie Davis at (803) 769-7391.

Reviewed By



080639.08

1A
VOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

600621

Lab Name: GENERAL ENGINEERING LABOR Contract: NA

Lab Code: NA Case No.: NA SAS No.: NA SDG No.: FS4B04S

Matrix: (soil/water) SOIL Lab Sample ID: 9809641-01

Sample wt/vol: 10.0 (g/mL) G Lab File ID: 2B506

Level: (low/med) LOW Date Received: 09/21/98

% Moisture: not dec. 12 Date Analyzed: 09/25/98

GC Column: J&W DB-624 (PID) ID: 0.53 (mm) Dilution Factor: 1.0

Soil Extract Volume: _____ (ml) Soil Aliquot Volume: _____ (uL)

CAS NO.	COMPOUND	CONCENTRATION UNITS: (ug/L or ug/Kg) UG/KG	Q
---------	----------	---	---

71-43-2-----Benzene	2.3	U	21120
108-88-3-----Toluene	4.0	U	
100-41-4-----Ethylbenzene	2.3	U	
1330-20-7-----Xylenes (total)	6.8	U	

FORM I VOA

✓ K01, K02

DATA VALIDATION
COPY

1B
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

600621

Lab Name: GENERAL ENGINEERING LABOR Contract: NA

Lab Code: NA Case No.: NA SAS No.: NA SDG No.: FS4B04S

Matrix: (soil/water) SOIL Lab Sample ID: 9809641-01

Sample wt/vol: 30.1 (g/mL) G Lab File ID: 7M511

Level: (low/med) LOW Date Received: 09/21/98

% Moisture: 12 decanted: (Y/N) N Date Extracted: 09/23/98

Concentrated Extract Volume: 1.00 (mL) Date Analyzed: 09/24/98

Injection Volume: 1.0 (uL) Dilution Factor: 1.0

GPC Cleanup: (Y/N) N pH: 7.0

CAS NO. COMPOUND CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/KG Q

91-20-3-----	naphthalene	378	U
91-58-7-----	2-chloronaphthalene	378	U
208-96-8-----	acenaphthylene	378	U
83-32-9-----	acenaphthene	378	U
86-73-7-----	fluorene	378	U
85-01-8-----	phenanthrene	378	U
120-12-7-----	anthracene	378	U
206-44-0-----	fluoranthene	378	U
129-00-0-----	pyrene	378	U
56-55-3-----	benzo (a) anthracene	378	U
218-01-9-----	chrysene	378	U
205-99-2-----	benzo (b) fluoranthene	378	U
207-08-9-----	benzo (k) fluoranthene	378	U
50-32-8-----	benzo (a) pyrene	378	U
193-39-5-----	indeno (1,2,3-cd) pyrene	378	U
53-70-3-----	dibenz (a,h) anthracene	378	U
191-24-2-----	benzo (g,h,i) perylene	378	U

U
↓

Client: Science Applications International Corp.
P.O. Box 2502
800 Oak Ridge Turnpike
Oak Ridge, Tennessee 37831

Contact: Ms. Lorene Rollins

Project Description: CAP-Part A for UST Sites (Task Order No. 8)

cc: SAIC00598

Report Date: October 08, 1998

Page 1 of 1

Sample ID : 600621
Lab ID : 9809641-01
Matrix : Soil
Date Collected : 09/18/98
Date Received : 09/21/98
Priority : Routine
Collector : Client

Parameter	Qualifier	Result	DL	RL	Units	DF	Analyst	Date	Time	Batch	M
General Chemistry											
Total Rec. Petro. Hydrocarbons		265 J	5.62	28.4	mg/kg	2.5	AAT	10/06/98	1100	132809	1

M = Method

Method-Description

M 1

EPA 418.1 Modified

Notes:

The qualifiers in this report are defined as follows:

ND indicates that the analyte was not detected at a concentration greater than the detection limit.

J indicates presence of analyte at a concentration less than the reporting limit (RL) and greater than the detection limit (DL).

U indicates that the analyte was not detected at a concentration greater than the detection limit.

* indicates that a quality control analyte recovery is outside of specified acceptance criteria.

This data report has been prepared and reviewed

in accordance with General Engineering Laboratories

standard operating procedures. Please direct

any questions to your Project Manager, Valerie Davis at (803) 769-7391.

Reviewed By



080641.01

DATA VALIDATION
COPY

Form 1: Inorganic Analyses Data Sheet

SDG No. FS48045

Method Type: Total Metals

Sample ID: 9809641-01

Client ID: 600621

Contract: SAIC00598

Lab Code: GEL

Case No.:

SAS No.:

Matrix: SOIL

Date Received: 9/21/98

Level: LOW

% Solids: 88.00

CAS No.	Analyte	Concentration	Units	C	Qual	M	DL	Instrument ID	Analytical Run
7439-92-1	Lead	3.5	mg/kg			P	0.16	TJA61 Trace21CPAES	980924-1

Color Before:

Clarity Before:

Texture:

Color After:

Clarity After:

Artifacts:

Comments:



Science Applications International Corporation
An Employee-Owned Company

800 Oak Ridge Turnpike, Oak Ridge, TN 37831 (423) 481-4600

CHAIN OF CUSTODY RECORD

COC NO.: GAS08

PROJECT NAME: 46-6MMU-Investigations		CAP-A Options	
PROJECT NUMBER: 01-0331-04-2328-208		9405-Z10	
PROJECT MANAGER: Jeff Longaker		Patty Stoll	
Sampler (Signature) <i>David Lumsley</i> (Printed Name)			
Sample ID	Date Collected	Time Collected	Matrix
600722	9/20/98	1535	water
600312	9/20/98	1435	water
580311	9/17/98	1310	soil
600313	9/20/98	1739	
600311	9/20/98	1739	
600411	9/14/98	1044	
620511	9/14/98	1445	
630311	9/19/98	810	
620311	9/20/98	1013	
600611	9/18/98	1235	
630611	9/19/98	920	
630313	9/19/98	810	
630411	9/19/98	1020	

REQUESTED PARAMETERS									
TOTAL LEAD									
SVOC									
VOC									
RCRA METALS									
PAH									
BTEX									
PAH, TPH									
No. of Bottles/Vials									
OVA SCREENING									
OBSERVATIONS, COMMENTS, SPECIAL INSTRUCTIONS									
LABORATORY NAME: General Engineering Laboratory									
LABORATORY ADDRESS: 2040 Savage Road Charleston, SC 29417									
PHONE NO: (803) 556-8171									
Cooler Temperature: 4°C									
FEDEX NUMBER:									

RELINQUISHED BY: <i>David Lumsley</i>	DATE/TIME: 9/21/98	RECEIVED BY: <i>Shirley</i>	DATE/TIME: 9/21/98
COMPANY NAME: SASC	1145	COMPANY NAME: <i>Shirley</i>	
RELINQUISHED BY: <i>Patricia</i>	DATE/TIME: 9/21/98	RECEIVED BY:	DATE/TIME:
COMPANY NAME: <i>Patricia</i>	1145	COMPANY NAME:	
RELINQUISHED BY: <i>Patricia</i>	DATE/TIME: 9/21/98	RECEIVED BY:	DATE/TIME:
COMPANY NAME: <i>Patricia</i>	1545	COMPANY NAME:	

PERMEABILITY TEST ANALYSIS (ASTM D5084)

Project : Fort Stewart
 Location of Project : CAP Part A
 Description of Soil : Gray Silty Sand

Job # : 98066
 Date of Testing: 12/14-18/98
 Tested by: BV/CA
 Boring # :
 Sample # : 600831
 Sample Depth : 4.0-6.2 ft.

Sample Type (Undisturbed or Remolded)
 Standard Proctor:
 Maximim Dry Density: pcf
 Optimum Moisture Content: %

% Sample Compaction: %
 Sample Dry Density: pcf
 Sample Moisture Content: %
 Sample Wet Density: pcf

Sample Permeation:

De-Aired Water
 % Saturation: 98 %
 Cell Pressure: 80 psi
 Lower Pressure: 77 psi
 Upper Pressure: 75 psi
 Gradient: 19.55

Sample Dimensions		
	Before	After
Length (cm)	7.20	7.20
Diameter (cm)	4.80	4.70
Water Content (%)	17.21	21.8
Weight (g)	264.0	263.7

Constant Head Calculation:

$$K = [V(t_1, t_2) LR_T] / [P_b A t] \text{ (cm/sec)}$$

$V(t_1, t_2)$ = Volume of flow from t_1 to t_2 (cm³)

L = Length of Sample = 7.20 cm

A = Area of Sample = 18.1 cm²

t = $t_2 - t_1$ (sec)

P_b = Bias Pressure = 2 psi x 70.37 cm/psi (cm - H₂O) 140.74 cm

R_T = Temperature correction = 0.953

t_2 (sec)	t_1 (sec)	$(t_2 - t_1)$ (sec)	V (cm ³)	$[LR_T] / [P_b A]$ (cm ²)	K (cm/sec)
265	250	15	0.3	2.69E-03	5.39E-05
280	265	15	0.2	2.69E-03	3.59E-05
295	280	15	0.2	2.69E-03	3.59E-05
310	295	15	0.1	2.69E-03	1.80E-05


$$K_{avg} = \underline{3.59E-05} \text{ cm/sec}$$

*CATLIN Engineers and Scientists
 Geotechnical Laboratories*

SPECIFIC GRAVITY AND POROSITY

PROJECT: Fort Stewart
 LOCATION OF PROJECT: CAP Part A
 DESCRIPTION OF SOIL: Gray Silty Sand
 TESTED BY: FB

JOB NO.: 98066
 SAMPLE NO.: 600831
 DEPTH OF SAMPLE: 4.0-6.2 ft.
 DATE OF TESTING: 12/14/98



$$\begin{aligned} W &= 1.06195 \\ W_w &= W - W_s = 0.13743 \\ W_s &= Y_d \cdot V = 0.9245 \\ V &= 0.00856 \\ V_w &= W_w / Y_w = 0.0022 \\ V_s &= W_s / G_s \cdot Y_w = 0.0056 \\ V_G &= V - (V_s + V_w) = 0.00077 \\ V_v &= V_G + V_w = 0.0030 \end{aligned}$$

MEASUREMENTS OF TUBE/CAN

HEIGHT= 13.4 cm
 DIAMETER= 4.8 cm

WT. OF TUBE/CAN + WET SOIL= 689.90 g
 WEIGHT OF TUBE/CAN= 188.2 g
 WEIGHT OF WET SOIL= 481.70 g
 W = 1.06195 lb

CALCULATED VOLUME OF TUBE/CAN

V = 242.48 cm³
 0.00856 ft³

MOISTURE CONTENT

$M_{cws} = 18.80$ g $M_c = 15.40$ g
 $M_{cds} = 18.36$ g $M_s = 2.96$ g
 $M_w = 0.44$ g $w = 14.9$ %

Wet Density, $Y_m = W / V$

Dry Density, $Y_d = W_s / V$ or $Y_d = Y_m / (1 + w)$	
<u>double check</u>	$Y_d = Y_m / (1 + w)$
$Y_d = W_s / V$	$Y_m = 124.00$ lbs/ft ³
$Y_d = 107.95$ lbs/ft ³	$Y_d = 107.95$ lbs/ft ³

Void Ratio, $e = V_v / V_s$
 $e = 0.5326$

Porosity, $n = V_v / V$
 $n = 0.35$

Specific Gravity = 2.65

Degree of Saturation, $S = V_w / V_v$
 $S = 0.7397$

GRAIN SIZE ANALYSIS-SIEVE (ASTM D422)

Project: Fort Stewart	Job No.: 98066
Project Location: Cap Part A	Sample No.: 600831
Sample Description: Gray Silty Sand	Sample Depth:.
	Boring No.:
Tested By: FB	Date of Testing: 12/10/98

Mcws	Mcds	Mc : A6	Mw	Ms	w%	Mws	Ms
18.80	18.36	15.40	0.44	2.96	14.9	200.80	174.81

Sieve No.	Diam. (mm)	Wt. retained	% retained	E % retained	% passing
3	76.2	0	0.00	0.00	100.00
2	50.8	0	0.00	0.00	100.00
1 1/2	25.4	0	0.00	0.00	100.00
3/4	19.05	0	0.00	0.00	100.00
3/8	9.51	0	0.00	0.00	100.00
4	4.76	11.39	6.52	6.52	93.48
10	2.00	4.13	2.36	8.88	91.12
20	0.841	5.83	3.33	12.21	87.79
40	0.42	25.5	14.59	26.80	73.20
60	0.25	50.99	29.17	55.97	44.03
140	0.106	32.38	18.52	74.49	25.51
200	0.074	0.8	0.46	74.95	25.05
pan	—	0.04	0.02	74.97	25.03
total		131.06			

CATLIN Engineers and Scientists
Geotechnical Laboratories

**SOIL ANALYTICAL DATA
OBTAINED DURING UST 28B
CLOSURE ACTIVITIES
(July 1996)**

THIS PAGE INTENTIONALLY LEFT BLANK

**SPECIALIZED ASSAYS, INC.**

2960 Foster Creighton Dr.
P.O. Box 40566
Nashville, TN 37204-0566
Phone 1-615-726-0177

ANALYTICAL REPORT

DIRECTOR U.S. ARMY CORPS ENG. 5394
CESAD LABORATORY
611 SOUTH COBB DRIVE
MARIETTA, GA 30060-3172

Sample Location: 29441 282 T1 S-1
FT. STEWART

Lab Number: 96-A040479

Sampler: BOBBI THORN

Date Collected: 7/ 2/96

Date Received: 7/ 6/96

Time Collected: 11:45

Time Received: 8:30

Sample type: Soil

Organics Reference Data

P Blank 56284SBB
C Tune, BNA DF0711B
Calibration Check, BNA CC0711B

Percent solids: 86.1

SEMIVOLATILE ORGANICS and PESTICIDE/PCB's

Analyte	Result	Flag	DF	Units	Date	Time	Analyst	Method
Acenaphthene	1940	U	5	ug/kg	7/12/96	10:31	M.Goodrich	8270B
Acenaphthylene	1940	U	5	ug/kg	7/12/96	10:31	M.Goodrich	8270B
Anthracene	1940	U	5	ug/kg	7/12/96	10:31	M.Goodrich	8270B
Benzo(a)anthracene	1940	U	5	ug/kg	7/12/96	10:31	M.Goodrich	8270B
Benzo(a)pyrene	1940	U	5	ug/kg	7/12/96	10:31	M.Goodrich	8270B
Benzo(b)fluoranthene	1940	U	5	ug/kg	7/12/96	10:31	M.Goodrich	8270B
Benzo(g,h,i)perylene	1940	U	5	ug/kg	7/12/96	10:31	M.Goodrich	8270B
Benzo(k)fluoranthene	778	J	5	ug/kg	7/12/96	10:31	M.Goodrich	8270B
4-Bromobenzyloxyphenyl ether	1940	U	5	ug/kg	7/12/96	10:31	M.Goodrich	8270B
Butylbenzylphthalate	1940	U	5	ug/kg	7/12/96	10:31	M.Goodrich	8270B
Carbazole	1940	U	5	ug/kg	7/12/96	10:31	M.Goodrich	8270B
4-Chloro-3-methylphenol	1940	U	5	ug/kg	7/12/96	10:31	M.Goodrich	8270B
4-Chloroaniline	1940	U	5	ug/kg	7/12/96	10:31	M.Goodrich	8270B
1-(2-Chloroethoxy)methane	1940	U	5	ug/kg	7/12/96	10:31	M.Goodrich	8270B
1-(2-Chloroethyl) ether	1940	U	5	ug/kg	7/12/96	10:31	M.Goodrich	8270B
1-(2-Chloroisopropyl) ether	1940	U	5	ug/kg	7/12/96	10:31	M.Goodrich	8270B
3-Chloronaphthalene	1940	U	5	ug/kg	7/12/96	10:31	M.Goodrich	8270B

**SPECIALIZED ASSAYS, INC.**

2960 Foster Creighton Dr.
P.O. Box 40566
Nashville, TN 37204-0566
Phone 1-615-726-0177

ANALYTICAL REPORT

DIRECTOR U.S. ARMY CORPS ENG. 5394
CESAD LABORATORY
611 SOUTH COBB DRIVE
MARIETTA, GA 30060-3172

Sample Location: 29441 28B T1 S-1
FT. STEWART

Lab Number: 96-A040479

Sampler: BOBBI THORN

Date Collected: 7/ 2/96

Date Received: 7/ 6/96

Time Collected: 11:45

Time Received: 8:30

Sample type: Soil

SEMIVOLATILE ORGANICS and PESTICIDE/PCB's

byte	Result	Flag	DF	Units	Date	Time	Analyst	Method
2-Chlorophenol	1940	U	5	ug/kg	7/12/96	10:31	M.Goodrich	8270B
4-Chlorophenylphenylether	1940	U	5	ug/kg	7/12/96	10:31	M.Goodrich	8270B
Chrysene	1940	U	5	ug/kg	7/12/96	10:31	M.Goodrich	8270B
Dibenzofuran	1940	U	5	ug/kg	7/12/96	10:31	M.Goodrich	8270B
Dibenz(a,h)anthracene	1940	U	5	ug/kg	7/12/96	10:31	M.Goodrich	8270B
1,2-Dichlorobenzene	1940	U	5	ug/kg	7/12/96	10:31	M.Goodrich	8270B
1,3-Dichlorobenzene	1940	U	5	ug/kg	7/12/96	10:31	M.Goodrich	8270B
1,4-Dichlorobenzene	1940	U	5	ug/kg	7/12/96	10:31	M.Goodrich	8270B
3,3'-Dichlorobenzidine	3870	U	5	ug/kg	7/12/96	10:31	M.Goodrich	8270B
2,4-Dichlorophenol	1940	U	5	ug/kg	7/12/96	10:31	M.Goodrich	8270B
Diethylphthalate	1940	U	5	ug/kg	7/12/96	10:31	M.Goodrich	8270B
2,4-Dimethylphenol	1940	U	5	ug/kg	7/12/96	10:31	M.Goodrich	8270B
Dimethylphthalate	1940	U	5	ug/kg	7/12/96	10:31	M.Goodrich	8270B
Di-n-butylphthalate	1940	U	5	ug/kg	7/12/96	10:31	M.Goodrich	8270B
4,6-Dinitro-2-methylphenol	4840	U	5	ug/kg	7/12/96	10:31	M.Goodrich	8270B
2,4-Dinitrophenol	4840	U	5	ug/kg	7/12/96	10:31	M.Goodrich	8270B
2,4-dinitrotoluene	1940	U	5	ug/kg	7/12/96	10:31	M.Goodrich	8270B
2,6-Dinitrotoluene	1940	U	5	ug/kg	7/12/96	10:31	M.Goodrich	8270B
Di-n-octylphthalate	1940	U	5	ug/kg	7/12/96	10:31	M.Goodrich	8270B
Fluoranthene	523	J	5	ug/kg	7/12/96	10:31	M.Goodrich	8270B
Fluorene	1940	U	5	ug/kg	7/12/96	10:31	M.Goodrich	8270B
Hexachlorobenzene	1940	U	5	ug/kg	7/12/96	10:31	M.Goodrich	8270B
Hexachlorobutadiene	1940	U	5	ug/kg	7/12/96	10:31	M.Goodrich	8270B
Hexachlorocyclopentadiene	1940	U	5	ug/kg	7/12/96	10:31	M.Goodrich	8270B
Hexachloroethane	1940	U	5	ug/kg	7/12/96	10:31	M.Goodrich	8270B

**SPECIALIZED ASSAYS, INC.**

2960 Foster Creighton Dr.
P.O. Box 40566
Nashville, TN 37204-0566
Phone 1-615-726-4177

ANALYTICAL REPORT

DIRECTOR U.S. ARMY CORPS ENG. 5394
CESAD LABORATORY
611 SOUTH COBB DRIVE
MARIETTA, GA 30060-3172

Sample Location: 29441 283 T1 S-1
FT. STEWART

Lab Number: 96-A040479

Sampler: BOBBI THORN

Date Collected: 7/ 2/96

Date Received: 7/ 6/96

Time Collected: 11:45

Time Received: 8:20

Sample type: Soil

SEMIVOLATILE ORGANICS and PESTICIDE/PCB's

Byte	Result	Flag	DF	Units	Date	Time	Analyst	Meth.
Indeno(1,2,3-cd)pyrene	1940	U	5	ug/kg	7/12/96	10:31	M.Goodrich	8270B
Isophorone	1940	U	5	ug/kg	7/12/96	10:31	M.Goodrich	8270B
2-Methylnaphthalene	1940	U	5	ug/kg	7/12/96	10:31	M.Goodrich	8270B
2-Methylphenol	1940	U	5	ug/kg	7/12/96	10:31	M.Goodrich	8270B
m,p-Methylphenol	1940	U	5	ug/kg	7/12/96	10:31	M.Goodrich	8270B
Naphthalene	1940	U	5	ug/kg	7/12/96	10:31	M.Goodrich	8270B
2-Nitroaniline	4840	U	5	ug/kg	7/12/96	10:31	M.Goodrich	8270B
3-Nitroaniline	4840	U	5	ug/kg	7/12/96	10:31	M.Goodrich	8270B
4-Nitroaniline	4840	U	5	ug/kg	7/12/96	10:31	M.Goodrich	8270B
Nitrobenzene	1590	U	5	ug/kg	7/12/96	10:31	M.Goodrich	8270B
2-Nitrophenol	1940	U	5	ug/kg	7/12/96	10:31	M.Goodrich	8270B
4-Nitrophenol	4840	U	5	ug/kg	7/12/96	10:31	M.Goodrich	8270B
N-nitrosodi-n-propylamine	1940	U	5	ug/kg	7/12/96	10:31	M.Goodrich	8270B
N-nitrosodiphenylamine	1940	U	5	ug/kg	7/12/96	10:31	M.Goodrich	8270B
Pentachlorophenol	4840	U	5	ug/kg	7/12/96	10:31	M.Goodrich	8270B
Phenanthrene	1940	U	5	ug/kg	7/12/96	10:31	M.Goodrich	8270B
Phenol	1940	U	5	ug/kg	7/12/96	10:31	M.Goodrich	8270B
Pyrene	581.	J	5	ug/kg	7/12/96	10:31	M.Goodrich	8270B
Bis(2-ethylhexyl)phthalate	929.	J	5	ug/kg	7/12/96	10:31	M.Goodrich	8270B
1,2,4-Trichlorobenzene	1940	U	5	ug/kg	7/12/96	10:31	M.Goodrich	8270B
2,4,5-Trichlorophenol	4840	U	5	ug/kg	7/12/96	10:31	M.Goodrich	8270B
2,4,6-Trichlorophenol	1940	U	5	ug/kg	7/12/96	10:31	M.Goodrich	8270B
action, SNA.s	Completed			ug/kg	7/10/96	14:55	C.Serenser	3550

**SPECIALIZED ASSAYS, INC.**

2960 Foster Creighton Dr.
P.O. Box 40566
Nashville, TN 37204-0566
Phone 1-615-726-4177

ANALYTICAL REPORT

DIRECTOR U.S. ARMY CORPS ENG. 5394
CESAD LABORATORY
611 SOUTH COBB DRIVE
MARIETTA, GA 30060-3172

Sample Location: 29441 28B T1 S-1
FT. STEWART

Lab Number: 96-A040479

Sampler: BOBBI THORN

Date Collected: 7/ 2/96

Date Received: 7/ 6/96

Time Collected: 11:45

Time Received: 8:30

Sample type: Soil

UNDERGROUND STORAGE TANK RESULTS

Analyte	Result	Units	PQL	Dil	Date	Time	Analyst	Method
				Factor				
Benzene	< 0.116	mg/kg	0.116	1	7/ 8/96	1:30	Holingwrth	8020
Toluene	< 0.116	mg/kg	0.116	1	7/ 8/96	1:30	Holingwrth	8020
Ethylbenzene	< 0.116	mg/kg	0.116	1	7/ 8/96	1:30	Holingwrth	8020
Xylenes, total	< 0.116	mg/kg	0.116	1	7/ 8/96	1:30	Holingwrth	8020
TRPH	14600	mg/kg	11.6	1	7/ 9/96	15:01	M.Himelick	9073

Sample Extraction Data

BNA's Extracted 7/10/96 Wt extracted: 30.0 gm Extract Volume: 1.0 ml

**** QUALITY CONTROL DATA ******Surrogate Recoveries**

Surrogate	% Recovery	Target Range
BRO Surrogate, soil	111.	50 - 150
NA Surrogate, Nitrobenzene	54.0	23 - 120
BNA Surr., 2-Fluorobiphenyl	55.0	30 - 115
BNA Surrogate, Terphenyl d14	62.0	18 - 140



SPECIALIZED ASSAYS, INC.

2960 Foster Creighton Dr.
P.O. Box 40566
Nashville, TN 37204-0566
Phone 1-615-726-0177

ANALYTICAL REPORT

DIRECTOR U.S. ARMY CORPS ENG. 5394
CESAD LABORATORY
611 SOUTH COBB DRIVE
MARIETTA, GA 30060-3172

Lab Number: 96-A040479

Sample ID: 29441 2SB T1 S-1

Date Collected: 7/ 2/96

Project: CALL #269

Time Collected: 11:45

Project Name:

Date Received: 7/ 6/96

Sampler: BOBBI THORN

Time Received: 8:30

State Certification:

Sample Type: Soil

Site I.D.:

**** QUALITY CONTROL DATA ****

Surrogate Recoveries

Surrogate	% Recovery	Target Range
BNA Surrogate, Phenol d5	47.0	10 - 115
BNA Surrogate, 2-Fluorophenol	41.0	20 - 121
BNA Surrogate, 2,4,6-Tribromophenol	60.0	19 - 122

Report Approved By:

Michael H. Dunn

Report Date: 7/16/96

Theodore J. Duello, Ph.D.
Michael H. Dunn, M.S.
Danny B. Hale, M.S.

**SPECIALIZED ASSAYS, INC.**

2960 Foster Creighton Dr.
P.O. Box 40566
Nashville, TN 37204-0566
Phone 1-615-726-0177

ANALYTICAL REPORT

DIRECTOR U.S. ARMY CORPS ENG. 5394
CESAD LABORATORY
611 SOUTH COBB DRIVE
MARIETTA, GA 30060-3172

Sample Location: 29442 28B T1 S-2
FT. STEWART

Lab Number: 96-A040480

Sampler: BOBBI THORN

Date Collected: 7/ 2/96

Date Received: 7/ 6/96

Time Collected: 11:50

Time Received: 8:30

Sample type: Soil

Organics Reference Data

RM Blank 5628458B
J Tune, BNA DF0711B
Calibration Check, BNA CC0711B

Percent solids: 94.7

SEMIVOLATILE ORGANICS and PESTICIDE/PCB's

Analyte	Result	Flag	DF	Units	Date	Time	Analyst	Method
Acenaphthene	1760	U	5	ug/kg	7/12/96	11:07	M.Goodrich	8270B
Acenaphthylene	1760	U	5	ug/kg	7/12/96	11:07	M.Goodrich	8270B
Anthracene	1760	U	5	ug/kg	7/12/96	11:07	M.Goodrich	8270B
Benzo(a)anthracene	1760	U	5	ug/kg	7/12/96	11:07	M.Goodrich	8270B
Benzo(a)pyrene	1760	U	5	ug/kg	7/12/96	11:07	M.Goodrich	8270B
Benzo(b)fluoranthene	1760	U	5	ug/kg	7/12/96	11:07	M.Goodrich	8270B
Benzo(g,h,i)perylene	1760	U	5	ug/kg	7/12/96	11:07	M.Goodrich	8270B
Benzo(k)fluoranthene	1760	U	5	ug/kg	7/12/96	11:07	M.Goodrich	8270B
4-Bromophenylphenylether	1760	U	5	ug/kg	7/12/96	11:07	M.Goodrich	8270B
Butylbenzylphthalate	1760	U	5	ug/kg	7/12/96	11:07	M.Goodrich	8270B
Carbazole	1760	U	5	ug/kg	7/12/96	11:07	M.Goodrich	8270B
4-Chloro-3-methylphenol	1760	U	5	ug/kg	7/12/96	11:07	M.Goodrich	8270B
4-Chloroaniline	1760	U	5	ug/kg	7/12/96	11:07	M.Goodrich	8270B
2-(2-Chloroethoxy)methane	1760	U	5	ug/kg	7/12/96	11:07	M.Goodrich	8270B
2-Chloroethyl ether	1760	U	5	ug/kg	7/12/96	11:07	M.Goodrich	8270B
2-(2-Chloroisopropyl) ether	1760	U	5	ug/kg	7/12/96	11:07	M.Goodrich	8270B
2-Chloronaphthalene	1760	U	5	ug/kg	7/12/96	11:07	M.Goodrich	8270B

**SPECIALIZED ASSAYS, INC.**

2960 Foster Creighton Dr.
P.O. Box 40566
Nashville, TN 37204-0566
Phone (615) 726-0177

ANALYTICAL REPORT

DIRECTOR U.S. ARMY CORPS ENG. 5394
CESAD LABORATORY
611 SOUTH COBB DRIVE
MARIETTA, GA 30060-3172

Sample Location: 29442 28B T1 S-2
FT. STEWART

Lab Number: 96-A040480

Sampler: BOBBI THORN

Date Collected: 7/ 2/96

Date Received: 7/ 6/96

Time Collected: 11:50

Time Received: 8:30

Sample type: Soil

SEMIVOLATILE ORGANICS and PESTICIDE/PCB's

Byte	Result	Flag	DF	Units	Date	Time	Analyst	Met:
2-Chlorophenol	1760	U	5	ug/kg	7/12/96	11:07	M.Goodrich	8270B
4-Chlorophenylphenylether	1760	U	5	ug/kg	7/12/96	11:07	M.Goodrich	8270B
Chrysene	1760	U	5	ug/kg	7/12/96	11:07	M.Goodrich	8270B
Dibenzofuran	1760	U	5	ug/kg	7/12/96	11:07	M.Goodrich	8270B
Dibenz(a,h)anthracene	1760	U	5	ug/kg	7/12/96	11:07	M.Goodrich	8270B
1,2-Dichlorobenzene	1760	U	5	ug/kg	7/12/96	11:07	M.Goodrich	8270B
1,3-Dichlorobenzene	1760	U	5	ug/kg	7/12/96	11:07	M.Goodrich	8270B
1,4-Dichlorobenzene	1760	U	5	ug/kg	7/12/96	11:07	M.Goodrich	8270B
3,3'-Dichlorobenzidine	3520	U	5	ug/kg	7/12/96	11:07	M.Goodrich	8270B
2,4-Dichlorophenol	1760	U	5	ug/kg	7/12/96	11:07	M.Goodrich	8270B
Diethylphthalate	1760	U	5	ug/kg	7/12/96	11:07	M.Goodrich	8270B
2,4-Dimethylphenol	1760	U	5	ug/kg	7/12/96	11:07	M.Goodrich	8270B
Dimethylphthalate	1760	U	5	ug/kg	7/12/96	11:07	M.Goodrich	8270B
Di-n-butylphthalate	1760	U	5	ug/kg	7/12/96	11:07	M.Goodrich	8270B
4,6-Dinitro-2-methylphenol	4380	U	5	ug/kg	7/12/96	11:07	M.Goodrich	8270B
2,4-Dinitrophenol	4380	U	5	ug/kg	7/12/96	11:07	M.Goodrich	8270B
2,4-dinitrotoluene	1760	U	5	ug/kg	7/12/96	11:07	M.Goodrich	8270B
2,6-Dinitrotoluene	1760	U	5	ug/kg	7/12/96	11:07	M.Goodrich	8270B
Di-n-octylphthalate	1760	U	5	ug/kg	7/12/96	11:07	M.Goodrich	8270B
Fluoranthene	1760	U	5	ug/kg	7/12/96	11:07	M.Goodrich	8270B
Fluorene	1760	U	5	ug/kg	7/12/96	11:07	M.Goodrich	8270B
Hexachlorobenzene	1760	U	5	ug/kg	7/12/96	11:07	M.Goodrich	8270B
Hexachlorobutadiene	1760	U	5	ug/kg	7/12/96	11:07	M.Goodrich	8270B
Hexachlorocyclopentadiene	1760	U	5	ug/kg	7/12/96	11:07	M.Goodrich	8270B
Hexachloroethane	1760	U	5	ug/kg	7/12/96	11:07	M.Goodrich	8270B

**SPECIALIZED ASSAYS, INC.**

2960 Foster Creighton Dr.
P.O. Box 40566
Nashville, TN 37204-0566
Phone (615) 726-0177

ANALYTICAL REPORT

DIRECTOR U.S. ARMY CORPS ENG. 5394
CECAD LABORATORY
611 SOUTH COBB DRIVE
MARIETTA, GA 30060-3172

Sample Location: 29442 283 T1 S-2
FT. STEWART

Lab Number: 96-A040480

Sampler: BOBBI THORN

Date Collected: 7/ 2/96

Date Received: 7/ 6/96

Time Collected: 11:50

Time Received: 8:30

Sample type: Soil

SEMIVOLATILE ORGANICS and PESTICIDE/PCB's

yte	Result	Flag	DF	Units	Date	Time	Analyst	Method
Indeno(1,2,3-cd)pyrene	1760	U	5	ug/kg	7/12/96	11:07	M.Goodrich	8270B
Isoproporone	1760	U	5	ug/kg	7/12/96	11:07	M.Goodrich	8270B
2-Methylnaphthalene	1760	U	5	ug/kg	7/12/96	11:07	M.Goodrich	8270B
2-Methylphenol	1760	U	5	ug/kg	7/12/96	11:07	M.Goodrich	8270B
m,3-Methylphenol	1760	U	5	ug/kg	7/12/96	11:07	M.Goodrich	8270B
Naphthalene	1760	U	5	ug/kg	7/12/96	11:07	M.Goodrich	8270B
2-Nitroaniline	1760	U	5	ug/kg	7/12/96	11:07	M.Goodrich	8270B
3-Nitroaniline	4380	U	5	ug/kg	7/12/96	11:07	M.Goodrich	8270B
4-Nitroaniline	4380	U	5	ug/kg	7/12/96	11:07	M.Goodrich	8270B
Nitrobenzene	1760	U	5	ug/kg	7/12/96	11:07	M.Goodrich	8270B
2-Nitrophenol	1760	U	5	ug/kg	7/12/96	11:07	M.Goodrich	8270B
4-Nitrophenol	1760	U	5	ug/kg	7/12/96	11:07	M.Goodrich	8270B
N-nitrosodi-n-propylamine	1760	U	5	ug/kg	7/12/96	11:07	M.Goodrich	8270B
N-nitrosodiphenylamine	1760	U	5	ug/kg	7/12/96	11:07	M.Goodrich	8270B
Pentachlorophenol	4380	U	5	ug/kg	7/12/96	11:07	M.Goodrich	8270B
Phenanthrene	1760	U	5	ug/kg	7/12/96	11:07	M.Goodrich	8270B
Phenol	1760	U	5	ug/kg	7/12/96	11:07	M.Goodrich	8270B
Pyrene	1760	U	5	ug/kg	7/12/96	11:07	M.Goodrich	8270B
3-(2-ethylhexyl)phthalate	1060	J	5	ug/kg	7/12/96	11:07	M.Goodrich	8270B
1,2,4-Trichlorobenzene	1760	U	5	ug/kg	7/12/96	11:07	M.Goodrich	8270B
2,4,5-Trichlorophenol	4380	U	5	ug/kg	7/12/96	11:07	M.Goodrich	8270B
2,4,6-Trichlorophenol	1760	U	5	ug/kg	7/12/96	11:07	M.Goodrich	8270B
action, BNA.s	Completed			ug/kg	7/10/96	14:55	C.Gerenser	3550



SPECIALIZED ASSAYS, INC.

2960 Foster Creighton Dr.
P.O. Box 40566
Nashville, TN 37204-0566
Phone 1-615-726-0177

ANALYTICAL REPORT

DIRECTOR U.S. ARMY CORPS ENG. 5394
CESAD LABORATORY
611 SOUTH COBB DRIVE
MARLETTA, GA 30060-3172

Sample Location: 29442 28B T1 S-2
FT. STEWART

Lab Number: 96-A040480

Sampler: BOBBI THORN

Date Collected: 7/ 2/96

Date Received: 7/ 6/96

Time Collected: 11:50

Time Received: 8:30

Sample type: Soil

UNDERGROUND STORAGE TANK RESULTS

analyte	Result	Units	PQL	Dil Factor	Date	Time	Analyst	Method
Benzene	< 0.106	mg/kg	0.106	1	7/ 8/96	2:02	Holingwrth	8020
Toluene	< 0.106	mg/kg	0.106	1	7/ 8/96	2:02	Holingwrth	8020
Ethylbenzene	< 0.106	mg/kg	0.106	1	7/ 8/96	2:02	Holingwrth	8020
Xylenes, total	< 0.106	mg/kg	0.106	1	7/ 8/96	2:02	Holingwrth	8020
TRPH	13200	mg/kg	10.6	1	7/ 9/96	15:02	M.Himelick	9073

Sample Extraction Data

BNA's Extracted 7/10/96 Wt extracted: 30.0 gm Extract Volume: 1.0 ml

** QUALITY CONTROL DATA **

Surrogate Recoveries

Surrogate	% Recovery	Target Range
GRO Surrogate, soil	119.	50 - 150
NA Surrogate, Nitrobenzene	50.0	23 - 120
BNA Surr., 2-Fluorodiphenyl	55.0	30 - 115
BNA Surrogate, Terphenyl d14	63.0	18 - 140



SPECIALIZED ASSAYS, INC.

2960 Foster Creighton Dr.
P.O. Box 40566
Nashville, TN 37204-0566
Phone 1-615-726-0177

ANALYTICAL REPORT

DIRECTOR U.S. ARMY CORPS ENG. 5394
CESAD LABORATORY
611 SOUTH COBB DRIVE
MARIETTA, GA 30060-3172

Lab Number: 96-A040480

Sample ID: 29442 28B T1 S-2

Date Collected: 7/ 2/96

Project: CALL #269

Time Collected: 11:50

Project Name:

Date Received: 7/ 6/96

Sampler: BCEBI THORN

Time Received: 8:30

State Certification:

Sample Type: Soil

Site I.D.:

*** QUALITY CONTROL DATA ***

Surrogate Recoveries

Surrogate	% Recovery	Target Range
BNA Surrogate, Phenol d5	45.0	10 - 115
BNA Surrogate, 2-Fluorophenol	40.0	20 - 121
BNA Surrogate, 2,4,6-Tribromophenol	59.0	19 - 122

Report Approved By:

Michael A. Dunn

Report Date: 7/16/96

Theodore J. Duello, Ph.D.
Michael H. Dunn, M.S.
Danny B. Hale, M.S.

THIS PAGE INTENTIONALLY LEFT BLANK

APPENDIX VI

ALTERNATE THRESHOLD LEVEL (ATL)
CALCULATIONS

THIS PAGE INTENTIONALLY LEFT BLANK

The contaminant concentrations in soil did not exceed their respective soil threshold levels, except for the two closure samples with elevated benzene detection limits. Thus, no alternate threshold levels were calculated.

The maximum benzene concentration in groundwater was 171 µg/L in May 1998. The modeling of benzene estimated infinite dilution attenuation factors (DAFs) for the drainage ditch and Mill Creek indicating that contamination will never reach these locations, thus no alternate concentration limits were developed for these locations. The results of fate and transport modeling are presented in Attachment C.

THIS PAGE INTENTIONALLY LEFT BLANK

APPENDIX VII

MONITORING WELL DETAILS

THIS PAGE INTENTIONALLY LEFT BLANK

Monitoring wells were not installed as part of the CAP-Part A investigation. Temporary piezometers were installed at the UST 28B site for the determination of free product. Refer to Figure 5 (Appendix I) for locations and screened intervals.

THIS PAGE INTENTIONALLY LEFT BLANK

APPENDIX VIII
GROUNDWATER LABORATORY RESULTS

THIS PAGE INTENTIONALLY LEFT BLANK

TABLE VIII-A. Summary of Groundwater Analytical Results

Station:			60-01	60-02	60-03	60-04	60-05
Sample ID:	Federal	In Stream	600112	600212	600312	600412	600512
Sample Interval (ft):	SDWA	Water Quality	2.0 - 12.0	0.0 - 12.0	0.1 - 10.1	0.0 - 10.0	0.0 - 9.5
Collection Date:	MCLs ¹	Standards ²	10-May-98	10-May-98	18-Sep-98	18-Sep-98	18-Sep-98
Units:	(ug/L)	(ug/L)	(ug/L)	(ug/L)	(ug/L)	(ug/L)	(ug/L)
VOLATILE ORGANIC COMPOUNDS							
Benzene	5	71.28	128 =	171 =	2 U	2 U	2 U
Toluene	1000	200000	424 =	512 =	2 U	2 U	2 U
Ethylbenzene	700	28718	50 U	17.8 =	2 U	2 U	2 U
Xylenes, Total	10000	NRC	88.8 J	92 =	6 U	6 U	6 U
POLYNUCLEAR AROMATIC HYDROCARBONS							
2-Chloronaphthalene	NRC	NRC	10 U	42.1 U	12.5 UJ	10.8 U	10.1 U
Acenaphthene	NRC	NRC	10 U	42.1 U	12.5 UJ	10.8 U	10.1 U
Acenaphthylene	NRC	NRC	10 U	42.1 U	12.5 UJ	10.8 U	10.1 U
Anthracene	NRC	110000	10 U	42.1 U	12.5 UJ	10.8 U	10.1 U
Benzo(a)anthracene	NRC	0.0311	10 U	42.1 U	12.5 UJ	10.8 U	10.1 U
Benzo(a)pyrene	0.2	0.0311	10 U	42.1 U	12.5 UJ	10.8 U	10.1 U
Benzo(b)fluoranthene	NRC	NRC	10 U	42.1 U	12.5 UJ	10.8 U	10.1 U
Benzo(g,h,i)perylene	NRC	NRC	10 U	42.1 U	12.5 UJ	10.8 U	10.1 U
Benzo(k)fluoranthene	NRC	0.0311	10 U	42.1 U	12.5 UJ	10.8 U	10.1 U
Chrysene	NRC	0.0311	10 U	42.1 U	12.5 UJ	10.8 U	10.1 U
Dibenzo(a,h)anthracene	NRC	0.0311	10 U	42.1 U	12.5 UJ	10.8 U	10.1 U
Fluoranthene	NRC	370	10 U	42.1 U	12.5 UJ	10.8 U	10.1 U
Fluorene	NRC	14000	10 U	42.1 U	12.5 UJ	10.8 U	10.1 U
Indeno(1,2,3-cd)pyrene	NRC	0.0311	10 U	42.1 U	12.5 UJ	10.8 U	10.1 U
Naphthalene	NRC	NRC	10 U	42.1 U	12.5 UJ	10.8 U	10.1 U
Phenanthrene	NRC	NRC	10 U	42.1 U	12.5 UJ	10.8 U	10.1 U
Pyrene	NRC	11000	10 U	42.1 U	12.5 UJ	10.8 U	10.1 U

NOTES:

May 1998 sampling was performed prior to the new CAP-Part A guidance that was published in May 1998; thus, the new SW-846 analytical methods were not used during that sampling event.

Contract for the September 1998 sampling was prior to the new CAP-Part A guidance that was published in May 1998; thus, the new SW-846 analytical methods were not used during that sampling event.

Analytical data for QA/QC samples 600214 (duplicate), 600616 (equipment rinsate), and 600714 (duplicate) are contained within this appendix, but are not summarized in this table.

Elevated PAH detection limits are a result of associated organic content such as TPH or other organic compounds. During extraction of the PAH compounds, all other organic compounds are extracted, causing a wide range of organic compounds to be present; thus, the target PAHs become small peaks in the chromatograph. As a result, the laboratory dilutes the concentrate, in turn elevating the detection limit.

¹ U.S. Environmental Protection Agency Safe Drinking Water Act Maximum Contaminant Level

² GA EPD water quality standards (Chapter 391-3-6.03)

Bold values exceed MCLs

Laboratory Qualifiers

- U Indicates the compound was not detected above the reported quantitation limit.
- UJ Indicates that the compound was not detected above an approximated sample quantitation limit.
- J Indicates the value for the compound is an estimated value.
- = Indicates the compound was detected at the concentration reported.

TABLE VIII-A. Summary of Groundwater Analytical Results (continued)

Station:			60-06	60-07	60-07	60-07
Sample ID:	Federal	In Stream	600612	600712	600722	600732
Sample Interval (ft):	SDWA	Water Quality	0.0 - 10.0	6.0 - 10.0	11.0 - 15.0	16.0 - 20.0
Collection Date:	MCLs ¹	Standards ²	18-Sep-98	20-Sep-98	20-Sep-98	20-Sep-98
Units:	(ug/L)	(ug/L)	(ug/L)	(ug/L)	(ug/L)	(ug/L)
<i>VOLATILE ORGANIC COMPOUNDS</i>						
Benzene	5	71.28	2 U	2 U	2 U	2 U
Toluene	1000	200000	2 U	2 U	2 U	2 U
Ethylbenzene	700	28718	2 U	2 U	2 U	2 U
Xylenes, Total	10000	NRC	6 U	6 U	6 U	6 U
<i>POLYNUCLEAR AROMATIC HYDROCARBONS</i>						
2-Chloronaphthalene	NRC	NRC	10 U	10.4 U	10.3 U	10.4 U
Acenaphthene	NRC	NRC	10 U	10.4 U	10.3 U	10.4 U
Acenaphthylene	NRC	NRC	10 U	10.4 U	10.3 U	10.4 U
Anthracene	NRC	110000	10 U	10.4 U	10.3 U	10.4 U
Benzo(a)anthracene	NRC	0.0311	10 U	10.4 U	10.3 U	10.4 U
Benzo(a)pyrene	0.2	0.0311	10 U	10.4 U	10.3 U	10.4 U
Benzo(b)fluoranthene	NRC	NRC	10 U	10.4 U	10.3 U	10.4 U
Benzo(g,h,i)perylene	NRC	NRC	10 U	10.4 U	10.3 U	10.4 U
Benzo(k)fluoranthene	NRC	0.0311	10 U	10.4 U	10.3 U	10.4 U
Chrysene	NRC	0.0311	10 U	10.4 U	10.3 U	10.4 U
Dibenzo(a,h)anthracene	NRC	0.0311	10 U	10.4 U	10.3 U	10.4 U
Fluoranthene	NRC	370	10 U	10.4 U	10.3 U	10.4 U
Fluorene	NRC	14000	10 U	10.4 U	10.3 U	10.4 U
Indeno(1,2,3-cd)pyrene	NRC	0.0311	10 U	10.4 U	10.3 U	10.4 U
Naphthalene	NRC	NRC	10 U	10.4 U	10.3 U	10.4 U
Phenanthrene	NRC	NRC	10 U	10.4 U	10.3 U	10.4 U
Pyrene	NRC	11000	10 U	10.4 U	10.3 U	10.4 U

NOTES:

May 1998 sampling was performed prior to the new CAP-Part A guidance that was published in May 1998; thus, the new SW-846 analytical methods were not used during that sampling event.

Contract for the September 1998 sampling was prior to the new CAP-Part A guidance that was published in May 1998; thus, the new SW-846 analytical methods were not used during that sampling event.

Analytical data for QA/QC samples 600214 (duplicate), 600616 (equipment rinsate), and 600714 (duplicate) are contained within this appendix, but are not summarized in this table.

Elevated PAH detection limits are a result of associated organic content such as TPH or other organic compounds. During extraction of the PAH compounds, all other organic compounds are extracted, causing a wide range of organic compounds to be present; thus, the target PAHs become small peaks in the chromatograph. As a result, the laboratory dilutes the concentrate, in turn elevating the detection limit.

¹ U.S. Environmental Protection Agency Safe Drinking Water Act Maximum Contaminant Level

² GA EPD water quality standards (Chapter 391-3-6.03)

Bold values exceed MCLs

Laboratory Qualifiers

- U Indicates the compound was not detected above the reported quantitation limit.
- UJ Indicates that the compound was not detected above an approximated sample quantitation limit.
- J Indicates the value for the compound is an estimated value.
- = Indicates the compound was detected at the concentration reported.

1A
VOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

600112

Lab Name: GENERAL ENGINEERING LABOR Contract: NA

Lab Code: NA Case No.: NA SAS No.: NA SDG No.: FS4013W

Matrix: (soil/water) GROUNDH2O Lab Sample ID: 9805307-20

Sample wt/vol: 10.00 (g/ml) ML Lab File ID: 2J1030

Level: (low/med) LOW Date Received: 05/11/98

% Moisture: not dec. Date Analyzed: 05/19/98

GC Column: J&W DB-624(PID) ID: 0.53 (mm) Dilution Factor: 25.0

Soil Extract Volume: (ml) Soil Aliquot Volume: (uL)

CAS NO.	COMPOUND	CONCENTRATION UNITS: (ug/L or ug/Kg) UG/L	Q
71-43-2-----	Benzene	128	
108-88-3-----	Toluene	424	
100-41-4-----	Ethylbenzene	50.0	U
1330-20-7-----	Xylenes (total)	88.8	J

11/12/98

DATA VALIDATION
COPY

FORM I VOA

1B
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

600112

Lab Name: GENERAL ENGINEERING LABOR Contract: NA

Lab Code: NA Case No.: NA SAS No.: NA

SDG No.: FS4011W

Matrix: (soil/water) GROUNDH2O

Lab Sample ID: 9805303-12

Sample wt/vol: 1000 (g/mL) ML

Lab File ID: 4T418

Level: (low/med)

Date Received: 05/11/98

% Moisture: _____ decanted **DATA VALIDATION COPY**

Date Extracted: 05/12/98

Concentrated Extract Volume: 1.00 (mL)

Date Analyzed: 05/15/98

Injection Volume: 1.0 (uL)

Dilution Factor: 1.0

GPC Cleanup: (Y/N) N pH: 7.0

CAS NO.

COMPOUND

CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/L

Q

91-20-3-----	naphthalene	10.0	U
91-58-7-----	2-chloronaphthalene	10.0	U
208-96-8-----	acenaphthylene	10.0	U
83-32-9-----	acenaphthene	10.0	U
86-73-7-----	fluorene	10.0	U
85-01-8-----	phenanthrene	10.0	U
120-12-7-----	anthracene	10.0	U
206-44-0-----	fluoranthene	10.0	U
129-00-0-----	pyrene	10.0	U
56-55-3-----	benzo (a) anthracene	10.0	U
218-01-9-----	chrysene	10.0	U
205-99-2-----	benzo (b) fluoranthene	10.0	U
207-08-9-----	benzo (k) fluoranthene	10.0	U
50-32-8-----	benzo (a) pyrene	10.0	U
193-39-5-----	indeno (1,2,3-cd) pyrene	10.0	U
53-70-3-----	dibenz (a,h) anthracene	10.0	U
191-24-2-----	benzo (g,h,i) perylene	10.0	U

FORM I SV-1

OLM03.0

1A
VOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

600212

Lab Name: GENERAL ENGINEERING LABOR Contract: NA

Lab Code: NA Case No.: NA SAS No.: NA

SDG No.: FS4015W

Matrix: (soil/water) GROUNDH2O

Lab Sample ID: 9805309-05

Sample wt/vol: 10.00 (g/ml) ML

Lab File ID: 2J3027

Level: (low/med) LOW

Date Received: 05/11/98

% Moisture: not dec. _____

Date Analyzed: 05/20/98

GC Column: J&W DB-624 (PID) ID: 0.53 (mm)

Dilution Factor: 5.0

Soil Extract Volume: _____ (ml)

Soil Aliquot Volume: _____ (uL)

CAS NO.	COMPOUND	CONCENTRATION UNITS: (ug/L or ug/Kg) UG/L	Q
71-43-2-----	Benzene	171	
108-88-3-----	Toluene	512	
100-41-4-----	Ethylbenzene	17.8	
1330-20-7-----	Xylenes (total)	92.0	

DATA VALIDATION
COPY

FORM I VOA

1B
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

600212

Lab Name: GENERAL ENGINEERING LABOR Contract: NA

Lab Code: NA

Case No.: NA

SAS No.: NA

SDG No.: FS4011W

Matrix: (soil/water) GROUNDH2O

Lab Sample ID: 9805303-20

Sample wt/vol: 950.0 (g/mL) ML

Lab File ID: 4U109

Level: (low/med) LOW

Date Received: 05/11/98

% Moisture: _____ decanted: (Y/N)

Date Extracted: 05/12/98

Concentrated Extract Volume: 1.00 (mL)

Date Analyzed: 05/18/98

Injection Volume: 1.0 (uL)

Dilution Factor: 4.0

GPC Cleanup: (Y/N) N pH: 7.0

**DATA VALIDATION
COPY**

CAS NO.	COMPOUND	CONCENTRATION UNITS: (ug/L or ug/Kg) UG/L	Q
91-20-3	-----naphthalene	42.1	U
91-58-7	-----2-chloronaphthalene	42.1	U
208-96-8	-----acenaphthylene	42.1	U
83-32-9	-----acenaphthene	42.1	U
86-73-7	-----fluorene	42.1	U
85-01-8	-----phenanthrene	42.1	U
120-12-7	-----anthracene	42.1	U
206-44-0	-----fluoranthene	42.1	U
129-00-0	-----pyrene	42.1	U
56-55-3	-----benzo(a)anthracene	42.1	U
218-01-9	-----chrysene	42.1	U
205-99-2	-----benzo(b)fluoranthene	42.1	U
207-08-9	-----benzo(k)fluoranthene	42.1	U
50-32-8	-----benzo(a)pyrene	42.1	U
193-39-5	-----indeno(1,2,3-cd)pyrene	42.1	U
53-70-3	-----dibenz(a,h)anthracene	42.1	U
191-24-2	-----benzo(g,h,i)perylene	42.1	U

FORM I SV-1

OLM03.0

1A
VOLATILE ORGANICS ANALYSIS DATA SHEET

DUPLICATE
EPA SAMPLE NO.

600214

Lab Name: GENERAL ENGINEERING LABOR Contract: NA
 Lab Code: NA Case No.: NA SAS No.: NA SDG No.: FS4015W
 Matrix: (soil/water) GROUNDH2O Lab Sample ID: 9805309-10
 Sample wt/vol: 10.00 (g/ml) ML Lab File ID: 2J3018
 Level: (low/med) LOW Date Received: 05/11/98
 % Moisture: not dec. Date Analyzed: 05/20/98
 GC Column: J&W DB-624 (PID) ID: 0.53 (mm) Dilution Factor: 10.0
 Soil Extract Volume: (ml) Soil Aliquot Volume: (uL)

CAS NO.	COMPOUND	CONCENTRATION UNITS: (ug/L or ug/Kg) UG/L	Q
71-43-2	Benzene	174	
108-88-3	Toluene	528	
100-41-4	Ethylbenzene	18.8	J
1330-20-7	Xylenes (total)	94.5	

11/11/98

DATA VALIDATION
COPY

FORM I VOA

DATA VALIDATION COPY

1B SEMI-VOLATILE ORGANICS ANALYSIS DATA SHEET

DUPLICATE
EPA SAMPLE NO.

600214

Lab Name: GENERAL ENGINEERING LABOR Contract: NA

Lab Code: NA Case No.: NA SAS No.: NA

SDG No.: FS4012W

Matrix: (soil/water) GROUNDH2O

Lab Sample ID: 9805304-01

Sample wt/vol: 250.0 (g/mL) ML

Lab File ID: 1T307

Level: (low/med) LOW

Date Received: 05/11/98

% Moisture: _____ decanted: (Y/N) _____

Date Extracted: 05/13/98

Concentrated Extract Volume: 0.50 (mL)

Date Analyzed: 05/13/98

Injection Volume: 1.0 (uL)

Dilution Factor: 1.0

GPC Cleanup: (Y/N) N pH: 7.0

CAS NO.

COMPOUND

CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/L

Q

91-20-3	-----naphthalene	20.0	U
91-58-7	-----2-chloronaphthalene	20.0	U
208-96-8	-----acenaphthylene	20.0	U
83-32-9	-----acenaphthene	20.0	U
86-73-7	-----fluorene	20.0	U
85-01-8	-----phenanthrene	20.0	U
120-12-7	-----anthracene	20.0	U
206-44-0	-----fluoranthene	20.0	U
129-00-0	-----pyrene	20.0	U
56-55-3	-----benzo (a) anthracene	20.0	U
218-01-9	-----chrysene	20.0	U
205-99-2	-----benzo (b) fluoranthene	20.0	U
207-08-9	-----benzo (k) fluoranthene	20.0	U
50-32-8	-----benzo (a) pyrene	20.0	U
193-39-5	-----indeno (1,2,3-cd) pyrene	20.0	U
53-70-3	-----dibenz (a,h) anthracene	20.0	U
191-24-2	-----benzo (g,h,i) perylene	20.0	U

FORM I SV-1

OLM03.0



800 Oak Ridge Turnpike, Oak Ridge, TN 37831 (423) 481-4600

CHAIN OF CUSTODY RECORD

COC NO.: SAB010

PROJECT NAME: Fort Stewart New CAP Part A UST Investigation 7605				REQUESTED PARAMETERS												LABORATORY NAME: General Engineering Laboratory						
PROJECT NUMBER: 01-0331-04-5305-200																LABORATORY ADDRESS: 2040 Savage Road Charleston, SC 29417						
PROJECT MANAGER: Petty Stoll																PHONE NO: (803) 556-8171						
Sampler (Signature)				[Printed Name]												OBSERVATIONS, COMMENTS, SPECIAL INSTRUCTIONS						
Sample ID	Date Collected	Time Collected	Matrix	BTEX	PAH	TOC	BTEX, GRO	PAH, DRO	PAH, DRO, Lead	PAH, TPH	PAH, TPH, Lead	PAH, TPH, Lead, TOC	No. of Bottles/Vials:									
730312	5/10/98	1445	water	1	1	1	1	1	1	1	1	1	1									
590112	5/10/98	1040	↓	2	2	2	2	2	2	2	2	2	2									
600112	5/10/98	1555		2	2	2	2	2	2	2	2	2	2									
690312	5/9/98	1620		2	2	2	2	2	2	2	2	2	2									
730112	5/10/98	1135		2	2	2	2	2	2	2	2	2	2									
540212	5/10/98	1150		2	2	2	2	2	2	2	2	2	2									
730410	5/10/98	1430	↓	2	2	2	2	2	2	2	2	2	2									
RECEIVED BY: [Signature] 5/11/98				RECEIVED BY:		Date/Time		Date/Time		TOTAL NUMBER OF CONTAINERS: 13		Cooler Temperature: 40C										
COMPANY NAME: SAIC				COMPANY NAME:		COMPANY NAME:		COMPANY NAME:		Cooler ID: #508		FEDEX NUMBER:										
RECEIVED BY: [Signature] 5-11-98				RELINQUISHED BY:		Date/Time		Date/Time														
COMPANY NAME: [Signature]				COMPANY NAME:		COMPANY NAME:		COMPANY NAME:														
RELINQUISHED BY: [Signature]				RECEIVED BY:		Date/Time		Date/Time														
COMPANY NAME: [Signature]				COMPANY NAME:		COMPANY NAME:		COMPANY NAME:														



CHAIN OF CUSTODY RECORD

COC NO.: 5713071

VIII-12



Science Applications International Corporation
An Employee-Owned Company

800 Oak Ridge Turnpike, Oak Ridge, TN 37831 (423) 481-4600

11035

CHAIN OF CUSTODY RECORD

COC NO.: SA B018

PROJECT NAME: Fort Stewart New CAP Part A UST Investigation 9805				REQUESTED PARAMETERS												LABORATORY NAME: General Engineering Laboratory	
PROJECT NUMBER: 01-0331-04 9805-200																LABORATORY ADDRESS: 2040 Savage Road Charleston, SC 29417	
PROJECT MANAGER: Patty Stoll																PHONE NO: (803) 556-8171	
Sampler (Signature) <i>Laura Lumley</i>																OBSERVATIONS, COMMENTS, SPECIAL INSTRUCTIONS (Impressure)	
Sample ID	Date Collected	Time Collected	Matrix	BTEX	PAH	TOC	BTEX, GRO	PAH, DRO	PAH, DRO, Lead	PAH, TPH	PAH, TPH, Lead	PAH, TPH, Lead, TOC	No. of Bottles/ Vials				
600112	5/10/98	1555	water	2	2	2	2	2	2	2	2	2	2	2	2		
760514	5/16/98	1745		2	2	2	2	2	2	2	2	2	2	2	2		
590112	5/10/98	1040		2	2	2	2	2	2	2	2	2	2	2	2		
760412	5/8/98	1345		2	2	2	2	2	2	2	2	2	2	2	2		
760532	5/8/98	1845		2	2	2	2	2	2	2	2	2	2	2	2		
600212	5/10/98	1630		2	2	2	2	2	2	2	2	2	2	2	2		
760522	5/8/98	1745		2	2	2	2	2	2	2	2	2	2	2	2		
640212	5/19/98	1530		2	2	2	2	2	2	2	2	2	2	2	2		
640112	5/19/98	1445		2	2	2	2	2	2	2	2	2	2	2	2		
760312	5/18/98	1630		2	2	2	2	2	2	2	2	2	2	2	2		
600214	5/10/98	1620		2	2	2	2	2	2	2	2	2	2	2	2		
760612	5/19/98	1930		2	2	2	2	2	2	2	2	2	2	2	2		
761012	5/10/98	1445		2	2	2	2	2	2	2	2	2	2	2	2		
RELINQUISHED BY: <i>Laura Lumley</i>	Date/Time 5/11/98	RECEIVED BY:		TOTAL NUMBER OF CONTAINERS:												Cooler Temperature: 40C	
COMPANY NAME: SAIC	1130	COMPANY NAME:		Cooler ID: #1388												FEDEX NUMBER:	
RELINQUISHED BY: <i>Shackles</i>	Date/Time 5/11/98	RELINQUISHED BY:		Date/Time													
COMPANY NAME: <i>SAIC</i>	1130	COMPANY NAME:		Date/Time													
RELINQUISHED BY:	Date/Time	RECEIVED BY:		Date/Time													
COMPANY NAME:		COMPANY NAME:		Date/Time													

1A
VOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

600312

Lab Name: GENERAL ENGINEERING LABOR Contract: NA

Lab Code: NA Case No.: NA SAS No.: NA SDG No.: FS4B06W

Matrix: (soil/water) WATER Lab Sample ID: 9809645-08

Sample wt/vol: 10.00 (g/ml) ML Lab File ID: 2B3018

Level: (low/med) LOW Date Received: 09/21/98

% Moisture: not dec. Date Analyzed: 09/23/98

GC Column: J&W DB-624 (PID) ID: 0.53 (mm) Dilution Factor: 1.0

Soil Extract Volume: (ml) Soil Aliquot Volume: (uL)

CAS NO. COMPOUND CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/L Q

71-43-2-----Benzene	2.0	U	U ↓
108-88-3-----Toluene	2.0	U	
100-41-4-----Ethylbenzene	2.0	U	
1330-20-7-----Xylenes (total)	6.0	U	

FORM I VOA

1B
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

600312RE

Lab Name: GENERAL ENGINEERING LABOR Contract: NA

Lab Code: NA Case No.: NA SAS No.: NA SDG No.: FS4B02W

Matrix: (soil/water) GROUNDH2O Lab Sample ID: 9809638-19

Sample wt/vol: 800.0 (g/mL) ML Lab File ID: 1N414

Level: (low/med) LOW Date Received: 09/21/98

% Moisture: _____ decanted: (Y/N) _____ Date Extracted: 09/29/98

Concentrated Extract Volume: 1.00 (mL) Date Analyzed: 10/01/98

Injection Volume: 1.0 (uL) Dilution Factor: 1.0

GPC Cleanup: (Y/N) N pH: 7.0

CAS NO. COMPOUND CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/L

91-20-3-----	naphthalene	12.5	U
91-58-7-----	2-chloronaphthalene	12.5	U
209-96-8-----	acenaphthylene	12.5	U
83-32-9-----	acenaphthene	12.5	U
86-73-7-----	fluorene	12.5	U
85-01-8-----	phenanthrene	12.5	U
120-12-7-----	anthracene	12.5	U
206-44-0-----	fluoranthene	12.5	U
129-00-0-----	pyrene	12.5	U
56-55-3-----	benzo (a) anthracene	12.5	U
218-01-9-----	chrysene	12.5	U
205-99-2-----	benzo (b) Fluoranthene	12.5	U
207-08-9-----	benzo (k) fluoranthene	12.5	U
50-32-8-----	benzo (a) pyrene	12.5	U
193-39-5-----	indeno (1,2,3-cd) pyrene	12.5	U
53-70-3-----	dibenz (a,h) anthracene	12.5	U
191-24-2-----	benzo (g,h,i) perylene	12.5	U

USE

WAD1

↓ ↓

FORM I SV-1

OLM03.0

DATA VALIDATED
000Y

1A
VOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

600412

Lab Name: GENERAL ENGINEERING LABOR Contract: NA

Lab Code: NA Case No.: NA SAS No.: NA SDG No.: FS4B06W

Matrix: (soil/water) WATER Lab Sample ID: 9809645-03

Sample wt/vol: 10.00 (g/ml) ML Lab File ID: 2B3012

Level: (low/med) LOW Date Received: 09/21/98

% Moisture: not dec. Date Analyzed: 09/23/98

GC Column: J&W DB-624 (PID) ID: 0.53 (mm) Dilution Factor: 1.0

Soil Extract Volume: (ml) Soil Aliquot Volume: (uL)

CAS NO. COMPOUND CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/L Q

71-43-2-----Benzene	2.0	U
108-88-3-----Toluene	2.0	U
100-41-4-----Ethylbenzene	2.0	U
1330-20-7-----Xylenes (total)	6.0	U

U
↓

FORM I VOA

1B
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

600412

Lab Name: GENERAL ENGINEERING LABOR Contract: NA

Lab Code: NA Case No.: NA SAS No.: NA SDG No.: FS4B01W

Matrix: (soil/water) GROUNDH2O Lab Sample ID: 9809637-03

Sample wt/vol: 930.0 (g/mL) ML Lab File ID: 4M410

Level: (low/med) LOW Date Received: 09/21/98

% Moisture: _____ decanted: (Y/N) _____ Date Extracted: 09/22/98

Concentrated Extract Volume: 1.00 (mL) Date Analyzed: 09/24/98

Injection Volume: 1.0 (uL) Dilution Factor: 1.0

GPC Cleanup: (Y/N) N pH: 7.0

CAS NO. COMPOUND CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/L Q

91-20-3-----	naphthalene	10.8	U
91-58-7-----	2-chloronaphthalene	10.8	U
209-96-8-----	acenaphthylene	10.8	U
83-32-9-----	acenaphthene	10.8	U
86-73-7-----	fluorene	10.8	U
85-01-8-----	phenanthrene	10.8	U
120-12-7-----	anthracene	10.8	U
206-44-0-----	fluoranthene	10.8	U
129-00-0-----	pyrene	10.8	U
56-55-3-----	benzo (a) anthracene	10.8	U
218-01-9-----	chrysene	10.8	U
205-99-2-----	benzo (b) fluoranthene	10.8	U
207-08-9-----	benzo (k) fluoranthene	10.8	U
50-32-8-----	benzo (a) pyrene	10.8	U
193-39-5-----	indeno (1,2,3-cd) pyrene	10.8	U
53-70-3-----	dibenz (a,h) anthracene	10.8	U
191-24-2-----	benzo (g,h,i) perylene	10.8	U

FORM I SV-1

OLM03.0

1A
VOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

600512

Lab Name: GENERAL ENGINEERING LABOR Contract: NA

Lab Code: NA Case No.: NA SAS No.: NA SDG No.: FS4B06W

Matrix: (soil/water) WATER Lab Sample ID: 9809645-07

Sample wt/vol: 10.00 (g/ml) ML Lab File ID: 2B3017

Level: (low/med) LOW Date Received: 09/21/98

% Moisture: not dec. _____ Date Analyzed: 09/23/98

GC Column: J&W DB-624 (PID) ID: 0.53 (mm) Dilution Factor: 1.0

Soil Extract Volume: _____ (ml) Soil Aliquot Volume: _____ (uL)

CAS NO. COMPOUND CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/L Q

71-43-2-----Benzene	2.0	U	U ↓
108-88-3-----Toluene	2.0	U	
100-41-4-----Ethylbenzene	2.0	U	
1330-20-7-----Xylenes (total)	6.0	U	

FORM I VOA

1B
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

600512

Lab Name: GENERAL ENGINEERING LABOR Contract: NA
 Lab Code: NA Case No.: NA SAS No.: NA SDG No.: FS4B01W
 Matrix: (soil/water) GROUNDH2O Lab Sample ID: 9809637-01
 Sample wt/vol: 990.0 (g/mL) ML Lab File ID: 4M408
 Level: (low/med) LOW Date Received: 09/21/98
 % Moisture: _____ decanted: (Y/N) _____ Date Extracted: 09/22/98
 Concentrated Extract Volume: 1.00 (mL) Date Analyzed: 09/24/98
 Injection Volume: 1.0 (uL) Dilution Factor: 1.0
 GPC Cleanup: (Y/N) N pH: 7.0

CAS NO.	COMPOUND	CONCENTRATION UNITS: (ug/L or ug/Kg) UG/L	Q
91-20-3-----	naphthalene	10.1 U	U ↓
91-58-7-----	2-chloronaphthalene	10.1 U	
209-96-8-----	acenaphthylene	10.1 U	
83-32-9-----	acenaphthene	10.1 U	
86-73-7-----	fluorene	10.1 U	
85-01-8-----	phenanthrene	10.1 U	
120-12-7-----	anthracene	10.1 U	
206-44-0-----	fluoranthene	10.1 U	
129-00-0-----	pyrene	10.1 U	
56-55-3-----	benzo (a) anthracene	10.1 U	
218-01-9-----	chrysene	10.1 U	
205-99-2-----	benzo (b) fluoranthene	10.1 U	
207-08-9-----	benzo (k) fluoranthene	10.1 U	
50-32-8-----	benzo (a) pyrene	10.1 U	
193-39-5-----	indeno (1,2,3-cd) pyrene	10.1 U	
53-70-3-----	dibenz (a,h) anthracene	10.1 U	
191-24-2-----	benzo (g,h,i) perylene	10.1 U	

FORM I SV-1

OLM03.0

1A
VOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

600612

Lab Name: GENERAL ENGINEERING LABOR Contract: NA

Lab Code: NA Case No.: NA SAS No.: NA SDG No.: FS4B06W

Matrix: (soil/water) WATER Lab Sample ID: 9809645-19

Sample wt/vol: 10.00 (g/ml) ML Lab File ID: 2B407

Level: (low/med) LOW Date Received: 09/21/98

% Moisture: not dec. Date Analyzed: 09/24/98

GC Column: J&W DB-624 (PID) ID: 0.53 (mm) Dilution Factor: 1.0

Soil Extract Volume: (ml) Soil Aliquot Volume: (uL)

CAS NO.	COMPOUND	CONCENTRATION UNITS: (ug/L or ug/Kg) UG/L	Q
---------	----------	--	---

71-43-2-----Benzene	2.0	U	U ↓
108-88-3-----Toluene	2.0	U	
100-41-4-----Ethylbenzene	2.0	U	
1330-20-7-----Xylenes (total)	5.0	U	

FORM I VOA

15
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

600612

Lab Name: GENERAL ENGINEERING LABOR Contract: NA

Lab Code: NA Case No.: NA SAS No.: NA SDG No.: FS4B01W

Matrix: (soil/water) GROUNDH2O Lab Sample ID: 9809637-02

Sample wt/vol: 1000 (g/mL) ML Lab File ID: 4M409

Level: (low/med) LOW Date Received: 09/21/98

% Moisture: _____ decanted: (Y/N) _____ Date Extracted: 09/22/98

Concentrated Extract Volume: 1.00 (mL) Date Analyzed: 09/24/98

Injection Volume: 1.0 (uL) Dilution Factor: 1.0

GPC Cleanup: (Y/N) N pH: 7.0

CAS NO.	COMPOUND	CONCENTRATION UNITS: (ug/L or ug/Kg) UG/L	Q
---------	----------	--	---

91-20-3-----	naphthalene	10.0	U
91-58-7-----	2-chloronaphthalene	10.0	U
209-96-8-----	acenaphthylene	10.0	U
83-32-9-----	acenaphthene	10.0	U
86-73-7-----	fluorene	10.0	U
85-01-8-----	phenanthrene	10.0	U
120-12-7-----	anthracene	10.0	U
206-44-0-----	fluoranthene	10.0	U
129-00-0-----	pyrene	10.0	U
56-55-3-----	benzo (a) anthracene	10.0	U
218-01-9-----	chrysene	10.0	U
205-99-2-----	benzo (b) fluoranthene	10.0	U
207-08-9-----	benzo (k) fluoranthene	10.0	U
50-32-8-----	benzo (a) pyrene	10.0	U
193-39-5-----	indeno (1,2,3-cd) pyrene	10.0	U
53-70-3-----	dibenz (a,h) anthracene	10.0	U
191-24-2-----	benzo (g,h,i) perylene	10.0	U

FORM I SV-1

OLM03.0

1A
VOLATILE ORGANICS ANALYSIS DATA SHEET

RINSATE
EPA SAMPLE NO.

600616

Lab Name: GENERAL ENGINEERING LABOR Contract: NA

Lab Code: NA Case No.: NA SAS No.: NA SDG No.: FS4B06W

Matrix: (soil/water) WATER Lab Sample ID: 9809645-01

Sample wt/vol: 10.00 (g/ml) ML Lab File ID: 2B3010

Level: (low/med) LOW Date Received: 09/21/98

% Moisture: not dec. Date Analyzed: 09/23/98

GC Column: J&W DB-624 (PID) ID: 0.53 (mm) Dilution Factor: 1.0

Soil Extract Volume: (ml) Soil Aliquot Volume: (uL)

CAS NO. COMPOUND CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/L Q

71-43-2-----Benzene	2.0	U	U ↓
108-88-3-----Toluene	2.0	U	
100-41-4-----Ethylbenzene	2.0	U	
1330-20-7-----Xylenes (total)	6.0	U	

FORM I VOA

1B
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET

RINSA TE
EPA SAMPLE NO.

600616

Lab Name: GENERAL ENGINEERING LABOR Contract: NA
 Lab Code: NA Case No.: NA SAS No.: NA SDG No.: FS4B02W
 Matrix: (soil/water) GROUNDH2O Lab Sample ID: 9809638-07
 Sample wt/vol: 990.0 (g/mL) ML Lab File ID: 8M516
 Level: (low/med) LOW Date Received: 09/21/98
 % Moisture: _____ decanted: (Y/N) _____ Date Extracted: 09/22/98
 Concentrated Extract Volume: 1.00 (mL) Date Analyzed: 09/25/98
 Injection Volume: 1.0 (uL) Dilution Factor: 1.0
 GPC Cleanup: (Y/N) N pH: 7.0

CAS NO.	COMPOUND	CONCENTRATION UNITS: (ug/L or ug/Kg) UG/L		Q
91-20-3	-----naphthalene	10.1	U	U ↓
91-58-7	-----2-chloronaphthalene	10.1	U	
208-96-8	-----acenaphthylene	10.1	U	
83-32-9	-----acenaphthene	10.1	U	
86-73-7	-----fluorene	10.1	U	
85-01-8	-----phenanthrene	10.1	U	
120-12-7	-----anthracene	10.1	U	
206-44-0	-----fluoranthene	10.1	U	
129-00-0	-----pyrene	10.1	U	
56-55-3	-----benzo (a) anthracene	10.1	U	
218-01-9	-----chrysene	10.1	U	
205-99-2	-----benzo (b) fluoranthene	10.1	U	
207-08-9	-----benzo (k) fluoranthene	10.1	U	
50-32-8	-----benzo (a) pyrene	10.1	U	
193-39-5	-----indeno (1,2,3-cd) pyrene	10.1	U	
53-70-3	-----dibenz (a, h) anthracene	10.1	U	
191-24-2	-----benzo (g, h, i) perylene	10.1	U	

FORM I SV-1

OLM03.0

1A
VOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

600712

Lab Name: GENERAL ENGINEERING LABOR Contract: NA

Lab Code: NA Case No.: NA SAS No.: NA SDG No.: FS4B06W

Matrix: (soil/water) WATER Lab Sample ID: 9809645-09

Sample wt/vol: 10.00 (g/ml) ML Lab File ID: 2B3019

Level: (low/med) LOW Date Received: 09/21/98

% Moisture: not dec. Date Analyzed: 09/23/98

GC Column: J&W DB-624 (PID) ID: 0.53 (mm) Dilution Factor: 1.0

Soil Extract Volume: (ml) Soil Aliquot Volume: (uL)

CAS NO.	COMPOUND	CONCENTRATION UNITS: (ug/L or ug/Kg) UG/L	Q
---------	----------	--	---

71-43-2-----Benzene	2.0	U	U ↓ Y
108-88-3-----Toluene	2.0	U	
100-41-4-----Ethylbenzene	2.0	U	
1330-20-7-----Xylenes (total)	6.0	U	

FORM I VOA

1B
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

600712

Lab Name: GENERAL ENGINEERING LABOR Contract: NA

Lab Code: NA Case No.: NA SAS No.: NA SDG No.: FS4B02W

Matrix: (soil/water) GROUNDH2O Lab Sample ID: 9809638-16

Sample wt/vol: 960.0 (g/mL) ML Lab File ID: 8M525

Level: (low/med) LOW Date Received: 09/21/98

% Moisture: _____ decanted: (Y/N) _____ Date Extracted: 09/22/98

Concentrated Extract Volume: 1.00 (mL) Date Analyzed: 09/25/98

Injection Volume: 1.0 (uL) Dilution Factor: 1.0

GPC Cleanup: (Y/N) N pH: 7.0

CAS NO. COMPOUND CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/L

91-20-3-----	naphthalene	10.4	U
91-58-7-----	2-chloronaphthalene	10.4	U
208-96-8-----	acenaphthylene	10.4	U
83-32-9-----	acenaphthene	10.4	U
86-73-7-----	fluorene	10.4	U
85-01-8-----	phenanthrene	10.4	U
120-12-7-----	anthracene	10.4	U
206-44-0-----	fluoranthene	10.4	U
129-00-0-----	pyrene	10.4	U
56-55-3-----	benzo(a)anthracene	10.4	U
218-01-9-----	chrysene	10.4	U
205-99-2-----	benzo(b)fluoranthene	10.4	U
207-08-9-----	benzo(k)fluoranthene	10.4	U
50-32-8-----	benzo(a)pyrene	10.4	U
193-39-5-----	indeno(1,2,3-cd)pyrene	10.4	U
53-70-3-----	dibenz(a,h)anthracene	10.4	U
191-24-2-----	benzo(g,h,i)perylene	10.4	U

FORM I SV-1

OLM03.0

1A
VOLATILE ORGANICS ANALYSIS DATA SHEET

DUPLICATE
EPA SAMPLE NO.

600714

Lab Name: GENERAL ENGINEERING LABOR Contract: NA

Lab Code: NA Case No.: NA SAS No.: NA SDG No.: FS4B06W

Matrix: (soil/water) WATER Lab Sample ID: 9809645-14

Sample wt/vol: 10.00 (g/ml) ML Lab File ID: 2B3025

Level: (low/med) LOW Date Received: 09/21/98

% Moisture: not dec. Date Analyzed: 09/23/98

GC Column: J&W DB-624(PID) ID: 0.53 (mm) Dilution Factor: 1.0

Soil Extract Volume: (ml) Soil Aliquot Volume: (uL)

CAS NO.	COMPOUND	CONCENTRATION UNITS: (ug/L or ug/Kg) UG/L	Q
---------	----------	--	---

71-43-2-----	Benzene	2.0	U
108-88-3-----	Toluene	2.0	U
100-41-4-----	Ethylbenzene	2.0	U
1330-20-7-----	Xylenes (total)	6.0	U

U
↓
V

FORM I VOA

1B
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET

DUPLICATE
EPA SAMPLE NO.

600714

Lab Name: GENERAL ENGINEERING LABOR Contract: NA
 Lab Code: NA Case No.: NA SAS No.: NA SDG No.: FS4B02W
 Matrix: (soil/water) GROUNDH2O Lab Sample ID: 9809638-17
 Sample wt/vol: 960.0 (g/mL) ML Lab File ID: 8M526
 Level: (low/med) LOW Date Received: 09/21/98
 % Moisture: _____ decanted: (Y/N) _____ Date Extracted: 09/22/98
 Concentrated Extract Volume: 1.00 (mL) Date Analyzed: 09/25/98
 Injection Volume: 1.0 (uL) Dilution Factor: 1.0
 GPC Cleanup: (Y/N) N pH: 7.0

CAS NO.	COMPOUND	CONCENTRATION UNITS: (ug/L or ug/Kg) UG/L		
91-20-3	-----naphthalene	10.4	U	↓
91-58-7	-----2-chloronaphthalene	10.4	U	
208-96-8	-----acenaphthylene	10.4	U	
83-32-9	-----acenaphthene	10.4	U	
86-73-7	-----fluorene	10.4	U	
85-01-8	-----phenanthrene	10.4	U	
120-12-7	-----anthracene	10.4	U	
206-44-0	-----fluoranthene	10.4	U	
129-00-0	-----pyrene	10.4	U	
56-55-3	-----benzo (a) anthracene	10.4	U	
218-01-9	-----chrysene	10.4	U	
205-99-2	-----benzo (b) fluoranthene	10.4	U	
207-08-9	-----benzo (k) fluoranthene	10.4	U	
50-32-8	-----benzo (a) pyrene	10.4	U	
193-39-5	-----indeno (1,2,3-cd) pyrene	10.4	U	
53-70-3	-----dibenz (a,h) anthracene	10.4	U	
191-24-2	-----benzo (g,h,i) perylene	10.4	U	

FORM I SV-1

OLM03.0

1A
VOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

600722

Lab Name: GENERAL ENGINEERING LABOR Contract: NA

Lab Code: NA Case No.: NA SAS No.: NA SDG No.: FS4B06W

Matrix: (soil/water) WATER Lab Sample ID: 9809645-10

Sample wt/vol: 10.00 (g/ml) ML Lab File ID: 2B3020

Level: (low/med) LOW Date Received: 09/21/98

% Moisture: not dec. Date Analyzed: 09/23/98

GC Column: J&W DB-624 (PID) ID: 0.53 (mm) Dilution Factor: 1.0

Soil Extract Volume: (ml) Soil Aliquot Volume: (uL)

CAS NO.	COMPOUND	CONCENTRATION UNITS: (ug/L or ug/Kg) UG/L	Q
---------	----------	--	---

71-43-2-----Benzene	2.0	U	U ↓
108-88-3-----Toluene	2.0	U	
100-41-4-----Ethylbenzene	2.0	U	
1330-20-7-----Xylenes (total)	6.0	U	

FORM I VOA

1B
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

600722

Lab Name: GENERAL ENGINEERING LABOR Contract: NA

Lab Code: NA Case No.: NA SAS No.: NA SDG No.: FS4B02W

Matrix: (soil/water) GROUNDH2O Lab Sample ID: 9809638-18

Sample wt/vol: 970.0 (g/mL) ML Lab File ID: 8M527

Level: (low/med) LOW Date Received: 09/21/98

% Moisture: _____ decanted: (Y/N) _____ Date Extracted: 09/22/98

Concentrated Extract Volume: 1.00 (mL) Date Analyzed: 09/25/98

Injection Volume: 1.0 (uL) Dilution Factor: 1.0

GPC Cleanup: (Y/N) N pH: 7.0

CAS NO. COMPOUND CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/L

91-20-3-----	naphthalene	10.3	U
91-58-7-----	2-chloronaphthalene	10.3	U
208-96-8-----	acenaphthylene	10.3	U
83-32-9-----	acenaphthene	10.3	U
86-73-7-----	fluorene	10.3	U
85-01-8-----	phenanthrene	10.3	U
120-12-7-----	anthracene	10.3	U
206-44-0-----	fluoranthene	10.3	U
129-00-0-----	pyrene	10.3	U
56-55-3-----	benzo (a) anthracene	10.3	U
218-01-9-----	chrysene	10.3	U
205-99-2-----	benzo (b) fluoranthene	10.3	U
207-08-9-----	benzo (k) fluoranthene	10.3	U
50-32-8-----	benzo (a) pyrene	10.3	U
193-39-5-----	indeno (1,2,3-cd) pyrene	10.3	U
53-70-3-----	dibenz (a,h) anthracene	10.3	U
191-24-2-----	benzo (g,h,i) perylene	10.3	U

FORM I SV-1

OLM03.0

1A
VOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

600732

Lab Name: GENERAL ENGINEERING LABOR Contract: NA

Lab Code: NA Case No.: NA SAS No.: NA SDG No.: FS4B06W

Matrix: (soil/water) WATER Lab Sample ID: 9809645-15

Sample wt/vol: 10.00 (g/ml) ML Lab File ID: 2B3026

Level: (low/med) LOW Date Received: 09/21/98

% Moisture: not dec. Date Analyzed: 09/23/98

GC Column: J&W DB-624 (PID) ID: 0.53 (mm) Dilution Factor: 1.0

Soil Extract Volume: (ml) Soil Aliquot Volume: (uL)

CAS NO. COMPOUND CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/L Q

71-43-2-----Benzene	2.0	U
108-88-3-----Toluene	2.0	U
100-41-4-----Ethylbenzene	2.0	U
1330-20-7-----Xylenes (total)	6.0	U

U
↓

FORM I VOA

1B
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

600732

Lab Name: GENERAL ENGINEERING LABOR Contract: NA

Lab Code: NA Case No.: NA SAS No.: NA SDG No.: FS4B02W

Matrix: (soil/water) GROUNDH2O Lab Sample ID: 9809638-15

Sample wt/vol: 960.0 (g/mL) ML Lab File ID: 8M524

Level: (low/med) LOW Date Received: 09/21/98

% Moisture: _____ decanted: (Y/N) _____ Date Extracted: 09/22/98

Concentrated Extract Volume: 1.00 (mL) Date Analyzed: 09/25/98

Injection Volume: 1.0 (uL) Dilution Factor: 1.0

GPC Cleanup: (Y/N) N pH: 7.0

CAS NO. COMPOUND CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/L

91-20-3-----	naphthalene	10.4	U
91-58-7-----	2-chloronaphthalene	10.4	U
208-96-8-----	acenaphthylene	10.4	U
83-32-9-----	acenaphthene	10.4	U
86-73-7-----	fluorene	10.4	U
85-01-8-----	phenanthrene	10.4	U
120-12-7-----	anthracene	10.4	U
206-44-0-----	fluoranthene	10.4	U
129-00-0-----	pyrene	10.4	U
56-55-3-----	benzo(a)anthracene	10.4	U
218-01-9-----	chrysene	10.4	U
205-99-2-----	benzo(b)fluoranthene	10.4	U
207-08-9-----	benzo(k)fluoranthene	10.4	U
50-32-8-----	benzo(a)pyrene	10.4	U
193-39-5-----	indeno(1,2,3-cd)pyrene	10.4	U
53-70-3-----	dibenz(a,h)anthracene	10.4	U
191-24-2-----	benzo(g,h,i)perylene	10.4	U

FORM I SV-1

OLM03.0



800 Oak Ridge Turnpike, Oak Ridge, TN 37831 (423) 481-4600.

CHAIN OF CUSTODY RECORD

COC NO.: GASØ1

[illegible]

CHAIN OF CUSTODY RECORD

COC NO.: GAS ØZ

PROJECT NAME: 46 SWAMP Investigations CAP A Options						REQUESTED PARAMETERS																		LABORATORY NAME: General Engineering Laboratory	
PROJECT NUMBER: 01-0331-04-3328-200 9205 - 210																								LABORATORY ADDRESS: 2040 Savage Road Charleston, SC 29417	
PROJECT MANAGER: Jeff Longaker Patty Stoll																								PHONE NO: (803) 556-8171	
Sampler (Signature) <i>Sandra Lumley</i>																								OBSERVATIONS, COMMENTS, SPECIAL INSTRUCTIONS 9809237-070	
Sample ID	Date Collected	Time Collected	Matrix	VOC	SVOC	TOTAL LEAD	FILTERED LEAD	RCLA METALS											No. of Bottles/Vials:	OVA SCREENING					
650522	9/14/98	930	water					PAT										1		-08					
650512	9/18/98	900						Z										2		-08					
620742	9/18/98	1745						Z										2		-09					
600415	9/18/98	1040						4										4		-10					
620722	9/18/98	1640						Z										2							
<i>(Signature)</i>						<i>(Signature)</i>																		Cooler Temperature: 40C	
																								FEDEX NUMBER:	
RELINQUISHED BY: Sandra Lumley						RECEIVED BY: Shavio						TOTAL NUMBER OF CONTAINERS: 11						Cooler Temperature: 40C							
COMPANY NAME: SATC						COMPANY NAME: gpc						COOLER ID: # 259, 3C						FEDEX NUMBER:							
RECEIVED BY: Mike Locke						RELINQUISHED BY:						Date/Time: 9/21/98						Date/Time: 9/21/98							
COMPANY NAME: GEL						COMPANY NAME:						Date/Time: 1145						Date/Time: 1945							
RELINQUISHED BY: Mike Locke						RECEIVED BY:						Date/Time: 9/21/98						Date/Time: 1145							
COMPANY NAME: GEL						COMPANY NAME:						Date/Time: 9/21/98						Date/Time: 1145							



SAIC
Science Applications International Corporation
An Employer-Owned Company

800 Oak Ridge Turnpike, Oak Ridge, TN 37831 (423) 481-4600

CHAIN OF CUSTODY RECORD

COC NO.: GAS 86

PROJECT NAME: 16 SWAMP Investigations CAP-A Option				REQUESTED PARAMETERS												LABORATORY NAME: General Engineering Laboratory															
PROJECT NUMBER: 01-0331-04-7328-200- 9805-210																LABORATORY ADDRESS: 2040 Savage Road Charleston, SC 29417															
PROJECT MANAGER: Jeff Longaker Patty Stoll																PHONE NO: (803) 556-8171															
Sampler (Signature) Laura Lumley																OBSERVATIONS, COMMENTS, SPECIAL INSTRUCTIONS 980968-07 -08 -09 -10 -11 -12															
Sample ID	Date Collected	Time Collected	Matrix	VOC	SVOC	TOTAL LEAD	FILTERED LEAD	RCRA METALS	PAH	No. of Bottles/Vials:			OVA SCREENING																		
600616	9/18/98	1253	water																												
560316	9/17/98	1335																													
630714	9/19/98	1230																													
950112	9/17/98	1445																													
620616	9/20/98	910																													
630412	9/19/98	1635																													
88 9/21/98				TOTAL NUMBER OF CONTAINERS: 11												Cooler Temperature: 40C															
				Cooler ID: #2, 4C												FEDEX NUMBER:															
				Date/Time: 9/21/98 1545																											
RELINQUISHED BY: SAIC				Date/Time: 9/21/98 1145				RECEIVED BY: Glen C. Co				Date/Time: 9/21/98 1545				RELINQUISHED BY: SAIC				Date/Time: 9/21/98 1545				RECEIVED BY: Glen C. Co				Date/Time: 9/21/98 1545			
COMPANY NAME:				COMPANY NAME:				COMPANY NAME:				COMPANY NAME:				COMPANY NAME:				COMPANY NAME:				COMPANY NAME:							



800 Oak Ridge Turnpike, Oak Ridge, TN 37831 (423) 481-4600
Science Applications International Corporation

CHAIN OF CUSTODY RECORD

COC NO.: GAS 07

PROJECT NAME: 16 SUMMIT Investigations CAD-A Options				REQUESTED PARAMETERS												LABORATORY NAME: General Engineering Laboratory	
PROJECT NUMBER: 01-0331-04-7320-200-7405-210				No. of Bottles/Vials: 1												LABORATORY ADDRESS: 2040 Savage Road Charleston, SC 29417	
PROJECT MANAGER: Just Longaker Patty Stoll				No. of Bottles/Vials: 2												PHONE NO: (803) 556-8171	
Sampler (Signature) James D. Lumley				No. of Bottles/Vials: 2												OVA SCREENING	
Printed Name James D. Lumley				No. of Bottles/Vials: 2												OBSERVATIONS, COMMENTS, SPECIAL INSTRUCTIONS 9809638-13 -14 -15 -16 -17	
Sample ID 630412				Date Collected 9/19/98				Time Collected 11055				Matrix water				NO. OF BOTTLES/VIALS 1	
620612				9/20/98				920				2				2	
620312				9/20/98				1040				2				2	
600732				9/20/98				1605				2				2	
600712				9/20/98				1505				2				2	
600714				9/20/98				1505				2				2	
(Signature)				(Signature)				(Signature)				(Signature)				(Signature)	
RELINQUISHED BY: James D. Lumley				Date/Time 9/21/98				RECEIVED BY: (Signature)				Date/Time 9/21/98				TOTAL NUMBER OF CONTAINERS: 11	
COMPANY NAME: SATC				1145				COMPANY NAME: (Signature)				1545				Cooler ID: #62,4C	
RECEIVED BY: (Signature)				Date/Time 9/24/98				RELINQUISHED BY: (Signature)				Date/Time 1145				Cooler Temperature: 40C	
COMPANY NAME: (Signature)				1145				COMPANY NAME: (Signature)				1545				FEDEX NUMBER:	
RELINQUISHED BY: (Signature)				Date/Time 9/21/98				RECEIVED BY: (Signature)				Date/Time 1545					
COMPANY NAME: (Signature)				1545				COMPANY NAME: (Signature)				1545					



800 Oak Ridge Turnpike, Oak Ridge, TN 37831 (423) 481-4600

3065

COC NO.: GAS09

CHAIN OF CUSTODY RECORD

PROJECT NAME: 16-04715 Investigations CAP-A Options				REQUESTED PARAMETERS												LABORATORY NAME: General Engineering Laboratory	
PROJECT NUMBER: 01-0331-04-7220-200																LABORATORY ADDRESS: 2040 Savage Road Charleston, SC 29417	
PROJECT MANAGER: Jeff Longaker Patty Stol																PHONE NO: (803) 556-8171	
Sampler (Signature): <i>Laura Lumley</i> (Printed Name)																OBSERVATIONS, COMMENTS, SPECIAL INSTRUCTIONS	
Sample ID	Date Collected	Time Collected	Matrix	VOC	SVOC	TOTAL LEAD	FILTERED LEAD	HCRA METALS	No. of Bottles/Vials				OVA SCREENING				
950112	9/17/98	1445	water												9809642-15		
620714	9/18/98	1610													7		
650412	9/17/98	1645													-17		
650325	9/17/98	920													-18		
620712	9/18/98	1610													-19		
580316	9/17/98	1335													-20		
6000110	9/18/98	1255													9809645-01		
600415	9/18/98	1040													02		
600412	9/18/98	1115													03		
650512	9/18/98	900													04		
620512	9/18/98	1535													05		
620742	9/18/98	1745													06		
600512	9/18/98	1215													07		
RELINQUISHED BY: <i>Laura Lumley</i> COMPANY NAME: SAIC				RECEIVED BY: <i>Shawna</i> COMPANY NAME: <i>gel</i>				Date/Time: 9/21/98				TOTAL NUMBER OF CONTAINERS: Cooler ID: #406030				Cooler Temperature: 40c	
RECEIVED BY: <i>Kyle</i> COMPANY NAME: <i>GEEL</i>				RELINQUISHED BY: <i>Shawna</i> COMPANY NAME: <i>gel</i>				Date/Time: 9/21/98								FEDEX NUMBER:	
RELINQUISHED BY: <i>Shawna</i> COMPANY NAME: <i>gel</i>				RECEIVED BY: <i>Shawna</i> COMPANY NAME: <i>gel</i>				Date/Time: 9/21/98									

2015

COC NO.: 64509

CHAIN OF CUSTODY RECORD

PROJECT NAME: 46 SUMMIT INVESTIGATIONS CAP-A Options				REQUESTED PARAMETERS												LABORATORY NAME: General Engineering Laboratory	
PROJECT NUMBER: 01-0331-04-7326-200 9405-210																LABORATORY ADDRESS: 2040 Savage Road Charleston, SC 29417	
PROJECT MANAGER: Jeff Longaker Patty Stoll																PHONE NO: (803) 556-8171	
Sampler (Signature) Sams Sunday Laura Humley																OBSERVATIONS, COMMENTS, SPECIAL INSTRUCTIONS 9809645-08 -09 -10 -11 -12 -13 -14 -15 -16 -17 -18 -19 -20	
Sample ID	Date Collected	Time Collected	Matrix	VOC	SVOC	TOTAL LEAD	FILTERED LEAD	PCRA METALS	No. of Bottles/Vials				OVA SCREENING				
600312	9/20/98	1835	water														
600712	9/20/98	1505															
600722	9/20/98	1535															
620612	9/20/98	920															
620616	9/20/98	916															
620312	9/20/98	1040															
600714	9/20/98	1505															
600732	9/20/98	1605															
625219	9/20/98	1220															
630412	9/19/98	1655															
620412	9/20/98	1205															
600612	9/18/98	1300															
TB003	9/17/98	745															
RELINQUISHED BY: Sams Sunday				RECEIVED BY: Francisco				TOTAL NUMBER OF CONTAINERS: 40C				Cooler Temperature: 40C					
COMPANY NAME: SAIC				COMPANY NAME: 1145				Cooler ID: #4060, 32				FEDEX NUMBER:					
RECEIVED BY: Pat Beckel				RELINQUISHED BY: 1145				Date/Time: 9/21/98				Date/Time: 1545					
COMPANY NAME: GEC				COMPANY NAME: 1145				Date/Time: 9/21/98				Date/Time: 1545					
RELINQUISHED BY: Pat Beckel				RECEIVED BY: 1145				Date/Time: 9/21/98				Date/Time: 1545					
COMPANY NAME: GEC				COMPANY NAME: 1145				Date/Time: 9/21/98				Date/Time: 1545					

THIS PAGE INTENTIONALLY LEFT BLANK

APPENDIX IX
CONTAMINATED SOIL DISPOSAL MANIFESTS

THIS PAGE INTENTIONALLY LEFT BLANK

All contaminated soil removed during the entire project (i.e., all USTs removed under contract with ACE, to include clean and non-clean closures) was tested in accordance with the disposal facility requirements and transported to Kedesh, Inc., Highway 84, Ludowici, GA, 31316. The Closure Report was not submitted to GA EPD in 1996 because review of the closure analytical data indicated that a CAP-Part A would be required (i.e., per requirements of GUST-9, Item 15, page 12, dated August 1995). However, all pertinent information (i.e., copies of analytical data, manifests, and maps) are provided in this CAP-Part A report. Disposal manifests for the UST 28B site were submitted to GA EPD USTMP in September 1998 with the UST 207A (Facility ID #9-089039) Closure Report response to comments correspondence (Perez 1998). Approximately 23.52 tons of contaminated soil was excavated from the site.

I certify that the above information is true and accurate.

Name: Thomas C. Fry

Title: Acting Chief, ENRD

Signature: Thomas C. Fry

Date: 09/07/99

THIS PAGE INTENTIONALLY LEFT BLANK



DEPARTMENT OF THE ARMY
HEADQUARTERS, 3D INFANTRY DIVISION (MECHANIZED) AND FORT STEWART
Directorate of Public Works
1557 Frank Cochran Drive
Fort Stewart, Georgia 31314-4928

SEP 15 1998

REPLY TO
ATTENTION OF

Directorate of Public Works

CERTIFIED MAIL

E-098-024-167

Georgia Department of Natural Resources
Environmental Protection Division
Underground Storage Tank Management Program
Attention: Mr. William Logan, Environmental Specialist
4244 International Parkway, Suite 104
Atlanta, Georgia 30354

Dear Mr. Logan:

Fort Stewart is pleased to receive the Georgia Environmental Protection Division's correspondence dated August 14, 1998, in reference to the Closure Report submitted for Fort Stewart's former Underground Storage Tank (UST) #207A, Building 230, Facility Identification Number 9089039. As requested in that correspondence, the April 3, 1998 Closure Report Addendum should be amended to include the enclosed manifests for Anderson Columbia Environmental Delivery Order 101, which are provided for your use and convenience. These manifests include additional UST sites (as shown on the attached list). A total of 45 USTs were removed under this delivery order. In addition, this delivery order removed dispensing islands (note included on the provided list) from another 22 sites, for a total of 67 sites as noted in the Closure Report Addendum.

If you have any questions or comments, please contact Ms. Melanie Little or Ms. Tressa Rutland, Directorate of Public Works, Environmental Branch, at (405) 364-8461 or (912) 767-7919, respectively.

Sincerely,

for *Hale F. Kiefer*
Ovidio E. Perez
Colonel, U.S. Army
Director, Public Works

Enclosure

IX-5

FORT STEWART UST Removal List for FY 1996

Anderson Columbia Delivery Order #101

<u>TANK #</u>	<u>LOCATION</u>	<u>SIZE</u>	<u>FACILITY ID #</u>
2	Bldg 1840: Diesel	25,000	9-089065
3	Bldg 1850: Mogas	5,000	9-089065
4	Bldg 1840: Waste Oil	2,500	9-089065
4A	Bldg 1840: Waste Oil	1,000	9-089065
5	Bldg 1824: Mogas	6,000	9-089066
6	Bldg 1824: Diesel	25,000	9-089066
22	Bldg 1720: Waste Oil	2,000	9-089011
24	Bldg 1720: Waste Oil	2,000	9-089011
28B	Bldg 1720: Waste Oil	2,000	9-089011
38	Bldg 1510/13: Waste Oil	1,000	9-089109
41	Bldg 1542: Waste Oil	1,000	9-089145
45	Bldg 1172: Waste Oil	500	9-089054
56	Bldg 1056: Waste Oil	2,000	9-089116
65	Bldg 927: Mogas	10,000	9-089091
66	Bldg 967: Diesel	10,000	9-089091
71	Bldg 1203: Waste Oil	1,000	9-089022
71A	Bldg 1260: Waste Oil	1,000	9-089023
74	Bldg 1280: Waste Oil	2,500	9-089072
79	Bldg 1224: Waste Oil	1,000	9-089026
87	Bldg 1245: Diesel	5,000	9-089073
88	Bldg 1245: Diesel	5,000	9-089073
93	Bldg 1330: Waste Oil	2,500	9-089112
94	Bldg 1320/23: Waste Oil	1,000	9-089076
94B	Bldg 1339: Waste Oil	1,000	9-089110
94C	Bldg 1339A: Waste Oil	1,000	9-089110
100A	Bldg 1349: Waste Oil	1,000	9-089080
100B	Bldg 1350: Waste Oil	1,000	9-089081
201A	Bldg 260: Waste Oil	1,000	9-089043
201B	Bldg 260: Waste Oil	1,000	9-089043
207	Bldg 232: Waste Oil	500	9-089038
207A	Bldg 230: Waste Oil	2,500	9-089039
214	Bldg 1503: Waste Oil	550	9-089015
215	Bldg 1503: Waste Oil	500	9-089015
216	Bldg 4502: Waste Oil	1,000	9-089060
224	Bldg 4528: Waste Oil	1,000	9-089063
225	Bldg 4529: Waste Oil	1,000	9-089090
238	Bldg 4586: Waste Oil	1,000	9-089044
241	Bldg 241: Waste Oil	2,000	9-089041
242	Bldg 241: Waste Oil	1,000	9-089041
243	Bldg 241: Waste Oil	1,000	9-089041
244	Bldg 241: Waste Oil	1,000	9-089041
261	Bldg 430 (AAFES):Waste Oil	500	9-089118
115	Bldg 15003 Em. Gen: Diesel	250	9-054005
118	Bldg 1239 Em. Gen: Diesel	1,000	9-089070
123	Bldg 933 Em. Gen: Diesel	1,000	9-089092

REYNOLDS CONSTRUCTION COMPANY

Highway 84 • P. O. Box 749
Ludowici, Georgia 31316
Office (912) 368-7488 • Plant (912) 876-8085

Date _____ 19____ Load No. 22
Triple "R" MONT. Pes
Customer _____ Description _____
RRR-104
Project Number _____
STEWART Liberty
Location _____ County _____

47040 1b Net

23000 1b Tare

70040 1b+ Gross

02:02 PM AU 12 96

Signature of Weigher

TONS:

23,52

TOTAL TONS:

452.50
~~453.29~~

TRUCKER

DRIVER

70ndriv
Robert Slonell

TRUCK NO.

TICKET NO.

33

58846

VIP-15

286

NON-HAZARDOUS WASTE MANIFEST		Manifest Document No. 000003	1. Page 1 of 1		
2. Generator's Name and Mailing Address Ft. Stewart Minesville, GA 31313					
3. Generator's Phone (912) 234-6579					
4. Transporter 1 Company Name Hendricks Hauling					
5. Transporter 2 Company Name					
6. Designated Facility Name and Site Address Triple B Management, Inc. c/o Reynolds Constr Co. Rt. 84 Ludowici, GA 31316		A. Transporter's Phone B. Transporter's Phone 912-427-6756 C. Facility's Phone 912-756-3655			
7. Waste Shipping Name and Description		8. Containers		9. Total Quantity	
		No.	Type		
		a.	1	TT	18.00
		b.			
		c.			
d.					
10. Unit Wt/Vol		CY			
D. Additional Descriptions for Materials Listed Above		E. Handling Codes for Wastes Listed Above			
11. Special Handling Instructions and Additional Information 8101 Tank # <u>28B</u>					
12. GENERATOR'S CERTIFICATION: I certify the materials described above on this manifest are not subject to federal regulations for reporting proper disposal of Hazardous Waste.					
Printed/Typed Name <u>Tom C. Fey</u>		Signature <u>Tom C. Fey</u>		Month Day Year <u>08</u> <u>06</u> <u>96</u>	
13. Transporter 1 Acknowledgement of Receipt of Materials					
Printed/Typed Name <u>ROBERT STOVALL</u>		Signature <u>Robert Stovall</u>		Month Day Year <u>08</u> <u>12</u> <u>96</u>	
14. Transporter 2 Acknowledgement of Receipt of Materials					
Printed/Typed Name		Signature		Month Day Year <u>08</u> <u>12</u> <u>96</u>	
15. Discrepancy Indication Space					
16. Facility Owner or Operator: Certification of receipt of waste materials covered by this manifest except as noted in Item 19.					
Printed/Typed Name		Signature		Month Day Year <u>08</u> <u>12</u> <u>96</u>	

GENERATOR

TRANSPORTER

FACILITY

APPENDIX X
SITE RANKING FORM

THIS PAGE INTENTIONALLY LEFT BLANK

SITE RANKING FORM

Facility Name: UST 28B, Building 1720

Ranked by: S. Stoller

County: Liberty Facility ID #: 9-089011

Date Ranked: 6/30/99

SOIL CONTAMINATION (based on soil closure data)

A. Total PAHs –
Maximum Concentration found on the site
(Assume <0.660 mg/kg if only gasoline
was stored on site)

- ☐ ≤0.660 mg/kg = 0
- ☐ >0.66 - 1 mg/kg = 10
- ☒ >1 - 10 mg/kg = 25
- ☐ >10 mg/kg = 50

B. Total Benzene -
Maximum Concentration found on the site

- ☐ ≤0.005 mg/kg = 0
- ☐ >0.005 - .05 mg/kg = 1
- * ☒ >0.05 - 1 mg/kg = 10
- ☐ >1 - 10 mg/kg = 25
- ☐ >10 - 50 mg/kg = 40
- ☐ >50 mg/kg = 50

* Due to elevated detected limits during
closure sampling.

C. Depth to Groundwater
(bls = below land surface)

- ☐ >50' bls = 1
- ☐ >25' - 50' bls = 2
- ☐ >10' - 25' bls = 5
- ☒ ≤10' bls = 10

Fill in the blanks: (A. 25) + (B. 10) = (35) x (C. 10) = (D. 350)

GROUNDWATER CONTAMINATION (based on CAP-Part A groundwater data)

E. Free Product (Nonaqueous-phase
liquid hydrocarbons; See Guidelines
For definition of "sheen").

- ☒ No free product = 0
- ☐ Sheen - 1/8" = 250
- ☐ >1/8" - 6" = 500
- ☐ >6" - 1ft. = 1,000
- ☐ For every additional inch, add another
100 points = 1,000 +

F. Dissolved Benzene -
Maximum Concentration at the site
(One well must be located at the source
of the release.)

- ☐ ≤5 µg/L = 0
- ☐ >5 - 100 µg/L = 5
- ☒ >100 - 1,000 µg/L = 50
- ☐ >1,000 - 10,000 µg/L = 100
- ☐ >10,000 µg/L = 250

Fill in the blanks: (E. 0) + (F. 50) = (G. 50)

POTENTIAL RECEPTORS (MUST BE FIELD-VERIFIED)

Distance from nearest contaminant plume boundary to the nearest downgradient and hydraulically connected Point of Withdrawal for water supply. **If the point of withdrawal is not hydraulically connected, evidence as outlined in the CAP-A guidance document MUST be presented to substantiate this claim.**

H. Public Water Supply

- ☐ Impacted = 2000
☐ ≤500' = 500
☐ >500' - ¼ mi = 25
☐ ¼ mi - 1 mi = 10
☐ >1 mi - 2 mi = 2

* ☒ > 2 mi = 0

For lower susceptibility areas only:

- ☐ >1 mi = 0

Note: If site is in lower susceptibility area, do not use the shaded areas.

* For justification that withdrawal point is not hydraulically connected, see attached text.

I. Non-Public Water Supply

- ☐ Impacted = 1000
☐ ≤100' = 500
☐ >100' - 500' = 25
☐ >500' - ¼ mi = 5
☐ >¼ - ½ mi = 2

☒ >½ mi = 0

For lower susceptibility areas only:

- ☐ >¼ mi = 0

J. Distance from nearest Contaminant Plume boundary to downgradient Surface Waters OR UTILITY TRENCHES & VAULTS (a utility trench may be omitted from ranking if its invert elevation is more than 5 feet above the water table)

- ☐ Impacted = 500
☒ ≤500' = 50
☐ >500' - 1,000' = 5
☐ >1,000' = 1

K. Distance from any Free Product to basements and crawl spaces

- ☐ Impacted = 500
☐ <500' = 50
☐ >500' - 1,000' = 5
☒ >1,000' or no free product. = 0

Fill in the blanks: (H. 0) + (I. 0) + (J. 50) + (K. 0) = L. 50

(G. 50) x (L. 50) = M. 2500

(M. 2500) + (D. 350) = N. 2850

P. SUSCEPTIBILITY AREA MULTIPLIER

- ☐ If site is located in a Low Ground-Water Pollution Susceptibility Area = 0.5
☒ All other sites = 1

Q. EXPLOSION HAZARD

Have any explosive petroleum vapors, possibly originating from this release, been detected in any subsurface structure (e.g., utility trenches, basements, vaults, crawl spaces, etc.)?

- ☐ Yes = 200,000
☒ No = 0

Fill in the blanks: (N. 2850) x (P. 1) = (2850) + (Q. 0)

= 2850 (based on closure soil data and CAP-Part A groundwater data)
ENVIRONMENTAL SENSITIVITY SCORE

ADDITIONAL GEOLOGIC AND HYDROLOGIC DATA

The following information is presented to provide supplemental information to Section II.D.5 of the CAP-Part A form and Item H of the Site Ranking Form and provides detailed information relating to the geologic and hydrogeologic conditions at Fort Stewart which supports Fort Stewart's determination that the water withdrawal point(s) located at Fort Stewart is (are) not hydraulically connected to the surficial aquifer.

1.0 REGIONAL AND LOCAL GEOLOGY

Fort Stewart is located within the coastal plain physiographic province. This province is typified by nine southeastward dipping strata that increase in thickness from 0 feet at the fall line located approximately 150 miles inland from the Atlantic coast, to approximately 4,200 feet at the coast. State geologic records describe a probable petroleum exploration well (the No. 1 Jelks-Rogers) located in the region as encountering crystalline basement rocks at a depth of 4254 feet BGS. This well provides the most complete record for Cretaceous, Tertiary, and Quaternary sedimentary strata in the region.

The Cretaceous section was found to be approximately 1970 feet thick and dominated by clastics. The Tertiary section was found to be approximately 2170 feet thick and dominated by limestone with a 175-foot-thick cap of dark green phosphatic clay. This clay is regionally extensive and is known as the Hawthorn Group. The interval from approximately 110 feet to the surface is Quaternary in age and composed primarily of sand with interbeds of clay or silt. This section is undifferentiated into separate formations (Herrick and Vochis 1963).

State geologic records contain information regarding a well drilled in October 1942, 1.8 miles north of Flemington at Liberty Field of Camp Stewart (now known as Fort Stewart). This well is believed to be an artesian well located approximately one-quarter mile north of the runway at Wright Army Airfield within the Fort Stewart Military Reservation. The log for this well describes a 410-foot section, the lowermost 110 feet of which consisted predominantly of limestone sediments, above which 245 feet of dark green phosphatic clay typical of the Hawthorn Group was encountered. The uppermost portion of the section was found to be Quaternary-age interbedded sands and clays. The top 15 feet of these sediments were described as sandy clay (Herrick and Vochis 1963).

The surface soil located throughout the Fort Stewart garrison area consists of Stilson loamy sand. The surface layer of this soil is typically dark grayish-brown loamy sand measuring approximately 6 inches in depth. The surface layer is underlain by material consisting of pale yellow loamy sand and extends to a depth of approximately 29 inches. The subsoil is dominantly sandy clay loam and extends to a depth of 72 inches or more (Herrick and Vochis 1963).

2.0 REGIONAL AND LOCAL HYDROGEOLOGY

The hydrogeology in the vicinity of Fort Stewart is dominated by two aquifers referred to as the Principal Artesian and the surficial aquifers. The Principal Artesian aquifer is the lowermost hydrologic unit and is regionally extensive from South Carolina through Georgia, Alabama, and most of Florida. Known elsewhere as the Floridan, this aquifer is composed primarily of Tertiary-age limestone, including the

Bug Island Formation, the Ocala Group, and the Suwannee Limestone. These formations are approximately 800 feet thick, and groundwater from this aquifer is used primarily for drinking water (Arora 1984).

The uppermost hydrologic unit is the surficial aquifer, which consists of widely varying amounts of sand and clay ranging from 55 to 150 feet in thickness. This aquifer is primarily used for domestic lawn and agricultural irrigation. The top of the water table ranges from approximately 2 to 10 feet BGS (Geraghty and Miller 1993). The base of the aquifer corresponds to the top of the underlying dense clay of the Hawthorn Group. The Hawthorn Group was not encountered during drilling at this site but is believed to be located at 40 to 50 feet BGS; thus, the effective aquifer thickness would be approximately 35 to 45 feet. Soil surveys for Liberty and Long Counties describe the occurrence of a perched water table within the Stilson loamy sands present within Fort Stewart (Looper 1980).

The confining layer for the Principal Artesian aquifer is the phosphatic clay of the Hawthorn Group and ranges in thickness from 15 to 90 feet. The vertical hydraulic conductivity of this confining unit is on the order of 10^{-8} cm/sec. There are minor occurrences of aquifer material within the Hawthorn Group; however, they have limited utilization (Miller 1990). The Hawthorn Group has been divided into three formations: Coosawhatchie Formation, Markshead Formation, and the Parachula Formation, which are listed from youngest to oldest.

The Coosawhatchie Formation is composed predominantly of clay but also has sandy clay, argillaceous sand, and phosphorite units. The formation is approximately 170 feet thick in the Savannah Georgia area. This unit disconformably overlies the Markshead Formation and is distinguished from the underlying unit by dark phosphatic clays or phosphorite in the lower part and fine-grained sand in the upper part.

The Markshead Formation is approximately 70 feet thick in the Savannah Georgia area and consists of light-colored phosphatic, slightly dolomitic, argillaceous sand to fine-grained sandy clay with scattered beds of dolostone and limestone.

The Parachula Formation consists of sand, clay, limestone, and dolomite, and is approximately 10 feet thick in the Savannah Georgia area. The Parachula Formation generally overlies the Suwannee Limestone in Georgia.

Groundwater encountered at all the UST investigation sites is part of the Surficial Aquifer system. Based on the fact that all public and non-public water supply wells draw water from the Principal (Floridan) Aquifer, and that the Hawthorn confining unit separates the Principal Aquifer from the Surficial Aquifer, it is concluded that there is no hydraulic interconnection between the Surficial Aquifer (and associated groundwater plumes, if applicable) located beneath former UST sites and identified water supply withdrawal points at Fort Stewart.

APPENDIX XI

COPIES OF PUBLIC NOTIFICATION LETTERS AND CERTIFIED RECEPTS OF NEWSPAPER NOTICE

THIS PAGE INTENTIONALLY LEFT BLANK

Personally appeared before me, Lynnette Tuck, to me known, who being sworn, deposes and says:

That he is the Class. Inside Sales Mgr. of Southeastern Newspapers Corporation, a Georgia corporation, doing business in Chatham County, Georgia, under the trade name of Savannah Morning News/Savannah Evening Press, a daily newspaper published in said county;

That he is authorized to make affidavits of publication on behalf of said published corporation;

That said newspaper is of general circulation in said county and in the area adjacent thereto;

That he has reviewed the regular editions of the Savannah Morning News/Savannah Evening Press, published on 6-27, 1999, 7-4, 1999, , 1999, , 1999, and finds that the following Advertisement, to-wit:

015 Miscellaneous Notices
PUBLIC NOTICE
Notification of Corrective Action Plan, Underground Storage Tank Releases, Fort Stewart Garrison Area, Fort Stewart, Ga.
The Georgia EPD (GEPD) has required Fort Stewart Directorate of Public Works to prepare a Corrective Action Plans Part-A to investigate and/or clean up contamination at the underground storage tank sites listed at the end of this notification. These plans will be submitted to the GEPD on or before September 30, 1999. If you want

to examine a copy of one or more of the plans, please contact Commander, 3rd Infantry Division (Mechanized) and Fort Stewart, attn: DPW ENRD ENV. Br. (T. Ruffland), 1557 Frank Cochran, Fort Stewart, Ga. 31314-4928
A copy will be mailed at a nominal fee.
Comments to the plan will be accepted until October 31, 1999, and should be directed to GEPD at 404-362-2687. Following is the mailing address:
GEPD USTMP, 4244 International Parkway, Suite 104, Atlanta, Ga. 30354
Fort Stewart CAP - Part A and Part B Underground Storage Tank Sites
UST Building Facility IDs
2 & 3, 1848, 9-089045
5 & 6, 1834, 9-089046

28B, 1720, 9-089011
36 & 37m 1510, 9-089016
38, 1510-13, 9-089109
63 & 64, 1128, 9-089051
71, 1203, 9-089022
79, 1224, 9-089026
87 & 88, 1745, 9-089073
100B, 1350, 9-089081
122, 7705, 9-089083
123, 933, 9-089097
214, 1553, 9-089015
225, 4529, 9-089090
242 & 244, 241, 9-089041
248 & 249, 15016, 9-054006
4 & 5 NGTC, 9395, 9-890028
6 & 7 NGTC, 9795, 9-890028

appeared in each of said editions.

Lynnette Tuck
(Deponent)

Sworn to and subscribed before me this 7 day of July, 1999.

Julie D. Ray
Notary Public, Chatham County, Georgia

THIS PAGE INTENTIONALLY LEFT BLANK

APPENDIX XII

GUST TRUST FUND REIMBURSEMENT APPLICATION AND CLAIM FOR REIMBURSEMENT

THIS PAGE INTENTIONALLY LEFT BLANK

Fort Stewart is a federally owned facility and has funded the investigation for UST 28B, Building 1720, Facility ID #9-089011, using Department of Defense Environmental Restoration Account Funds. Application for Georgia Underground Storage Tank Trust Fund reimbursement is not being pursued at this time.

THIS PAGE INTENTIONALLY LEFT BLANK

ATTACHMENT A
TECHNICAL APPROACH

THIS PAGE INTENTIONALLY LEFT BLANK

TECHNICAL APPROACH

1.0 INTRODUCTION

The overall objective of this project is to provide the engineering services required to produce Corrective Action Plans (CAPs) for the subject UST sites. These reports will conform to the site closure requirements of a CAP-Part A for sites in Georgia. The field investigations necessary to support the report preparation included the installation of temporary piezometers, soil borings, and associated sampling of soil and groundwater. Upon completion of the field investigations, a CAP-Part A will be prepared to meet GA EPD, Fort Stewart, and the USACE-Savannah requirements.

2.0 FIELD ACTIVITIES

The following sections detail the methodologies used for geoprobe drilling, sampling, and piezometer installation. A geologist from SAIC was on site at all times during operations. No drilling activities were undertaken until all utility clearances and permits had been obtained from Fort Stewart's utility personnel.

2.1 Subsurface Soil Sampling

2.1.1 Geoprobe Drilling

The geoprobe method was used during the project for collecting soil samples. During all geoprobe drilling, soil samples were collected continuously on 4.0-foot centers from the ground surface to the bottom of the borehole. The total depth of each borehole was dictated by the depth where the water table was encountered.

2.1.2 Sample Collection

Soil samples for chemical analyses were collected from boreholes using 4.0-foot macro-core samplers. Upon retrieval of the sampling device, the soil core was split into two 2.0-foot sections using a stainless steel knife. A portion of each 2.0-foot section was collected for possible laboratory analysis. The remaining portion of each 2.0-foot section was used for field measurements.

During the May and June 1998 sampling events, samples designated for possible laboratory analysis were collected from the section using a stainless steel spoon. The spoon was run lengthwise down the core to collect a sample representative of the entire core section. The portion of the sample designated for volatile organic analyses was placed into laboratory sample containers first, followed by placement of the remaining portion of the sample into the containers designated for other types of analyses. Sample containers designated for volatile organic analyses were filled so that minimal headspace was present in the containers. Headspace gas concentration measurements were made using a field organic vapor meter (OVM). Initially, soil from each 2.0-foot interval was placed into a glass jar, leaving some air space, and covered with aluminum foil to create an air-tight seal. The sample was allowed to volatilize for a minimum of 15 minutes. The sealed jar was punctured with the OVM probe and headspace gas drawn until the meter reading was stable. The concentration of the headspace gas was recorded to the nearest 0.1 part per million.

Due to a change in the state regulations governing sample analysis, the collection of samples designated for volatile organic analyses was modified beginning with the November 1998 field effort. Soil samples designated for volatile organic analyses were collected using En Core™ samplers. The samplers were locked into an En Core T-Handle. Using the T-Handle, the sampler was pushed into the soil until the coring body of the sampler was full. Once the samplers were filled, caps were locked onto them insuring that no

headspace was present. The samplers were then removed from the handle and placed in an En Core zipper bag. Three encore samples are collected from each section 2.0-foot section.

Immediately after collection of each sample and completion of bottle label information, each potential analytical sample container was placed into an ice-filled cooler to ensure preservation. A clean split-barrel sampling device was used to collect soil core from each interval of the project boreholes. Information regarding the criteria for selection of soil samples for off-site shipment to a laboratory for chemical analysis is presented in Section 3.1.3 of the project Work Plan. Soil samples, which were not selected for laboratory analysis, were disposed of as investigation-derived waste (IDW).

2.2 Groundwater Sampling

2.2.1 Groundwater Collection

Groundwater samples from geoprobe boreholes installed during Preliminary Groundwater and CAP-Part A investigations were collected using a geoprobe sampler or from temporary piezometers. The geoprobe sampler is a probe that allows the collection of a groundwater sample from a discrete undisturbed depth interval in a soil boring. Temporary piezometers were constructed of 1.0-inch inside diameter (ID) polyvinyl chloride (PVC) casing with a 5-foot or 10-foot screened interval. These piezometers were installed in the open borehole following completion of all drilling activities.

Each soil borehole was advanced to the top of the water table using direct push methods. For each borehole, the geoprobe sampler was lowered to the bottom of the borehole and driven through the undisturbed soil to a depth of approximately 3.0 feet below the water table. The outer casing of the geoprobe sampler was retracted to expose the screen and allow groundwater to enter the chamber. In cases where the geoprobe sampler could not be driven or where groundwater recovery through the geoprobe sampler was poor, the groundwater sample was collected through the temporary piezometer.

Groundwater samples were collected using a peristaltic pump or a 0.75-inch diameter stainless steel bailer. The portion of the sample designated for volatile organic analysis was poured into laboratory sample containers first, followed by pouring the remaining sample portion into containers designated for other types of chemical analyses. Sample containers designated for volatile organic analysis were filled so that no headspace was present in the containers.

2.2.2 Field Measurements

Groundwater field measurements performed during the project included measurement of static groundwater level, pH, specific conductance, and temperature. Measurement of groundwater levels in soil boreholes was accomplished through the installation of temporary PVC piezometers. A summary of the procedures and criteria to be used for groundwater sample field measurements is presented in the following sections.

Static Groundwater Level

Static groundwater level measurements were made using an electronic water level indicator. Initially, the indicator probe was lowered into each temporary piezometer casing until the alarm sounded and/or the indicator light illuminated. The probe was withdrawn several feet and slowly lowered again until the groundwater surface was contacted as noted by the alarm and/or indicator light. Water level measurements were estimated to the nearest 0.01 foot based on the difference between the nearest probe cord mark to the top of the piezometer casing.

The distance between the top of casing and the surrounding ground surface was taken into account in measuring the water level to within 0.01 foot. The static water level measurement procedure was repeated two or three times to ensure that the water level measurements were consistent (plus or minus 0.01 foot). If this was the case, then the first measured level was recorded as the depth to groundwater. If this was not the case, the procedure was repeated until consistent readings were obtained from three consecutive measurements.

pH, Specific Conductance, and Temperature

The pH, specific conductance, and temperature measurements were recorded for groundwater during groundwater sampling. The pH, temperature, and conductivity measurements were made using a combination meter designed to measure these parameters. A portion of each groundwater sample was retrieved from the PowerPunch sampler and poured into the collection cup. With the combination meter set in the pH mode, the meter electrode was swirled at a slow constant rate within the sample until the meter reading reached equilibrium. The sample pH was recorded to the nearest 0.1 pH unit. The pH measurement procedure was repeated, using a new sample each time, until the pH measurements were consistent (less than 0.2 pH units variation).

Upon completion of the pH measurement, conductivity and temperature measurements were made on a groundwater sample collected in the same manner as described above. With the combination meter set in the conductivity mode, the meter electrode was swirled at a slow constant rate within the sample until the meter reading reached equilibrium. Concurrently, a temperature probe was placed into the sample and allowed to reach equilibrium. The sample conductivity was recorded to the nearest 10 mmhos/cm and the temperature to the nearest 0.1° C. All recorded conductivity values were converted to conductance at 25° C. The conductivity and temperature measurement procedure was repeated a minimum of three times using a new sample each time, until the measurements were consistent (less than 10 percent variation for conductance and less than 0.5° C variation for temperatures).

2.3 Temporary Piezometer Installation

Following the collection of the groundwater sample, a 1.0-inch PVC piezometer, with a 5-foot or 10-foot screened section, was installed in the borehole to prevent the borehole from collapsing. These piezometers remained in the boreholes approximately 24 hours, after which time the static water level was measured. During field activities in November 1998 or later, the temporary piezometers were screened from ground surface to the bottom of the borehole.

2.4 Borehole Abandonment

Once the static water level was measured, the temporary piezometers were removed and the boreholes were abandoned. Abandonment was conducted in a manner precluding any current or subsequent fluid media from entering or migrating within the subsurface environment along the axis or from the endpoint of the borehole. Abandonment was accomplished by filling the entire volume of the borehole with grout.

2.5 Surveying

A topographic survey of the horizontal and vertical locations of all soil boreholes was conducted after completion of all field activities. The topographic survey was conducted by a surveyor registered in the state of Georgia.

The horizontal coordinates for each soil borehole were surveyed to the closest 1.0 foot and referenced to the State Plane Coordinate System. Ground elevations were surveyed to the closest 0.1 foot. Elevations were referenced to the National Geodetic Vertical Datum of 1983.

2.6 Decontamination Procedures

2.6.1 Geoprobe Equipment

Decontamination of equipment used for drilling boreholes was conducted within the temporary decontamination pad constructed at the central staging area. The decontamination pad was constructed so that all decontamination liquids were contained from the surrounding environment and were recovered for disposal as IDW. The entire geoprobe vehicle and equipment were decontaminated once they arrived on site and the geoprobe sampling equipment was decontaminated after completion of each soil borehole. The equipment was decontaminated by removing the caked soil material from the exterior of equipment using a rod and/or brush, steam cleaning the interior and exterior of equipment, allowing the equipment to air dry as long as possible, and wrapping or covering the equipment in plastic.

2.6.2 Sampling Equipment

Decontamination of equipment used for soil sampling and collection of groundwater samples was conducted at the temporary decontamination area. Nondedicated equipment was decontaminated after each use. The sampling equipment was washed with potable water and phosphate-free detergent using various types of brushes required to remove particulate matter and surface films, followed by a potable water rinse, American Society for Testing and Materials (ASTM) Type I or equivalent water rinse, isopropyl alcohol rinse, ASTM Type I or equivalent water rinse, allowed to air dry, and wrapped in plastic or aluminum foil.

In addition to the sampling equipment, field measurement instruments were also decontaminated between uses. Only those portions of each instrument that come into contact with potentially contaminated environmental media were decontaminated. Because of the delicate nature of these instruments, the decontamination procedure only involved initial rinsing of the instrument probes with ASTM Type I or equivalent water.

2.7 Documentation of field activities

All information pertinent to sampling activities, including instrument calibration data, was recorded in field logbooks. The logbooks were bound and the pages consecutively numbered. Entries in the logbooks were made in black permanent ink and included, at a minimum, a description of all activities, individuals involved in drilling and sampling activities, date and time of drilling and sampling, weather conditions, any problems encountered, and all field measurements.

Sufficient information was recorded in the logbooks to permit reconstruction of all sampling activities. For a detailed description of all field documentation, see section 4.5 of Attachment IV of the Work Plan.

3.0 SAMPLE HANDLING AND ANALYSIS

3.1 Analytical Program

Soil samples were screened for the presence of volatile vapors using a MiniRae organic vapor analyzer (PID). The MiniRae was calibrated daily using 100 parts per million (ppm) isobutylene. The headspace of each sample was measured approximately 15 minutes after collection.

For sites where the UST had contained used oil, soil samples were analyzed for BTEX by method SW846-8020, PAH by method SW846-8270, TPH by method SW846-9073, and lead by method SW846-6010/7000, during the May and June 1998 field effort. Beginning in November 1998, BTEX was analyzed using method SW846-5035/8260B, while the analyses for the other contaminants remained the same. Groundwater samples were analyzed for BTEX by method SW846-8260 and PAH by method SW 846-8270. All samples were sent to General Engineering Laboratories, Charleston, South Carolina.

For sites where the UST had contained gasoline or diesel, soil samples were analyzed for BTEX by method SW846-8020, PAH by method SW846-8270, TPH by method SW846-8015 (modified), and lead by method SW846-6010/7000. Groundwater samples were analyzed for BTEX by method SW846-8260 and PAH by method SW 846-8270. TPH analysis included both gasoline range organics (GRO) and diesel range organics (DRO). Beginning in November 1998, soil samples were analyzed for BTEX using method SW846-5035/8260B. All samples were sent to General Engineering Laboratories, Charleston, South Carolina.

Duplicate samples of soil and groundwater were collected throughout the project and represented approximately 10 percent of the total sample population. Rinsate blanks were collected to determine whether the sampling equipment was causing cross-contamination of the samples and represented approximately 5 percent of the total sample population. Duplicates and rinsates were submitted to General Engineering Laboratories, Charleston, South Carolina.

3.2 Sample Containers, Preservation, and Holding Times

The soil sample containers, preservatives, and holding times are summarized in Table A-1. The groundwater sample containers, preservatives, and holding times are summarized in Table A-2.

3.3 Sampling Packaging and Shipment

Each sample container was labeled, taped shut with electrical tape (except those containing samples designated for volatile organic analysis), and an initialed/dated custody seal was placed over the lid. Each sample bottle was placed into a separate plastic bag and sealed. The samples were placed upright in thermally insulated rigid-body coolers and surrounded by vermiculite to prevent breakage during shipment. In addition, samples were cooled to approximately 4° C with wet ice. These measures were taken to slow the decomposition and volatilization of contaminants during shipping and handling. The sample coolers were shipped to the analytical laboratory via courier service provided by the laboratory.

Table A-1. Summary of Sample Containers, Preservation Techniques, and Holding Times for Soil Samples Collected During the Site Investigation

Analyte Group	Container	Minimum Sample Size	Preservative	Holding Time
BTEX/TPH-GRO	1 – 4 oz jar with Teflon®-lined cap (no headspace)	20 g	Cool, 4°C	14 d
BTEX (beginning 11/98)	3 – En Core™ Samplers	15 g	Cool, 0°C	48 hrs
TPH-GRO (beginning 11/98)	1 – 4 oz jar with Teflon®-lined cap (no headspace)	20 g	Cool, 4°C	14 d
PAHs	1 – 8 oz jar with Teflon®-lined cap	90 g	Cool, 4°C	14 d (extraction) 40 d (analysis)
TPH-DRO	use same container as PAHs	90 g	Cool, 4°C	14 d (extraction) 40 d (analysis)
TPH	use same container as PAHs	90 g	Cool, 4°C	14 d (extraction) 40 d (analysis)
Metals (lead)	use same container as PAHs	20 g	Cool, 4°C	180 d

Table A-2. Summary of Sample Containers, Preservation Techniques, and Holding Times for Groundwater Samples Collected During the Site Investigation

Analyte Group	Container	Minimum Sample Size	Preservative	Holding Time
BTEX	2 – 40 mL glass vials with Teflon®-lined septum (no headspace)	40 mL	Cool, 4°C HCl to pH < 2	14 d
PAHs	2 – 1L amber glass bottle with Teflon®-lined lid	1000 mL	Cool, 4°C	7 d (extraction) 40 d (analysis)

ATTACHMENT B

REFERENCES

THIS PAGE INTENTIONALLY LEFT BLANK

- Anderson Columbia Environmental Inc., 1996. *Closure Report, Used Oil Tank Removal, Building 1720, Tank 28B*, Facility ID: 9-089011, Fort Stewart, Georgia, October.
- Arora, Ram, 1984. *Hydrologic Evaluation for Underground Injection Control in the Coastal Plain of Georgia*, Department of Natural Resources, Environmental Protection Division, Georgia Geological Survey.
- GA EPD (Georgia Environmental Protection Division), 1992, *Groundwater Pollution Susceptibility Map of Georgia*.
- Geraghty and Miller, 1993. *RCRA Facility Investigation Work Plan*, Fort Stewart, Georgia.
- Herrick, S.M. and Vorchis, R.C. 1963. *Subsurface Geology of the Georgia Coastal Plain*, Georgia Geologic Survey Information Circular 25.
- Looper, Edward E., 1980. *Soil Survey of Liberty and Long Counties, Georgia*, U.S. Department of Agriculture, Soil Conservation Service.
- Miller, James A., 1990. *Groundwater Atlas of the United States*, U.S. Department of the Interior, U.S. Geological Survey, Hydrologic Inventory Atlas 730G.
- Perez, Ovidio E., 1998. Letter to William Logan (Georgia Department of Natural Resources, Environmental Protection Division, Underground Storage Tank Management Program) September 15, 1998.

THIS PAGE INTENTIONALLY LEFT BLANK

ATTACHMENT C

SUPPLEMENTAL INFORMATION
RISK-BASED CORRECTIVE ACTION

THIS PAGE INTENTIONALLY LEFT BLANK

1. RISK-BASED CORRECTIVE ACTION

A risk-based approach was used to aid in the decision making process to determine the need for further action at the UST 28B site. Due to the nature of the contamination (petroleum hydrocarbon contamination of groundwater), the risk-based approach was limited to human health concerns. Ecological risk concerns are negligible because of the lack of habitat available for ecological receptors as a result of the 10 to 12 inches of concrete overlying the majority of the site.

The methods for assessing human health concerns for the site were derived from GUST CAP-Part B guidance (GA EPD 1995) and recent GA EPD guidance (GA EPD 1996). These were supplemented by the additional guidance documents on risk assessment methods referenced in this section. In general, the risk-based corrective action approach is performed in two steps:

1. Results were screened against readily available regulatory levels and risk-based screening levels to identify chemicals of potential concern (COPCs).
2. Site-specific ACLs were developed for COPCs using the results of the fate and transport modeling and identified receptor locations.

The following sections present the conceptual model of the exposure setting and potential receptors as well as the general methodology employed to perform the screening for COPCs and the development of ACLs.

1.1 Potential receptor survey

The exposure assessment identifies any potentially complete pathways between the contaminant source and potential receptors. This involves identifying potential current and future receptors, release mechanisms through which contamination might come into contact with the receptors, and the routes of exposure through which the receptors might be exposed.

The UST 28B site is located within Fort Stewart, an active military installation, and within an access-controlled fence of a secured motorpool. The land use at the site is currently military industrial. In the direction of groundwater flow, an storm drain is located approximately 225 feet southeast of the site, a drainage ditch is located approximately 250 feet southeast of the site, and Mill Creek is located approximately 3000 feet southeast of the site.

No connection between site contamination and current off-site receptors has been identified. Site contamination may migrate to the surficial aquifer. The Hawthorn Group separates the surficial aquifer from the deep drinking water aquifer, the Floridan aquifer, which is approximately 90 feet of clay. There appears to be no vertical migration from the surficial aquifer to the Floridan aquifer. Well #3 is located approximately 1200 feet upgradient of the UST 28B site. However, the Hawthorn Group, a thick and highly effective confining unit, separates the water supply well from the surficial aquifer.

No current on-site receptors have been identified for the site. Potential future on-site receptors might include industrial workers and military residents.

Potential future on-site industrial receptors may come in direct contact with site soil contamination during construction or excavation activities. No near-term on-site receptors are likely to come into contact with groundwater, unless the surficial aquifer discharges into the drainage ditch.

1.2 Screening for Chemicals of Potential Concern

1.2.1 Screening Methodology

The purpose of a risk evaluation screen is to identify the COPCs and areas of concern at a site and possibly to identify sites for which no further action is needed. The first step in the risk process uses screening levels that are readily obtainable and that, due to their conservative nature, can be used with a high degree of confidence to indicate sites for which no further action is required.

An American Society of Testing and Materials (ASTM) (ASTM 1995) Tier 1-type risk evaluation process will be applied to the data collected for the UST 28B site to identify any COPCs and media for which no further action is needed. The risk evaluation screen involves the steps listed below.

- Identify potential migration and exposure pathways associated with the site, and identify potential exposure scenarios that should be used to select screening levels.
- Identify risk-based screening levels and regulatory based screening levels for each contaminant.
- Compare site-related concentrations to screening levels to determine if any potential COPCs exist at the site.
- Compare detection limits to screening levels to identify potential false negative screening results.

The screening levels for the UST 28B site data have been taken from the following sources based on GA EPD guidance (GA EPD 1996):

- federal MCLs (EPA 1989),
- GUST Soil Threshold Levels (i.e., Table A, Column 2),
- soil screening levels developed by the U.S. Environmental Protection Agency (EPA) (EPA 1996a), and
- soil and groundwater risk-based concentrations developed by EPA Region 3 (EPA 1996b).

These values reflect screening levels based on a combination of regulatory screening levels (i.e., MCLs and GUST soil threshold levels), and calculated risk-based values (i.e., EPA Region 3 risk-based concentrations).

Screening levels inherently incorporate assumptions about land use. In identifying COPCs, it is generally accepted that screening levels will reflect any potential future land uses, and thus, they usually reflect a conservative residential use scenario (EPA 1991; EPA 1996a; ASTM 1995). Based on GA EPD guidance, risk-based screening levels reflect residential land use for groundwater and industrial land use for deep soils (GA EPD 1996).

Default residential exposure scenarios for groundwater assume that use of the land could someday be residential and that the following exposures could occur:

- ingestion of groundwater and
- inhalation of volatiles during showering.

The default industrial exposure assumptions for deep soils assume that the following exposures could occur:

- incidental ingestion of soil and
- inhalation of volatiles and dust.

EPA's *Soil Screening Guidance* (EPA 1996a) provides two options for selecting soil values that address protection of groundwater. One value assumes no contaminant dilution or attenuation would occur between the soil and groundwater; a second value assumes a 20-fold dilution attenuation factor (DAF). A DAF of 20 was used to develop soil screening values protective of groundwater at the UST 28B site.

If ARAR- or risk-based values are not available, it generally means that (1) the chemical is not considered to be toxic except perhaps at extremely high concentrations (e.g., aluminum, sodium); (2) the dose-response data do not indicate a toxic effect; or (3) EPA is currently reviewing toxicity information, and no reference dose or cancer slope factor is currently available.

1.2.2 Screening Results

The risk screening process is a systematic screening of sample results to identify site-related COPCs. Constituent concentrations below risk- or regulatory-based screening levels are not considered COPCs and are not evaluated further. Table C-1 presents the results of the risk-based screening for the Part A SI soil data. Table C-2 presents the results of the risk-based screening for the Part A SI groundwater data.

No constituents were detected above the GUST soil threshold levels or the risk-based screening levels for soil data collected for the Part A SI. Toluene, lead, and TPH were detected below screening levels during the Part A sampling. No constituents were selected as COPCs for UST 28B site soils.

The detection limits for benzo(a)pyrene and dibenzo(a,h)anthracene exceeded risk-based screening values in three samples. The detection limit for benzo(a)anthracene exceeded the leaching to groundwater risk-based screening value in one of those samples. The elevated detection limits were the result of analytical dilutions of the samples to account for matrix interference during analysis. Detection limits represent levels of confidence where a reported value above the level is considered an accurate value. But estimated values may be detected and reported below the detection limits within the instrument's range of detection. No COPCs for soils were selected based on a detection limit screening.

Benzene was detected in two temporary wells at concentrations above screening levels. The detections ranged from 128 µg/L (well 60-01) to 171 µg/L (well 60-02). These results exceeded the risk-based screening level for benzene of 0.36 µg/L and the federal MCL for benzene of 5 µg/L. Ethylbenzene, toluene, and xylenes were detected below screening values for the Part A SI. Benzene was selected as a COPC for the UST 28B site groundwater.

Detection limits for benzene and several PAHs exceeded risk-based screening levels. For these constituents, risk-based values represent values below analytically achievable levels. The detection limits for one PAH, benzo(a)pyrene, also exceeded the federal MCL of 0.2 µg/L by two orders of magnitude. No COPCs for groundwater were selected based on the detection limit screening.

1.3 Site-Specific Levels

Detections exceeding the conservative generic screening levels are considered COPCs. ACLs are developed, when appropriate, for the COPCs using site-specific information from the fate and transport modeling.

1.3.1 Alternate Threshold Levels

No COPCs were identified for UST 28B site soils; thus no alternate threshold levels were developed for soils.

1.3.2 Alternative Concentration Limits

Benzene was identified as a COPC for groundwater at the site. Benzene was modeled to two potential downgradient locations where a receptor may come in contact with migrating site contamination. These two locations included a drainage ditch 250 feet downgradient and Mill Creek 3000 feet downgradient from the site. Fate and transport modeling was used to develop site-specific dilution attenuation factors (DAFs) between the source and the receptor locations (see 1.3.3.2 below). The modeling estimated infinite DAFs for the drainage ditch and Mill Creek. An infinite DAF indicates that contamination will never reach these locations, thus no ACLs were developed for the drainage ditch and Mill Creek.

1.3.3 Fate and transport model

1.3.3.1 Model Selection

Site-specific dilution attenuation factors between the source and the receptor locations were developed. The DAF is a numerical value that represents the attempt to mathematically quantify the natural physical, chemical, and biological processes (e.g., advection-dispersion, sorption-retardation, biodegradation, and volatilization) that result in the decrease of a chemical concentration in an environmental medium. In simple terms, the DAF is the ratio of chemical concentration at the source (or the point of origin) to the concentration at the exposure point. The DAFs reflect the natural attenuation concepts outlined in the ASTM's Risk Based Corrective Action (RBCA) protocol (ASTM 1995).

Fate and transport models are used as tools for developing DAFs. The application of fate and transport models at any release site must ensure that the modeling results are protective of human health and the environment. Therefore, the selection process of a predictive model at a release site must consider its performance, characteristics, and applicability to the site being considered. The following characteristics were considered before selecting an appropriate model for Fort Stewart:

- the model provides conservative predictions,
- the model is technically sound,
- the model is a public-domain model or is readily available,
- the model has received adequate peer review,
- the model has been applied to other similar sites, and
- the model is easy to use.

The Analytical Transient 1-, 2-, 3-Dimensional Model (AT123D) meets all of the above criteria, and was selected for performing fate and transport analysis for this site. AT123D is a well-known and commonly used analytical groundwater pollutant fate and transport model. It computes the spatial-temporal

concentration distribution of chemicals in the aquifer system and predicts the transient spread of a chemical plume through a groundwater aquifer. The fate and transport processes accounted for in AT123D are advection, dispersion, adsorption/retardation, and decay. This model can be used as a tool for estimating the dissolved concentration of a chemical in one, two, or three dimensions in the groundwater, resulting from a mass release (either continuous or instant or depleting source) over a source area (i.e., point, line, area, or volume source).

1.3.3.2 Fate and Transport Results

The AT123D model was used to determine the impact of dissolved hydrocarbons on potential receptors. A steady-state AT123D model was developed by calibrating the model against observed maximum concentrations in the groundwater (i.e., 171 $\mu\text{g/L}$) beneath the UST 28B site. Site-specific geotechnical information was collected during the CAP-Part A investigation and is presented in Table C-3. Modeling of the leaching of soil contamination to the groundwater was not performed because the additional contaminant contribution to the groundwater was negligible compared to the existing groundwater contamination. Potential receptors are a drainage ditch located 250 feet southeast of the site and Mill Creek located approximately 3000 feet south of the site. The storm drain catch basin located approximately 125 feet southeast of the site and the invert elevation is approximately 3.0 feet above the water table and is not considered a potential preferential pathway.

Vertical migration of the contaminant plume through the confining unit to the Principal Artesian aquifer is improbable. The confining unit has a vertical hydraulic conductivity on the order of 10^{-8} cm/sec and ranges from 15 to 90 feet in thickness. Assuming a vertical gradient of 1.0 ft/ft and an effective porosity of 0.06 (Mills et al. 1985) for the confining unit, the groundwater travel time is estimated to be 87 years. However, benzene will not travel at the same speed as water because of retardation due to adsorption. The retardation factor for benzene through the confining unit is 5.05. Therefore, the travel time for benzene through the confining unit (15 feet thick) is greater than 400 years (i.e., $87 \text{ years} \times 5.05 = 439$ years). The surficial aquifer in which the contaminant plume is located is not used as a source of drinking water.

The fate and transport modeling results are provided in Table C-4 and Section 1.5. Two potential downgradient locations, a drainage ditch and Mill Creek, at which a receptor might encounter migrating groundwater contamination, were modeled. These are the nearest possible locations at which a receptor might encounter migrating groundwater contamination due to a possible hydraulic connection between the groundwater and the surface water in the ditch and the creek. Contaminant fate and transport simulations were performed to predict the maximum concentrations at these receptor locations over a simulation period of 100 years. The modeling results indicate that the benzene concentrations at the drainage ditch and Mill Creek are predicted to be 0 $\mu\text{g/L}$. Therefore, potential receptors and surface water will not be impacted at concentrations above MCLs by the current site conditions at the UST 28B site, Facility ID #: 9-089011.

Based on modeling results, the estimated DAFs for at the drainage ditch and Mill Creek are both infinity, indicating that the predicted concentrations at these receptors are zero. Simulations were not performed to predict the maximum concentrations of benzene over a simulation period of two years because there are no permanent monitoring wells at the site to confirm the model predictions. This simulation will be performed during the CAP-Part B or long-term monitoring at the site.

1.4 Conclusions and recommendations

The conclusions below are based on a fate and transport modeling assuming a continuous source of contamination of infinite duration at the site based on the maximum observed benzene concentration (i.e., 171 µg/L) in groundwater during the CAP-Part A investigation.


- Risk-based screening results show that benzene concentrations in groundwater exceed the initial screening levels.
- The modeling of benzene estimated infinite DAFs for the drainage ditch and Mill Creek indicating that contamination will never reach these locations, thus no ACLs were developed for these locations.
- The horizontal and vertical extent of soil and groundwater contamination was determined during the CAP-Part A investigation.
- Fate and transport modeling of benzene indicates that contamination does not exceed MCLs at the conservatively defined downgradient receptors, a drainage ditch and Mill Creek.

Considering the site characteristics, a monitoring only plan is recommended to confirm that natural attenuation is taking place at the site.

1.5 Fate and Transport Model Output Results

Following are the data for fate and transport modeling.

**Figure C-1. AT123D modeled maximum concentration of benzene in the groundwater
versus downgradient distance from the source (USTs 28B)**



Ft Stewart UST 28B Benzene (calibrated plume)

NO. OF POINTS IN X-DIRECTION	9
NO. OF POINTS IN Y-DIRECTION	5
NO. OF POINTS IN Z-DIRECTION	1
NO. OF ROOTS: NO. OF SERIES TERMS	400
NO. OF BEGINNING TIME STEP	145
NO. OF ENDING TIME STEP	360
NO. OF TIME INTERVALS FOR PRINTED OUT SOLUTION	12
INSTANTANEOUS SOURCE CONTROL = 0 FOR INSTANT SOURCE	1
SOURCE CONDITION CONTROL = 0 FOR STEADY SOURCE	0
INTERMITTENT OUTPUT CONTROL = 0 NO SUCH OUTPUT	1
CASE CONTROL =1 THERMAL, = 2 FOR CHEMICAL, = 3 RAD	2
AQUIFER DEPTH, = 0.0 FOR INFINITE DEEP (METERS) ...	0.1040E+02
AQUIFER WIDTH, = 0.0 FOR INFINITE WIDE (METERS) ...	0.0000E+00
BEGIN POINT OF X-SOURCE LOCATION (METERS)	-0.3700E+01
END POINT OF X-SOURCE LOCATION (METERS)	0.0000E+00
BEGIN POINT OF Y-SOURCE LOCATION (METERS)	-0.2740E+01
END POINT OF Y-SOURCE LOCATION (METERS)	0.2740E+01
BEGIN POINT OF Z-SOURCE LOCATION (METERS)	0.0000E+00
END POINT OF Z-SOURCE LOCATION (METERS)	0.2000E+01
POROSITY	0.2000E+00
HYDRAULIC CONDUCTIVITY (METER/HOUR)	0.7200E-02
HYDRAULIC GRADIENT	0.7000E-02
LONGITUDINAL DISPERSIVITY (METER)	0.3000E+01
LATERAL DISPERSIVITY (METER)	0.1000E+01
VERTICAL DISPERSIVITY (METER)	0.3000E+00
DISTRIBUTION COEFFICIENT, KD (M**3/KG)	0.1620E-03
HEAT EXCHANGE COEFFICIENT (KCAL/HR-M**2-DEGREE C) ..	0.0000E+00
MOLECULAR DIFFUSION MULTIPLY BY POROSITY (M**2/HR)	0.3530E-05
DECAY CONSTANT (PER HOUR)	0.4015E-04
BULK DENSITY OF THE SOIL (KG/M**3)	0.1720E+04
ACCURACY TOLERANCE FOR REACHING STEADY STATE	0.1000E-02
DENSITY OF WATER (KG/M**3)	0.1000E+04
TIME INTERVAL SIZE FOR THE DESIRED SOLUTION (HR) ..	0.7300E+03
DISCHARGE TIME (HR)	0.8760E+06
WASTE RELEASE RATE (KCAL/HR), (KG/HR), OR (CI/HR) .	0.4166E-06
RETARDATION FACTOR	0.2393E+01
RETARDED DARCY VELOCITY (M/HR)	0.1053E-03
RETARDED LONGITUDINAL DISPERSION COEF. (M**2/HR) ..	0.3233E-03
RETARDED LATERAL DISPERSION COEFFICIENT (M**2/HR) .	0.1127E-03
RETARDED VERTICAL DISPERSION COEFFICIENT (M**2/HR) .	0.3896E-04

LIST OF Z-EIGENVALUES

0.3021E+00	0.6042E+00	0.9062E+00	0.1208E+01	0.1510E+01	0.1812E+01	0.2115E+01	0.2417E+01	0.2719E+01	0.3021E+01
0.3323E+01	0.3625E+01	0.3927E+01	0.4229E+01	0.4531E+01	0.4833E+01	0.5135E+01	0.5437E+01	0.5739E+01	0.6042E+01
0.6344E+01	0.6646E+01	0.6948E+01	0.7250E+01	0.7552E+01	0.7854E+01	0.8156E+01	0.8458E+01	0.8760E+01	0.9062E+01
0.9364E+01	0.9666E+01	0.9969E+01	0.1027E+02	0.1057E+02	0.1087E+02	0.1118E+02	0.1148E+02	0.1178E+02	0.1208E+02
0.1239E+02	0.1269E+02	0.1299E+02	0.1329E+02	0.1359E+02	0.1390E+02	0.1420E+02	0.1450E+02	0.1480E+02	0.1510E+02
0.1541E+02	0.1571E+02	0.1601E+02	0.1631E+02	0.1661E+02	0.1692E+02	0.1722E+02	0.1752E+02	0.1782E+02	0.1812E+02
0.1843E+02	0.1873E+02	0.1903E+02	0.1933E+02	0.1963E+02	0.1994E+02	0.2024E+02	0.2054E+02	0.2084E+02	0.2115E+02
0.2145E+02	0.2175E+02	0.2205E+02	0.2235E+02	0.2266E+02	0.2296E+02	0.2326E+02	0.2356E+02	0.2386E+02	0.2417E+02
0.2447E+02	0.2477E+02	0.2507E+02	0.2537E+02	0.2568E+02	0.2598E+02	0.2628E+02	0.2658E+02	0.2688E+02	0.2719E+02
0.2749E+02	0.2779E+02	0.2809E+02	0.2840E+02	0.2870E+02	0.2900E+02	0.2930E+02	0.2960E+02	0.2991E+02	0.3021E+02
0.3051E+02	0.3081E+02	0.3111E+02	0.3142E+02	0.3172E+02	0.3202E+02	0.3232E+02	0.3262E+02	0.3293E+02	0.3323E+02
0.3353E+02	0.3383E+02	0.3413E+02	0.3444E+02	0.3474E+02	0.3504E+02	0.3534E+02	0.3565E+02	0.3595E+02	0.3625E+02
0.3655E+02	0.3685E+02	0.3716E+02	0.3746E+02	0.3776E+02	0.3806E+02	0.3836E+02	0.3867E+02	0.3897E+02	0.3927E+02
0.3957E+02	0.3987E+02	0.4018E+02	0.4048E+02	0.4078E+02	0.4108E+02	0.4138E+02	0.4169E+02	0.4199E+02	0.4229E+02
0.4259E+02	0.4289E+02	0.4320E+02	0.4350E+02	0.4380E+02	0.4410E+02	0.4441E+02	0.4471E+02	0.4501E+02	0.4531E+02
0.4561E+02	0.4592E+02	0.4622E+02	0.4652E+02	0.4682E+02	0.4712E+02	0.4743E+02	0.4773E+02	0.4803E+02	0.4833E+02
0.4863E+02	0.4894E+02	0.4924E+02	0.4954E+02	0.4984E+02	0.5014E+02	0.5045E+02	0.5075E+02	0.5105E+02	0.5135E+02
0.5166E+02	0.5196E+02	0.5226E+02	0.5256E+02	0.5286E+02	0.5317E+02	0.5347E+02	0.5377E+02	0.5407E+02	0.5437E+02
0.5468E+02	0.5498E+02	0.5528E+02	0.5558E+02	0.5588E+02	0.5619E+02	0.5649E+02	0.5679E+02	0.5709E+02	0.5739E+02
0.5770E+02	0.5800E+02	0.5830E+02	0.5860E+02	0.5890E+02	0.5921E+02	0.5951E+02	0.5981E+02	0.6011E+02	0.6042E+02
0.6072E+02	0.6102E+02	0.6132E+02	0.6162E+02	0.6193E+02	0.6223E+02	0.6253E+02	0.6283E+02	0.6313E+02	0.6344E+02
0.6374E+02	0.6404E+02	0.6434E+02	0.6464E+02	0.6495E+02	0.6525E+02	0.6555E+02	0.6585E+02	0.6615E+02	0.6646E+02
0.6676E+02	0.6706E+02	0.6736E+02	0.6767E+02	0.6797E+02	0.6827E+02	0.6857E+02	0.6887E+02	0.6918E+02	0.6948E+02
0.6978E+02	0.7008E+02	0.7038E+02	0.7069E+02	0.7099E+02	0.7129E+02	0.7159E+02	0.7189E+02	0.7220E+02	0.7250E+02
0.7280E+02	0.7310E+02	0.7340E+02	0.7371E+02	0.7401E+02	0.7431E+02	0.7461E+02	0.7491E+02	0.7522E+02	0.7552E+02
0.7582E+02	0.7612E+02	0.7643E+02	0.7673E+02	0.7703E+02	0.7733E+02	0.7763E+02	0.7794E+02	0.7824E+02	0.7854E+02
0.7884E+02	0.7914E+02	0.7945E+02	0.7975E+02	0.8005E+02	0.8035E+02</				

LIST OF Z-COEFFICIENTS

[illegible]

0.1923E+00	0.1923E+00	0.1923E+00	0.1923E+00	0.1923E+00	0.1923E+00	0.1923E+00	0.1923E+00	0.1923E+00	0.1923E+00	0.1923E+00
0.1923E+00	0.1923E+00	0.1923E+00	0.1923E+00	0.1923E+00	0.1923E+00	0.1923E+00	0.1923E+00	0.1923E+00	0.1923E+00	0.1923E+00
0.1923E+00	0.1923E+00	0.1923E+00	0.1923E+00	0.1923E+00	0.1923E+00	0.1923E+00	0.1923E+00	0.1923E+00	0.1923E+00	0.1923E+00
0.1923E+00	0.1923E+00	0.1923E+00	0.1923E+00	0.1923E+00	0.1923E+00	0.1923E+00	0.1923E+00	0.1923E+00	0.1923E+00	0.1923E+00
0.1923E+00	0.1923E+00	0.1923E+00	0.1923E+00	0.1923E+00	0.1923E+00	0.1923E+00	0.1923E+00	0.1923E+00	0.1923E+00	0.1923E+00
LIST OF ZS-SERIES										
0.1881E+01	0.1548E+01	0.1071E+01	0.5488E+00	0.7981E-01	-0.2564E+00	-0.4187E+00	-0.4108E+00	-0.2753E+00	-0.7922E-01	
0.1067E+00	0.2270E+00	0.2546E+00	0.1946E+00	0.7826E-01	-0.4951E-01	-0.1458E+00	-0.1826E+00	-0.1543E+00	-0.7692E-01	
0.1900E-01	0.9978E-01	0.1397E+00	0.1290E+00	0.7522E-01	-0.3289E-06	-0.6965E-01	-0.1105E+00	-0.1108E+00	-0.7317E-01	
-0.1287E-01	0.4808E-01	0.8883E-01	0.9666E-01	0.7080E-01	0.2201E-01	-0.3173E-01	-0.7170E-01	-0.8488E-01	-0.6811E-01	
-0.2863E-01	0.1886E-01	0.5763E-01	0.7469E-01	0.6514E-01	0.3344E-01	-0.8490E-02	-0.4573E-01	-0.6560E-01	-0.6191E-01	
-0.3687E-01	0.3289E-06	0.3548E-01	0.5732E-01	0.5844E-01	0.3920E-01	0.7000E-02	-0.2652E-01	-0.4968E-01	-0.5477E-01	
-0.4062E-01	-0.1278E-01	0.1863E-01	0.4257E-01	0.5093E-01	0.4128E-01	0.1752E-01	-0.1165E-01	-0.3591E-01	-0.4695E-01	
-0.4128E-01	-0.2137E-01	0.5466E-02	0.2967E-01	0.4286E-01	0.4073E-01	0.2442E-01	-0.3289E-06	-0.2380E-01	-0.3869E-01	
-0.3968E-01	-0.2677E-01	-0.4807E-02	0.1831E-01	0.3449E-01	0.3821E-01	0.2848E-01	0.9002E-02	-0.1319E-01	-0.3027E-01	
-0.3638E-01	-0.2961E-01	-0.1262E-01	0.8428E-02	0.2608E-01	0.3423E-01	0.3022E-01	0.1570E-01	-0.4031E-02	-0.2195E-01	
-0.3182E-01	-0.3035E-01	-0.1826E-01	0.3289E-06	0.1791E-01	0.2920E-01	0.3004E-01	0.2033E-01	0.3661E-02	-0.1399E-01	
-0.2641E-01	-0.2934E-01	-0.2193E-01	-0.6949E-02	0.1021E-01	0.2349E-01	0.2829E-01	0.2309E-01	0.9864E-02	-0.6602E-02	
-0.2048E-01	-0.2694E-01	-0.2383E-01	-0.1241E-01	0.3193E-02	0.1742E-01	0.2531E-01	0.2418E-01	0.1458E-01	-0.2317E-06	
-0.1436E-01	-0.2345E-01	-0.2417E-01	-0.1638E-01	-0.2955E-02	0.1131E-01	0.2140E-01	0.2381E-01	0.1783E-01	0.5659E-02	
-0.8326E-02	-0.1919E-01	-0.2315E-01	-0.1892E-01	-0.8096E-02	0.5427E-02	0.1686E-01	0.2220E-01	0.1967E-01	0.1026E-01	
-0.2643E-02	-0.1444E-01	-0.2101E-01	-0.2010E-01	-0.1213E-01	0.3289E-06	0.1198E-01	0.1959E-01	0.2022E-01	0.1372E-01	
0.2478E-02	-0.9497E-02	-0.1798E-01	-0.2004E-01	-0.1502E-01	-0.4772E-02	0.7030E-02	0.1622E-01	0.1959E-01	0.1603E-01	
0.6865E-02	-0.4606E-02	-0.1432E-01	-0.1889E-01	-0.1675E-01	-0.8741E-02	0.2255E-02	0.1233E-01	0.1796E-01	0.1720E-01	
0.1039E-01	-0.2595E-06	-0.1028E-01	-0.1682E-01	-0.1737E-01	-0.1180E-01	-0.2133E-02	0.8183E-02	0.1551E-01	0.1730E-01	
0.1297E-01	0.4126E-02	-0.6083E-02	-0.1404E-01	-0.1698E-01	-0.1390E-01	-0.5959E-02	0.4001E-02	0.1245E-01	0.1643E-01	
0.1458E-01	0.7616E-02	-0.1966E-02	-0.1076E-01	-0.1568E-01	-0.1503E-01	-0.9084E-02	0.3289E-06	0.8998E-02	0.1474E-01	
0.1523E-01	0.1035E-01	0.1873E-02	-0.7189E-02	-0.1363E-01	-0.1521E-01	-0.1142E-01	-0.3634E-02	0.5361E-02	0.1238E-01	
0.1498E-01	0.1227E-01	0.5264E-02	-0.3537E-02	-0.1101E-01	-0.1454E-01	-0.1291E-01	-0.6747E-02	0.1743E-02	0.9545E-02	
0.1391E-01	0.1334E-01	0.8071E-02	-0.2749E-06	-0.8003E-02	-0.1312E-01	-0.1356E-01	-0.9223E-02	-0.1669E-02	0.6410E-02	
0.1216E-01	0.1358E-01	0.1020E-01	0.3247E-02	-0.4792E-02	-0.1108E-01	-0.1340E-01	-0.1099E-01	-0.4714E-02	0.3169E-02	
0.9872E-02	0.1304E-01	0.1159E-01	0.6057E-02	-0.1565E-02	-0.8575E-02	-0.1251E-01	-0.1200E-01	-0.7260E-02	0.2317E-06	
0.7205E-02	0.1181E-01	0.1222E-01	0.8315E-02	0.1505E-02	-0.5784E-02	-0.1098E-01	-0.1226E-01	-0.9211E-02	-0.2934E-02	
0.4332E-02	0.1002E-01	0.1213E-01	0.9943E-02	0.4268E-02	-0.2871E-02	-0.8946E-02	-0.1182E-01	-0.1051E-01	-0.5494E-02	
0.1420E-02	0.7785E-02	0.1136E-01	0.1090E-01	0.6598E-02	-0.1964E-06	-0.6553E-02	-0.1075E-01	-0.1112E-01	-0.7570E-02	
-0.1371E-02	0.5269E-02	0.1000E-01	0.1118E-01	0.8399E-02	0.2676E-02	-0.3953E-02	-0.9142E-02	-0.1107E-01	-0.9081E-02	
-0.3900E-02	0.2624E-02	0.8178E-02	0.1081E-01	0.9610E-02	0.5027E-02	-0.1300E-02	-0.7128E-02	-0.1040E-01	-0.9985E-02	
-0.6046E-02	0.3289E-06	0.6008E-02	0.9858E-02	0.1020E-01	0.6947E-02	0.1259E-02	-0.4838E-02	-0.9189E-02	-0.1027E-01	
-0.7719E-02	-0.2460E-02	0.3635E-02	0.8409E-02	0.1019E-01	0.8357E-02	0.3590E-02	-0.2416E-02	-0.7532E-02	-0.9958E-02	
-0.8856E-02	-0.4634E-02	0.1199E-02	0.6573E-02	0.9595E-02	0.9212E-02	0.5580E-02	-0.2915E-06	-0.5548E-02	-0.9104E-02	
-0.9426E-02	-0.6419E-02	-0.1163E-02	0.4472E-02	0.8496E-02	0.9498E-02	0.7141E-02	0.2276E-02	-0.3364E-02	-0.7784E-02	
-0.9431E-02	-0.7740E-02	-0.3325E-02	0.2238E-02	0.6980E-02	0.9231E-02	0.8211E-02	0.4297E-02	-0.1112E-02	-0.6098E-02	
-0.8904E-02	-0.8550E-02	-0.5180E-02	0.2595E-06	0.5152E-02	0.8457E-02	0.8758E-02	0.5965E-02	0.1081E-02	-0.4158E-02	
-0.7901E-02	-0.8834E-02	-0.6643E-02	-0.2118E-02	0.3131E-02	0.7246E-02	0.8781E-02	0.7207E-02	0.3097E-02	-0.2085E-02	
-0.6504E-02	-0.8603E-02	-0.7653E-02	-0.4006E-02	0.1037E-02	0.5687E-02	0.8306E-02	0.7977E-02	0.4834E-02	-0.2317E-06	
-0.4810E-02	-0.7896E-02	-0.8179E-02	-0.5571E-02	-0.1010E-02	0.3885E-02	0.7384E-02	0.8257E-02	0.6210E-02	0.1980E-02	

DISTRIBUTION OF DISSOLVED CHEMICALS IN PPM AT 0.0000E+00 HRS
(ADSORBED CHEMICAL CONC. = 0.1620E+00 * DISSOLVED CHEMICAL CONC.)
Z = 0.00

	X								
Y	0.	1.	2.	3.	4.	5.	6.	7.	8.
5.	0.000E+00	0.000E+00	0.000E+00	0.000E+00	0.000E+00	0.000E+00	0.000E+00	0.000E+00	0.000E+00
4.	0.000E+00	0.000E+00	0.000E+00	0.000E+00	0.000E+00	0.000E+00	0.000E+00	0.000E+00	0.000E+00
3.	0.000E+00	0.000E+00	0.000E+00	0.000E+00	0.000E+00	0.000E+00	0.000E+00	0.000E+00	0.000E+00
2.	0.000E+00	0.000E+00	0.000E+00	0.000E+00	0.000E+00	0.000E+00	0.000E+00	0.000E+00	0.000E+00
0.	0.000E+00	0.000E+00	0.000E+00	0.000E+00	0.000E+00	0.000E+00	0.000E+00	0.000E+00	0.000E+00

DISTRIBUTION OF DISSOLVED CHEMICALS IN PPM AT 0.1051E+06 HRS
(ADSORBED CHEMICAL CONC. = 0.1620E+00 * DISSOLVED CHEMICAL CONC.)
Z = 0.00

	X								
Y	0.	1.	2.	3.	4.	5.	6.	7.	8.
5.	0.165E-01	0.162E-01	0.150E-01	0.133E-01	0.115E-01	0.965E-02	0.798E-02	0.651E-02	0.526E-02
4.	0.365E-01	0.335E-01	0.290E-01	0.242E-01	0.198E-01	0.159E-01	0.126E-01	0.997E-02	0.783E-02
3.	0.796E-01	0.648E-01	0.511E-01	0.398E-01	0.308E-01	0.238E-01	0.183E-01	0.140E-01	0.107E-01
2.	0.136E+00	0.102E+00	0.752E-01	0.562E-01	0.421E-01	0.316E-01	0.238E-01	0.179E-01	0.135E-01
0.	0.171E+00	0.130E+00	0.964E-01	0.715E-01	0.530E-01	0.393E-01	0.292E-01	0.217E-01	0.162E-01

DISTRIBUTION OF DISSOLVED CHEMICALS IN PPM AT 0.1139E+06 HRS
(ADSORBED CHEMICAL CONC. = 0.1620E+00 * DISSOLVED CHEMICAL CONC.)
Z = 0.00

	X								
Y	0.	1.	2.	3.	4.	5.	6.	7.	8.
5.	0.166E-01	0.162E-01	0.150E-01	0.134E-01	0.115E-01	0.970E-02	0.803E-02	0.656E-02	0.531E-02
4.	0.365E-01	0.335E-01	0.291E-01	0.243E-01	0.198E-01	0.159E-01	0.127E-01	0.100E-01	0.789E-02
3.	0.797E-01	0.649E-01	0.511E-01	0.398E-01	0.309E-01	0.238E-01	0.183E-01	0.141E-01	0.108E-01
2.	0.136E+00	0.102E+00	0.753E-01	0.562E-01	0.421E-01	0.317E-01	0.238E-01	0.180E-01	0.136E-01
0.	0.171E+00	0.130E+00	0.965E-01	0.716E-01	0.530E-01	0.394E-01	0.292E-01	0.218E-01	0.163E-01

DISTRIBUTION OF DISSOLVED CHEMICALS IN PPM AT 0.1226E+06 HRS
(ADSORBED CHEMICAL CONC. = 0.1620E+00 * DISSOLVED CHEMICAL CONC.)
Z = 0.00

	X								
Y	0.	1.	2.	3.	4.	5.	6.	7.	8.
5.	0.166E-01	0.162E-01	0.150E-01	0.134E-01	0.115E-01	0.973E-02	0.806E-02	0.660E-02	0.535E-02
4.	0.365E-01	0.336E-01	0.291E-01	0.243E-01	0.198E-01	0.160E-01	0.127E-01	0.101E-01	0.793E-02
3.	0.797E-01	0.649E-01	0.512E-01	0.399E-01	0.309E-01	0.239E-01	0.184E-01	0.141E-01	0.109E-01
2.	0.136E+00	0.102E+00	0.753E-01	0.563E-01	0.422E-01	0.317E-01	0.239E-01	0.180E-01	0.136E-01
0.	0.171E+00	0.130E+00	0.965E-01	0.716E-01	0.531E-01	0.394E-01	0.293E-01	0.218E-01	0.163E-01

DISTRIBUTION OF DISSOLVED CHEMICALS IN PPM AT 0.1314E+06 HRS
(ADSORBED CHEMICAL CONC. = 0.1620E+00 * DISSOLVED CHEMICAL CONC.)
Z = 0.00

Y	0.	1.	2.	3.	X	4.	5.	6.	7.	8.
5.	0.166E-01	0.162E-01	0.151E-01	0.134E-01	0.116E-01	0.974E-02	0.808E-02	0.662E-02	0.537E-02	
4.	0.365E-01	0.336E-01	0.291E-01	0.243E-01	0.199E-01	0.160E-01	0.126E-01	0.101E-01	0.795E-02	
3.	0.797E-01	0.649E-01	0.512E-01	0.399E-01	0.309E-01	0.239E-01	0.184E-01	0.142E-01	0.109E-01	
2.	0.136E+00	0.102E+00	0.753E-01	0.563E-01	0.422E-01	0.317E-01	0.239E-01	0.181E-01	0.137E-01	
0.	0.171E+00	0.130E+00	0.965E-01	0.716E-01	0.531E-01	0.394E-01	0.293E-01	0.219E-01	0.163E-01	

DISTRIBUTION OF DISSOLVED CHEMICALS IN PPM AT 0.1402E+06 HRS
(ADSORBED CHEMICAL CONC. = 0.1620E+00 * DISSOLVED CHEMICAL CONC.)
Z = 0.00

Y	0.	1.	2.	3.	X	4.	5.	6.	7.	8.
5.	0.166E-01	0.162E-01	0.151E-01	0.134E-01	0.116E-01	0.976E-02	0.809E-02	0.663E-02	0.538E-02	
4.	0.366E-01	0.336E-01	0.291E-01	0.243E-01	0.199E-01	0.160E-01	0.128E-01	0.101E-01	0.797E-02	
3.	0.797E-01	0.649E-01	0.512E-01	0.399E-01	0.309E-01	0.239E-01	0.184E-01	0.142E-01	0.109E-01	
2.	0.136E+00	0.102E+00	0.753E-01	0.563E-01	0.422E-01	0.317E-01	0.239E-01	0.181E-01	0.137E-01	
0.	0.171E+00	0.130E+00	0.966E-01	0.716E-01	0.531E-01	0.394E-01	0.293E-01	0.219E-01	0.164E-01	

DISTRIBUTION OF DISSOLVED CHEMICALS IN PPM AT 0.1489E+06 HRS
(ADSORBED CHEMICAL CONC. = 0.1620E+00 * DISSOLVED CHEMICAL CONC.)
Z = 0.00

Y	0.	1.	2.	3.	X	4.	5.	6.	7.	8.
5.	0.166E-01	0.162E-01	0.151E-01	0.134E-01	0.116E-01	0.976E-02	0.810E-02	0.664E-02	0.539E-02	
4.	0.366E-01	0.336E-01	0.291E-01	0.243E-01	0.199E-01	0.160E-01	0.128E-01	0.101E-01	0.798E-02	
3.	0.797E-01	0.649E-01	0.512E-01	0.399E-01	0.309E-01	0.239E-01	0.184E-01	0.142E-01	0.109E-01	
2.	0.136E+00	0.102E+00	0.754E-01	0.563E-01	0.422E-01	0.318E-01	0.239E-01	0.181E-01	0.137E-01	
0.	0.171E+00	0.130E+00	0.966E-01	0.716E-01	0.531E-01	0.394E-01	0.294E-01	0.219E-01	0.164E-01	

DISTRIBUTION OF DISSOLVED CHEMICALS IN PPM AT 0.1577E+06 HRS
(ADSORBED CHEMICAL CONC. = 0.1620E+00 * DISSOLVED CHEMICAL CONC.)
Z = 0.00

Y	0.	1.	2.	3.	X	4.	5.	6.	7.	8.
5.	0.166E-01	0.162E-01	0.151E-01	0.134E-01	0.116E-01	0.977E-02	0.811E-02	0.664E-02	0.539E-02	
4.	0.366E-01	0.336E-01	0.291E-01	0.243E-01	0.199E-01	0.160E-01	0.128E-01	0.101E-01	0.798E-02	
3.	0.797E-01	0.649E-01	0.512E-01	0.399E-01	0.309E-01	0.239E-01	0.184E-01	0.142E-01	0.109E-01	
2.	0.136E+00	0.102E+00	0.754E-01	0.563E-01	0.422E-01	0.318E-01	0.239E-01	0.181E-01	0.137E-01	
0.	0.171E+00	0.130E+00	0.966E-01	0.716E-01	0.531E-01	0.395E-01	0.294E-01	0.219E-01	0.164E-01	

STEADY STATE SOLUTION HAS BEEN OBTAINED BEFORE FINAL SIMULATING TIME

DISTRIBUTION OF DISSOLVED CHEMICALS IN PPM AT 0.1664E+06 HRS
(ADSORBED CHEMICAL CONC. = 0.1620E+00 * DISSOLVED CHEMICAL CONC.)
Z = 0.00

Y	0.	1.	2.	3.	X	4.	5.	6.	7.	8.
5.	0.166E-01	0.162E-01	0.151E-01	0.134E-01	0.116E-01	0.977E-02	0.811E-02	0.665E-02	0.540E-02	
4.	0.366E-01	0.336E-01	0.291E-01	0.243E-01	0.199E-01	0.160E-01	0.128E-01	0.101E-01	0.799E-02	
3.	0.797E-01	0.650E-01	0.512E-01	0.399E-01	0.309E-01	0.239E-01	0.184E-01	0.142E-01	0.109E-01	
2.	0.136E+00	0.102E+00	0.754E-01	0.563E-01	0.422E-01	0.318E-01	0.239E-01	0.181E-01	0.137E-01	
0.	0.171E+00	0.130E+00	0.966E-01	0.716E-01	0.531E-01	0.395E-01	0.294E-01	0.219E-01	0.164E-01	

1.6 References

- ASTM, 1995, *Standard Guide for Risk-Based Corrective Action Applied at Petroleum Release Sites*, ASTM E 1739-95, approved September 10, 1995.
- EPA (U.S. Environmental Protection Agency), 1989, "Environmental Protection Agency National Primary Drinking Water Regulations," 40 *CAR 141*, as amended by 54FR27526,27562, June 29, 1989 and 54FR30001, July 17, 1989, The Bureau of National Affairs, Inc., Washington, DC.
- EPA, 1991, "Risk Assessment Guidance for Superfund, Volume I: Human Health Evaluation Manual, Supplemental Guidance, Standard Default Exposure Factors, Interim Final," OSWER Directive 9285.6-03, EPA, Office of Emergency and Remedial Response, Washington, DC.
- EPA, 1994, *Supplemental Guidance to RAGS: Region IV Bulletin: Development of Health based Preliminary Remediation Goals, Remedial Options and Remediation Levels*, U.S. EPA Region IV, Waste Management Division.
- EPA, 1996a, *Soil Screening Guidance*, Office of Solid Waste and Emergency Response, EPA/540/R-94/101, available from U.S. Government Printing Office, Washington, DC.
- GA EPD (Georgia Environmental Protection Division), 1992, *Groundwater Pollution Susceptibility Map of Georgia*.
- GA EPD, 1995, *Guidance Document for the Preparation of an Underground Storage Tank Corrective Action Plan, Part B*, February.
- GA EPD, 1996, *Guidance for Selecting Media Remediation Levels at RCRA Solid Waste Management Units*, Georgia Environmental Division, Atlanta, GA, November 1996.
- Mills, W.B., D.B. Porcella, M.J. Unga, S.A. Gherini, K.V. Summers, G.L. Rupp, and G.L. Buvois, 1985. *Water Quality Assessment: A Screening Procedure for Toxic and Conventional Pollutants; Parts 1, 2 and 3*, EPA/600/6-85/002, EPA Environment Research Laboratory, Office of Research and Development, Athens, Georgia.

Table C-1. Comparison of Fort Stewart CAP-Part A UST 28B Soil Results to Screening Levels

Station: Sample ID: Sample Interval (ft): Collection Date: Units:	Screening Levels			60-01 600111 0.5 - 2.0 10-May-98 (ug/kg)	60-01 600121 4.0 - 6.0 10-May-98 (ug/kg)	60-02 600221 0.2 - 2.0 10-May-98 (ug/kg)	60-03 600311 0.5 - 2.0 20-Sep-98 (ug/kg)	60-03 600321 4.0 - 6.0 20-Sep-98 (ug/kg)
	GA UST Soil Threshold Level ^a (ug/kg)	Risk-based Screening Level ^b (ug/kg)	Leaching to Groundwater ^c (ug/kg)					
VOLATILE ORGANIC COMPOUNDS								
Benzene	8	200000	30	0.55 U	0.55 U	0.6 UJ	2.2 U	2.2 U
Toluene	6000	410000000	12000	52.3 =	15.2 =	34.2 J	7.9 =	2.2 U
Ethylbenzene	10000	200000000	13000	2.2 U	2.2 U	2.4 UJ	2.2 U	2.2 U
Xylenes, Total	700000	1000000000	190000	6.6 U	6.6 U	7.1 UJ	6.7 U	6.6 U
POLYNUCLEAR AROMATIC HYDROCARBONS								
2-Chloronaphthalene ^d	N/A ^e	82000000	84000	359 U	364 U	3930 U	365 U	365 U
Acenaphthene	N/A ^e	120000000	570000	359 U	364 U	3930 U	365 U	365 U
Acenaphthylene	N/A ^e	61000000	4200000	359 U	364 U	3930 U	365 U	365 U
Anthracene	N/A ^e	610000000	12000000	359 U	364 U	3930 U	365 U	365 U
Benzo(a)anthracene	N/A ^e	7800	2000	359 U	364 U	3930 U	365 U	365 U
Benzo(a)pyrene	N/A ^e	780	8000	359 U	364 U	3930 U	365 U	365 U
Benzo(b)fluoranthene	N/A ^e	7800	5000	359 U	364 U	3930 U	365 U	365 U
Benzo(g,h,i)perylene	N/A ^e	-----	-----	359 U	364 U	3930 U	365 U	365 U
Benzo(k)fluoranthene	N/A ^e	78000	49000	359 U	364 U	3930 U	365 U	365 U
Chrysene	N/A ^e	780000	160000	359 U	364 U	3930 U	365 U	365 U
Dibenzo(a,h)anthracene	N/A ^e	780	2000	359 U	364 U	3930 U	365 U	365 U
Fluoranthene	N/A ^e	82000000	4300000	359 U	364 U	3930 U	365 U	365 U
Fluorene	N/A ^e	82000000	560000	359 U	364 U	3930 U	365 U	365 U
Indeno(1,2,3-cd)pyrene	N/A ^e	7800	14000	359 U	364 U	3930 U	365 U	365 U
Naphthalene	N/A ^e	61000000	4200000	359 U	364 U	3930 U	365 U	365 U
Phenanthrene ^f	N/A ^e	61000000	4200000	359 U	364 U	3930 U	365 U	365 U
Pyrene	N/A ^e	82000000	84000	359 U	364 U	3930 U	365 U	365 U
OTHER ANALYTES								
Lead	—	500000	—	23300 U	2200 =	4400 =	8400 =	13600 J
Total Petroleum Hydrocarbons	—	—	—	23300 U	15900 U	2420000 =	10800 UJ	13600 J

^a Average or higher groundwater pollution susceptibility area (where public water supply is within 2.0 mi.).^b Protective of soil exposure during Industrial Land Use.^c Protective of groundwater ingestion. Used a dilution attenuation factor of 20.^d Values based on naphthalene as a surrogate chemical.^e Not applicable. The screening level exceeds the expected soil concentration under free product condition.^f Values based on pyrene as a surrogate chemical.

Bold values indicate results exceeding Georgia UST action levels

Italicized values indicate results exceeding risk-based screening levels.

Underlined values indicate results exceeding leaching to groundwater screening levels.

U Indicates that the compound was not detected above the reported sample quantitation limit.

J Indicates that the value for the compound was an estimated value.

UJ Indicates that the sample was not detected above an approximate sample quantitation limit.

R Indicates that the sample results are unusable and the presence or absence of the compound could not be verified.

= Indicates that the compound was detected at the concentration reported.

Table C-1. Comparison of Fort Stewart CAP-Part A UST 28B Soil Results to Screening Levels (continued)

Station: Sample ID: Sample Interval (ft): Collection Date: Units:	Screening Levels			Leaching to Groundwater ^c (ug/kg)	60-04				60-05				60-06			
	Georgia UST Corrective Action Levels for Soil ^a (ug/kg)	Risk-based Screening Level ^b (ug/kg)			600411	600421	600511	600521	600611	600621	18-Sep-98	18-Sep-98	18-Sep-98	18-Sep-98		
	(ug/kg)	(ug/kg)			(ug/kg)	(ug/kg)	(ug/kg)	(ug/kg)	(ug/kg)	(ug/kg)	(ug/kg)	(ug/kg)	(ug/kg)			
VOLATILE ORGANIC COMPOUNDS																
Benzene	8	200000	30	2.1 U	2.1 U	2.2 U	2.3 U	2.1 U	2.3 U	2.1 U	2.3 U	2.1 U	2.3 U	2.3 U		
Toluene	6000	410000000	12000	2.1 U	2.3 =	4 =	2.3 U	11.1 =	4 =	2.1 U	2.3 U	11.1 =	4 =	2.3 U		
Ethylbenzene	10000	200000000	13000	2.1 U	2.1 U	2.2 U	2.3 U	2.1 U	2.3 U	2.1 U	2.3 U	2.1 U	2.3 U	2.3 U		
Xylenes, Total	700000	1000000000	190000	6.4 U	6.4 U	6.7 U	6.9 U	6.4 U	6.9 U	6.2 U	6.9 U	6.2 U	6.9 U	6.8 U		
POLYNUCLEAR AROMATIC HYDROCARBONS																
2-Chloronaphthalene ^d	N/A ^e	82000000	84000	1400 U	350 U	370 U	382 U	350 U	382 U	1370 U	382 U	1370 U	378 U	378 U		
Acenaphthene	N/A ^e	120000000	570000	1400 U	350 U	370 U	382 U	350 U	382 U	1370 U	382 U	1370 U	378 U	378 U		
Acenaphthylene	N/A ^e	61000000	4200000	1400 U	350 U	370 U	382 U	350 U	382 U	1370 U	382 U	1370 U	378 U	378 U		
Anthracene	N/A ^e	610000000	12000000	1400 U	350 U	370 U	382 U	350 U	382 U	1370 U	382 U	1370 U	378 U	378 U		
Benzo(a)anthracene	N/A ^e	7800	2000	1400 U	350 U	370 U	382 U	350 U	382 U	1370 U	382 U	1370 U	378 U	378 U		
Benzo(a)pyrene	N/A ^e	780	8000	1400 U	350 U	370 U	382 U	350 U	382 U	1370 U	382 U	1370 U	378 U	378 U		
Benzo(b)fluoranthene	N/A ^e	7800	5000	1400 U	350 U	370 U	382 U	350 U	382 U	1370 U	382 U	1370 U	378 U	378 U		
Benzo(g,h,i)perylene	N/A ^e	—	—	1400 U	350 U	370 U	382 U	350 U	382 U	1370 U	382 U	1370 U	378 U	378 U		
Benzo(k)fluoranthene	N/A ^e	78000	49000	1400 U	350 U	370 U	382 U	350 U	382 U	1370 U	382 U	1370 U	378 U	378 U		
Chrysene	N/A ^e	780000	160000	1400 U	350 U	370 U	382 U	350 U	382 U	1370 U	382 U	1370 U	378 U	378 U		
Dibenzo(a,h)anthracene	N/A ^e	780	2000	1400 U	350 U	370 U	382 U	350 U	382 U	1370 U	382 U	1370 U	378 U	378 U		
Fluoranthene	N/A ^e	820000000	4300000	1400 U	350 U	370 U	382 U	350 U	382 U	1370 U	382 U	1370 U	378 U	378 U		
Fluorene	N/A ^e	820000000	560000	1400 U	350 U	370 U	382 U	350 U	382 U	1370 U	382 U	1370 U	378 U	378 U		
Indeno(1,2,3-cd)pyrene	N/A ^e	7800	14000	1400 U	350 U	370 U	382 U	350 U	382 U	1370 U	382 U	1370 U	378 U	378 U		
Naphthalene	N/A ^e	61000000	4200000	1400 U	350 U	370 U	382 U	350 U	382 U	1370 U	382 U	1370 U	378 U	378 U		
Phenanthrene ^f	N/A ^e	61000000	4200000	1400 U	350 U	370 U	382 U	350 U	382 U	1370 U	382 U	1370 U	378 U	378 U		
Pyrene	N/A ^e	82000000	84000	1400 U	350 U	370 U	382 U	350 U	382 U	1370 U	382 U	1370 U	378 U	378 U		
OTHER ANALYTES																
Lead	—	5000000	—	2000 UJ	3400 =	27800 J	3200 =	2660000 J	3500 =	27800 J	3200 =	2660000 J	3500 =	265000 J		
Total Petroleum Hydrocarbons	—	—	—	2000 UJ	23900 J	27800 J	7020 UJ	2660000 J	265000 J	27800 J	7020 UJ	2660000 J	265000 J	265000 J		

^a Average or higher groundwater pollution susceptibility area (where public water supply is within 2.0 mi.).

^b Protective of soil exposure during Industrial Land Use.

^c Protective of groundwater ingestion. Used a dilution attenuation factor of 20.

^d Values based on naphthalene as a surrogate chemical.

^e Not applicable. The screening level exceeds the expected soil concentration under free product condition.

^f Values based on pyrene as a surrogate chemical.

Bold values indicate results exceeding Georgia UST action levels

Italicized values indicate results exceeding risk-based screening levels.

Underlined values indicate results exceeding leaching to groundwater screening levels.

U Indicates that the compound was not detected above the reported sample quantitation limit.

J Indicates that the value for the compound was an estimated value.

UJ Indicates that the sample was not detected above an approximate sample quantitation limit.

R Indicates that the sample results are unusable and the presence or absence of the compound could not be verified.

= Indicates that the compound was detected at the concentration reported.

Table C-2. Comparison of Fort Stewart CAP-Part A UST 28B Groundwater Results to Screening Levels

Station:	Screening Levels		60-01 600112 2.0 - 12.0 10-May-98 (ug/L)	60-02 600212 0.0 - 12.0 10-May-98 (ug/L)	60-03 600312 0.1 - 10.1 18-Sep-98 (ug/L)	60-04 600412 0.0 - 10.0 18-Sep-98 (ug/L)	60-05 600512 0.0 - 9.5 18-Sep-98 (ug/L)
Sample ID:	Federal						
Sample Interval (ft):	SDWA MCLs	Risk-based*					
Collection Date:	(ug/L)	(ug/L)					
Units:							
VOLATILE ORGANIC COMPOUNDS							
Benzene	5	0.36	128 =	171 =	2 U	2 U	2 U
Toluene	1000	750	424 =	512 =	2 U	2 U	2 U
Ethylbenzene	700	1300	50 U	17.8 =	2 U	2 U	2 U
Xylenes, Total	10000	12000	88.8 J	92 =	6 U	6 U	6 U
POLYNUCLEAR AROMATIC HYDROCARBONS							
2-Chloronaphthalene ^b	-	1500	10 U	42.1 U	12.5 UJ	10.8 U	10.1 U
Acenaphthene	-	2200	10 U	42.1 U	12.5 UJ	10.8 U	10.1 U
Acenaphthylene	-	1100	10 U	42.1 U	12.5 UJ	10.8 U	10.1 U
Anthracene	-	11000	10 U	42.1 U	12.5 UJ	10.8 U	10.1 U
Benzo(a)anthracene	-	0.092	10 U	42.1 U	12.5 UJ	10.8 U	10.1 U
Benzo(a)pyrene	0.2	0.0092	10 U	42.1 U	12.5 UJ	10.8 U	10.1 U
Benzo(b)fluoranthene	-	0.092	10 U	42.1 U	12.5 UJ	10.8 U	10.1 U
Benzo(g,h,i)perylene	-	-	10 U	42.1 U	12.5 UJ	10.8 U	10.1 U
Benzo(k)fluoranthene	-	0.92	10 U	42.1 U	12.5 UJ	10.8 U	10.1 U
Chrysene	-	9.2	10 U	42.1 U	12.5 UJ	10.8 U	10.1 U
Dibenzo(a,h)anthracene	-	0.0092	10 U	42.1 U	12.5 UJ	10.8 U	10.1 U
Fluoranthene	-	1500	10 U	42.1 U	12.5 UJ	10.8 U	10.1 U
Fluorene	-	1500	10 U	42.1 U	12.5 UJ	10.8 U	10.1 U
Indeno(1,2,3-cd)pyrene	-	0.092	10 U	42.1 U	12.5 UJ	10.8 U	10.1 U
Naphthalene	-	1500	10 U	42.1 U	12.5 UJ	10.8 U	10.1 U
Phenanthrene ^c	-	1100	10 U	42.1 U	12.5 UJ	10.8 U	10.1 U
Pyrene	-	1100	10 U	42.1 U	12.5 UJ	10.8 U	10.1 U

^a Protective of tap water ingestion by a resident.^b Values based on naphthalene as a surrogate chemical.^c Values based on pyrene as a surrogate chemical.

Bold values indicate results exceeding Federal Safe Drinking Water Act Maximum Contaminant Levels.
 Underlined values indicate results exceeding risk-based screening levels.

U Indicates that the compound was not detected above the reported sample quantitation limit.

J Indicates that the value for the compound was an estimated value.

UJ Indicates that the sample was not detected above an approximate sample quantitation limit.

R Indicates that the sample results are unusable and the presence or absence of the compound could not be verified.

= Indicates that the compound was detected at the concentration reported.

Table C-2. Comparison of Fort Stewart CAP-Part A UST 28B Groundwater Results to Screening Levels (continued)

Station: Sample ID: Sample Interval (ft): Collection Date: Units:	Screening Levels		60-06 600612 0.0 - 10.0 18-Sep-98 (ug/L)	60-07 600712 6.0 - 10.0 20-Sep-98 (ug/L)	60-07 600722 11.0 - 15.0 20-Sep-98 (ug/L)	60-07 600732 16.0 - 20.0 20-Sep-98 (ug/L)
	Federal SDWA MCLs (ug/L)	Risk-based ^a (ug/L)				
VOLATILE ORGANIC COMPOUNDS						
Benzene	5	0.36	2 <u>U</u>	2 <u>U</u>	2 <u>U</u>	2 <u>U</u>
Toluene	1000	750	2 <u>U</u>	2 <u>U</u>	2 <u>U</u>	2 <u>U</u>
Ethylbenzene	700	1300	2 <u>U</u>	2 <u>U</u>	2 <u>U</u>	2 <u>U</u>
Xylenes, Total	10000	12000	6 <u>U</u>	6 <u>U</u>	6 <u>U</u>	6 <u>U</u>
POLYNUCLEAR AROMATIC HYDROCARBONS						
2-Chloronaphthalene ^b	-	1500	10 <u>U</u>	10.4 <u>U</u>	10.3 <u>U</u>	10.4 <u>U</u>
Acenaphthene	-	2200	10 <u>U</u>	10.4 <u>U</u>	10.3 <u>U</u>	10.4 <u>U</u>
Acenaphthylene	-	1100	10 <u>U</u>	10.4 <u>U</u>	10.3 <u>U</u>	10.4 <u>U</u>
Anthracene	-	11000	10 <u>U</u>	10.4 <u>U</u>	10.3 <u>U</u>	10.4 <u>U</u>
Benzo(a)anthracene	-	0.092	10 <u>U</u>	10.4 <u>U</u>	10.3 <u>U</u>	10.4 <u>U</u>
Benzo(a)pyrene	0.2	0.0092	10 <u>U</u>	10.4 <u>U</u>	10.3 <u>U</u>	10.4 <u>U</u>
Benzo(b)fluoranthene	-	0.092	10 <u>U</u>	10.4 <u>U</u>	10.3 <u>U</u>	10.4 <u>U</u>
Benzo(g,h,i)perylene	-	-	10 <u>U</u>	10.4 <u>U</u>	10.3 <u>U</u>	10.4 <u>U</u>
Benzo(k)fluoranthene	-	0.92	10 <u>U</u>	10.4 <u>U</u>	10.3 <u>U</u>	10.4 <u>U</u>
Chrysene	-	9.2	10 <u>U</u>	10.4 <u>U</u>	10.3 <u>U</u>	10.4 <u>U</u>
Dibenzo(a,h)anthracene	-	0.0092	10 <u>U</u>	10.4 <u>U</u>	10.3 <u>U</u>	10.4 <u>U</u>
Fluoranthene	-	1500	10 <u>U</u>	10.4 <u>U</u>	10.3 <u>U</u>	10.4 <u>U</u>
Fluorene	-	1500	10 <u>U</u>	10.4 <u>U</u>	10.3 <u>U</u>	10.4 <u>U</u>
Indeno(1,2,3-cd)pyrene	-	0.092	10 <u>U</u>	10.4 <u>U</u>	10.3 <u>U</u>	10.4 <u>U</u>
Naphthalene	-	1500	10 <u>U</u>	10.4 <u>U</u>	10.3 <u>U</u>	10.4 <u>U</u>
Phenanthrene ^c	-	1100	10 <u>U</u>	10.4 <u>U</u>	10.3 <u>U</u>	10.4 <u>U</u>
Pyrene	-	1100	10 <u>U</u>	10.4 <u>U</u>	10.3 <u>U</u>	10.4 <u>U</u>

^a Protective of tap water ingestion by a resident.

^b Values based on naphthalene as a surrogate chemical.

^c Values based on pyrene as a surrogate chemical.

Bold values indicate results exceeding Federal Safe Drinking Water Act Maximum Contaminant Levels.

Underlined values indicate results exceeding risk-based screening levels.

U Indicates that the compound was not detected above the reported sample quantitation limit.

J Indicates that the value for the compound was an estimated value.

UJ Indicates that the sample was not detected above an approximate sample quantitation limit.

R Indicates that the sample results are unusable and the presence or absence of the compound could not be verified.

= Indicates that the compound was detected at the concentration reported.

Table C-3. Summary of Geotechnical Results for the UST 28B Site

Site	UST 28B
Boring	60-08
Sample ID	600831
Sample Depth Interval (ft BGS)	4.0 – 6.0
Grain Size Analysis - % Fines	25
Grain Size Analysis - % Sand	68
Grain Size Analysis - % Gravel	7
Liquid Limit	NP
Plastic Limit	NP
Plasticity Index	NP
Moisture Content (%)	14.9
Permeability	3.59×10^{-5}
Porosity	0.35
Specific Gravity	2.65
NP = nonplastic	

Table C-4. Natural Attenuation Modeling Results for UST 28B

Distance from the source (ft)	Distance from the source (m)	Predicted Maximum Conc. In Groundwater ($\mu\text{g/L}$)
0.0	0.0	171
3.3	1.0	130
6.6	2.0	96.6
9.8	3.0	71.6
13.1	4.0	53.1
16.4	5.0	39.5
19.7	6.0	29.4
23.0	7.0	21.9
26.2	8.0	16.4
29.5	9.0	12.3
32.8	10.0	9.26
39.4	12.0	5.28
49.2	15.0	2.32
65.6	20.0	0.61
82.0	25.0	0.17
98.4	30.0	0.046
124.7	38.0	0.006
250.0	76.2	0
3000.0	914.4	0